

CONTRACT NO. 60004

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
305	2007-028 RS	COOK	35	4
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		I000	TRAFFIC SIGNALS Y031-1F	SFTY-2A 016-0535			
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	611		611				
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1655		1655				
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	685		685				
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	4517		4517				
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	32.5		32.5				
87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	2		2				
88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	4		4				
88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	2		2				
88030210	SIGNAL HEAD, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2		2				
88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	2		2				
88102710	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED	EACH	4		4				
88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	2		2				
88500100	INDUCTIVE LOOP DETECTOR	EACH	13		13				
88600100	DETECTOR LOOP, TYPE I	FOOT	454		454				
88600600	DETECTOR LOOP REPLACEMENT	FOOT	660		660				
88800100	PEDESTRIAN PUSH-BUTTON	EACH	4		4				
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1		1				
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	302.5	302.5					
X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SO FT	286.4			286.4			
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SO FT	329.7			329.7			
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1215	1215					
X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	1		1				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		I000	TRAFFIC SIGNALS Y031-1F	SFTY-2A 016-0535			
* X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	18		18				
* XX006661	UNINTERRUPTABLE POWER SUPPLY	EACH	1		1				
* 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1		1				
* X8730320	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 20 3/C, TWISTED, SHIELDED	FOOT	50		50				
* 87502520	TRAFFIC SIGNAL POST, GALVANIZED STEEL 18 FT.	EACH	1		1				
* XX001287	LIGHT DETECTOR, TYPE 1	EACH	2		2				
* 88700300	LIGHT DETECTOR AMPLIFIER	EACH	1		1				

2/7/2008 2:48:23 PM C:\PROJECTS\60004\2007\8050015.DWG

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

Rev. *SPECIALTY ITEMS

PLOT DATE: 2/7/2008