

SUMMARY OF QUANTITIES				TOTAL QUANTITY	CONSTRUCTION TYPE CODE URBAN ROADWAY 1000-2A
CODE NO.	DESCRIPTION	UNIT			
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	110	110	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	94	94	
20400800	FURNISHED EXCAVATION	CU YD	209	209	
21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	450	450	
25000210	SEEDING, CLASS 2A	ACRE	0.1	0.1	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	9	9	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	9	9	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	9	9	
25100630	EROSION CONTROL BLANKET	SQ YD	450	450	
28000400	PERIMETER EROSION BARRIER	FOOT	700	700	
40300200	BITUMINOUS MATERIALS (PRIME COAT)	TON	15	15	
40600300	AGGREGATE (PRIME COAT)	TON	60	60	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	20	20	
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	280	280	
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	650	650	
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	55	55	
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	1825	1825	
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	18,100	18,100	
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	352	352	
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	170	170	
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	3290	3290	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	6220	6220	
48101498	AGGREGATE SHOULDERS, TYPE B 4"	SQ YD	3500	3500	
60255800	MANHOLE TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1	
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	625	625	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	8	8	
63200310	GUARDRAIL REMOVAL	FOOT	821	821	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1100	1100	
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	1100	1100	
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	21900	21900	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	400	400	

SUMMARY OF QUANTITIES				TOTAL QUANTITY	CONSTRUCTION TYPE CODE URBAN ROADWAY 1000-2A
CODE NO.	DESCRIPTION	UNIT			
* 72000100	SIGN PANEL - TYPE 1	SQ FT	43	43	
* 72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	5	5	
* 72900100	METAL POST - TYPE A	FOOT	42	42	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	20,500	20,500	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	22	22	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	340	340	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	8	8	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	168	168	
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52	
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	800	800	
Z0064800	SELECTIVE CLEARING	UNIT	10	10	

20101300 TREE PRUNING (1 TO 10 INCH DIAMETER) EACH 10 10
 20101350 TREE PRUNING (OVER 10 INCH DIAMETER) EACH 20 20
 44002212 HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3" SQ YD 3820 3820
 70102625 TRAFFIC CONTROL AND PROTECTION, STANDARD 701606 L SUM 1 1
 K1004595 PRUNING FOR SAFETY AND EQUIPMENT CLEARANCE L SUM 1 1

* SPECIALTY ITEMS

FILE NAME = N:\PROJ\3329\3329_20\Design\Propose\Plan\3329_20-500.dwt



Ciorba Group, Inc.
CONSULTING ENGINEERS
5507 North Cumberland Avenue, Suite 402
Chicago, Illinois 60656
Tel. 773.775.4009 Fax 773.775.4014

USER NAME = wloicester	DESIGNED - WBL	REVISED -
	DRAWN - WBL	REVISED -
PLOT SCALE = 0.9799' / IN.	CHECKED - MJL	REVISED -
PLOT DATE = 2/15/2008	DATE - 1/18/2008	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FAU 2697 (FLAVIN ROAD) IL 171 (ARCHER AVE.) TO 95TH ST. SUMMARY OF QUANTITIES			
SCALE: NO SCALE	SHEET NO. OF SHEETS	STA. TO STA.	

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2697	2007-051 Q	COOK	29	3
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 60D43	

Rev.