

EARTHWORK SCHEDULE								
STATION			20200100		20201200			20400800
			EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	FURNISHED EXCAVATION
LINE "FLAVIN"			(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)
137+25.00	TO	137+50.00	0	0	2	1	-1	1
137+50.00	TO	137+75.00	0	0	7	11	-11	11
137+75.00	TO	138+00.00	0	0	12	21	-21	21
138+00.00	TO	138+25.00	0	0	12	22	-22	22
138+25.00	TO	138+50.00	0	0	13	27	-27	27
138+50.00	TO	138+75.00	0	0	15	41	-41	41
138+75.00	TO	139+00.00	0	0	16	50	-50	50
139+00.00	TO	139+25.00	0	0	13	30	-30	30
139+25.00	TO	139+50.00	0	0	6	7	-7	7
139+50.00	TO	139+75.00	0	0	1	1	-1	1
TOTALS			0	0	94	209	-209	209

SUMMARY	
20201200	20400800
REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	FURNISHED EXCAVATION
(CU YD)	(CU YD)
94	209

FILE NAME = m:\proj\3293\3293_20\design\ProposedPlan\3293_20-FW_TABLE.dwg



Ciorba Group, Inc.
CONSULTING ENGINEERS
5607 North Cumberland Avenue, Suite 402
Chicago, Illinois 60656
Tel. 773.775.4009 Fax 773.775.4014

USER NAME = wlancaster	DESIGNED - WBL	REVISED -
PLOT SCALE = 1:8000' / 1" IN.	DRAWN - WBL	REVISED -
PLOT DATE = 2/15/2008	CHECKED - MJL	REVISED -
	DATE - 1/18/2008	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**FAU 2697 (FLAVIN ROAD)
IL 171 (ARCHER AVE.) TO 95TH ST.
EARTHWORK SCHEDULE**

SCALE: NO SCALE SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2697	2007-051 0	COOK	29	5
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 60D43	