

CONTRACT 60D92

SUMMARY OF QUANTITIES			URBAN 100% STATE CONSTRUCTION TYPE CODE SFTY-2A					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	SN 056-0012				
50300300	PROTECTIVE COAT	SO YD	29.1	29.1				
50301200	CONCRETE WEARING SURFACE	SO YD	29.1	29.1				
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SO FT	192	192				
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	610	610				
67000400	ENGINEERS FIELD OFFICE, TYPE A	CAL MO	3	3				
67100100	MOBILIZATION	L SUM	1	1				
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1				
70400100	TEMPORARY CONCRETE BARRIER	FOOT	362.5	362.5				
*78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	1169	1169				
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1	1				
80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1	1				
*81100200	CONDUIT ATTACHED TO STRUCTURE, 3/4" DIA., GALVANIZED STEEL	FOOT	200	200				
*81700120	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYP RHW) 1/C#6	FOOT	250	250				
*81800320	AERIAL CABLE, 3-1/C#4 WITH MESSENGER WIRE	FOOT	1450	1450				
*82103400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTOCELL CONTROL, 400 WATT	EACH	6	6				
*83057355	LIGHT POLE, WOOD, 60 FOOT, CLASS 4, WITH 15FT MAST ARM	EACH	6	6				
X0320047	REMOVAL OF EXISTING PRECAST PRESTRESSED CONCRETE DECK BEAMS	SO FT	196	196				
*X0321781	MECHANICAL SPLICE	EACH	129	129				
X0322467	TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE	SO FT	48	48				
X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	6	6				
X5030275	CONCRETE WEARING SURFACE REMOVAL	SO YD	7.3	7.3				
X8900005	TEMPORARY BRIDGE TRAFFIC SIGNAL INSTALLATION	EACH	1	1				
*XX006937	GROUND ROD, 5/8" DIA. X 10 FT.	EACH	3	3				
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON - REDIRECTIVE), TEST LEVEL 3	EACH	2	2				

SUMMARY OF QUANTITIES			URBAN 100% STATE CONSTRUCTION TYPE CODE SFTY-2A					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	SN 056-0012				
X0325949	ELECTRIC SERVICE DISCONNECT, LIGHTING AND TRAFFIC SIGNAL	EACH	1	1				
X0325948	TEMPORARY LIGHTING SYSTEM REMOVAL, NO SALVAGE	L SUM	1	1				
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	1280	1280				
70300560	PAVEMENT MARKING TAPE, TYPE III 12"	FOOT	24	24				
*78200200	BIDIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	20	20				
78300100	PAVEMENT MARKING REMOVAL	SR FT	715	715				

*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

Rev.

3/7/2008 10:41:12 AM C:\Users\jason\Documents\60D92\SUMMARY OF QUANTITIES.DWG