

CODE NO.	PAY ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODES														
				80% FEDERAL/20% STATE						80% FED/13.34% STATE/6.66% PROSPECT HTS.	80% FED/13.34% STATE/3.33% PROSPECT HTS./3.33% MT. PROSPECT	100% PROSPECT HTS. FIRE PROTECTION DISTRICT	100% MT. PROSPECT	50% STATE/50% GLENVIEW	50% STATE/50% PROSPECT HTS.	100% GLENVIEW		
				NHF ROADWAY	BRF BRIDGE IL 21 OVER DES PLAINES RIVER	NHF				NHF TRAFFIC SIGNALS IL 21/APPLE DRIVE	NHF TRAFFIC SIGNALS US 45/SEMINOLE LANE	NHF TRAFFIC SIGNALS EVP EQUIPMENT IL 21/APPLE DRIVE	NHF TRAFFIC SIGNALS EVP EQUIPMENT IL 21/US 45	NHF TRAFFIC SIGNALS EVP EQUIPMENT US 45/SEMINOLE LANE	NHF NEW SIDEWALK	NHF STORM SEWER	NHF NEW SIDEWALK	NHF WATERMAIN
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	598	J000-2A 598	X071-2A	Y030-1E	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-3D	Y031-3D	Y031-3D	SFTY-1B	Y060	SFTY-1B	Y060
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	209	209														
20101000	TEMPORARY FENCE	FOOT	4,014	4,014														
20101100	TREE TRUNK PROTECTION	EACH	22	22														
20200100	EARTH EXCAVATION	CU YD	11,005	11,005														
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	23,365	23,365														
20400800	FURNISHED EXCAVATION	CU YD	30,030	30,030														
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	210		210													
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	11,485	11,485														
20800150	TRENCH BACKFILL	CU YD	4,520	4,520														
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	28,617	28,617														
21101645	TOPSOIL FURNISH AND PLACE, 12"	SQ YD	141	141														
21101805	COMPOST FURNISH AND PLACE, 2"	SQ YD	6,050	6,050														
21101825	COMPOST FURNISH AND PLACE, 6"	SQ YD	2,002	2,002														
25000210	SEEDING, CLASS 2A	ACRE	3.50	3.50														
25000310	SEEDING, CLASS 4	ACRE	1.25	1.25														
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	428	428														
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	428	428														
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	428	428														
25100115	MULCH, METHOD 2	ACRE	4.75	4.75														
25100630	EROSION CONTROL BLANKET	SQ YD	7,173	7,173														
25200110	SODDING, SALT TOLERANT	SQ YD	6,706	6,706														
25200200	SUPPLEMENTAL WATERING	UNIT	101	101														
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	3,068	3,068														
28000300	TEMPORARY DITCH CHECKS	EACH	1	1														
28000400	PERIMETER EROSION BARRIER	FOOT	7,858	7,858														
28000500	INLET AND PIPE PROTECTION	EACH	27	27														
28000510	INLET FILTERS	EACH	165	165														
28100107	STONE RIPRAP, CLASS A4	SQ YD	1,160		1,160													
28200200	FILTER FABRIC	SQ YD	1,350		1,350													
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	848	848														
35101100	AGGREGATE BASE COURSE, TYPE A 12"	SQ YD	1,369	1,369														
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	99	99														
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	1,224	1,224														
35600900	HOT-MIX ASPHALT BASE COURSE WIDENING	TON	92.5	92.5														

○ NON-PARTICIPATING

* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES - 1

SCALE: NTS
DATE: 02/05/08

DRAWN BY: RDT
CHECKED BY: GC

