

CODE NO.	PAY ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODES															
				80% FEDERAL/20% STATE		80% FED/13.34% STATE/6.66% PROSPECT HTS.		80% FED/13.34% STATE/3.33% PROSPECT HTS./3.33% MT. PROSPECT		100% PROSPECT HTS. FIRE PROTECTION DISTRICT		100% MT. PROSPECT		50% STATE/50% GLENVIEW		50% STATE/50% PROSPECT HTS.		100% GLENVIEW	
				NHF	BRF	NHF	NHF	NHF	NHF	NHF	NHF	NHF	NHF	NHF	NHF	NHF	NHF	NHF	NHF
				ROADWAY	BRIDGE IL 21 OVER DES PLAINES RIVER	LIGHTING	TRAFFIC SIGNALS INTERCONNECT	TRAFFIC SIGNALS IL 21/US 45	TRAFFIC SIGNALS IL 21/SANDERS RD	TRAFFIC SIGNALS IL 21/APPLE DRIVE	TRAFFIC SIGNALS US 45/ SEMINOLE LANE	TRAFFIC SIGNALS EVP EQUIPMENT IL 21/APPLE DRIVE	TRAFFIC SIGNALS EVP EQUIPMENT IL 21/US 45	TRAFFIC SIGNALS EVP EQUIPMENT US 45/SEMINOLE LANE	NEW SIDEWALK	STORM SEWER	NEW SIDEWALK	WATERMAIN	
				J000-2A	X071-2A	Y030-1E	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-3D	Y031-3D	Y031-3D	SFTY-1B	Y060	SFTY-1B	Y060	
* 78008340	POLYUREA PAVEMENT MARKING TYPE II - LINE 8"	FOOT	764	764															
* 78008350	POLYUREA PAVEMENT MARKING TYPE II - LINE 12"	FOOT	906	906															
* 78008370	POLYUREA PAVEMENT MARKING TYPE II - LINE 24"	FOOT	292	292															
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	959	959															
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	22	22															
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2															
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	16	16															
* 78300100	PAVEMENT MARKING REMOVAL	SQ FT	2,120	2,120															
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	253	253															
* 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	3,195				873	1,252	130	448	492								
* 81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	584					400		100	84								
* 81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	5					5											
* 81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	372					126	78	120	48								
* 81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	90			90													
* 81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	659				534			35	90								
* 81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	593			593													
* 81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	802					311	66	192	233								
* 81400100	HANDHOLE	EACH	26				2	8	2	7	7								
* 81400200	HEAVY-DUTY HANDHOLE	EACH	2					1			1								
* 81400300	DOUBLE HANDHOLE	EACH	4					2		1	1								
* 81603210	UNIT DUCT, 600V, 3-1C NO.4, 1/C NO.6 GROUND, (EPR-TYPE RHW), 1 1/4" DIA. POLYETHYLENE	FOOT	3,804			3804													
* 81700355	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 3-1/C NO. 2	FOOT	180			180													
* 81800300	AERIAL CABLE, 3-1/C NO. 2 WITH MESSENGER WIRE	FOOT	4,639			4639													
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	7,274			3230	873	1,585	208	750	628								
* 82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	44			44													
* 82103400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 400 WATT	EACH	10			10													
* 83050810	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 15 FT. MAST ARM	EACH	18			18													
* 83050910	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 2-15 FT. MAST ARMS	EACH	4			4													
* 83057220	LIGHT POLE, WOOD, 40 FOOT, CLASS 4	EACH	1			1													
* 83057225	LIGHT POLE, WOOD, 40 FOOT, CLASS 4, WITH 15FT MAST ARM	EACH	2			2													
* 83057340	LIGHT POLE, WOOD, 60 FOOT, CLASS 3	EACH	2			2													
* 83057345	LIGHT POLE, WOOD, 60 FOOT, CLASS 3, WITH 15FT MAST ARM	EACH	24			24													
* 83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	206			206													
* 83800505	BREAKAWAY DEVICE, COUPLING, WITH ALUMINUM SKIRT	EACH	22			22													
* 84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	20			20													
* 84200705	LIGHTING FOUNDATION REMOVAL, PARTIAL	EACH	16			16													
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1				1												

○ NON-PARTICIPATING
* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES - 6



SCALE: NTS
DATE: 02/05/08
DRAWN BY: RDT
CHECKED BY: GC

... \c:\p1\m\stc\62387\sum_06.dgn 3/7/2008 11:03:31 AM