| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 374 | 3268F-R-1 | COOK | 279 | 11 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |

CONTRACT NO. 62387

| | CODE NO. | PAY ITEM | UNIT | URBAN TOTAL QUANTITY | CONSTRUCTION TYPE CODES | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | 80% FEDERAL/20% STATE | | | | | | 80% FED/13.34% STATE/6.66% PROSPECT HTS. | 80% FED/13.34% STATE/3.33% PROSPECT HTS./3.33% MT. PROSPECT | 100% PROSPECT HTS. FIRE PROTECTION DISTRICT | | 100% MT. PROSPECT | 50% STATE/50% GLENVIEW | | 50% STATE/50% PROSPECT HTS. | 100% GLENVIEW |
| | | | | | NHF | BRF | NHF | | | | NHF | NHF | | | | | | | |
| | | | | | ROADWAY | BRIDGE IL 21 OVER DES PLAINES RIVER | LIGHTING | TRAFFIC SIGNALS INTERCONNECT | TRAFFIC SIGNALS IL 21/US 45 | TRAFFIC SIGNALS IL 21/SANDERS RD | TRAFFIC SIGNALS IL 21/APPLE DRIVE | TRAFFIC SIGNALS US 45/ SEMINOLE LANE | TRAFFIC SIGNALS EVP EQUIPMENT IL 21/APPLE DRIVE | TRAFFIC SIGNALS EVP EQUIPMENT IL 21/US 45 | TRAFFIC SIGNALS EVP EQUIPMENT US 45/SEMINOLE LANE | NEW SIDEWALK | STORM SEWER | NEW SIDEWALK | WATERMAIN |
| | | | | | J000-2A | X071-2A | Y030-1E | Y031-1F | Y031-1F | Y031-1F | Y031-1F | Y031-1F | Y031-3D | Y031-3D | Y031-3D | SFTY-1B | Y060 | SFTY-1B | Y060 |
| * | 89502375 | REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT | EACH | 3 | | | 1 | | | 1 | 1 | 1 | | | | | | | |
| * | 89502380 | REMOVE EXISTING HANDHOLE | EACH | 29 | | | | | 12 | 2 | 7 | 8 | | | | | | | |
| * | 89502385 | REMOVE EXISTING CONCRETE FOUNDATION | EACH | 22 | | | | | 9 | | 7 | 6 | | | | | | | |
| | Z0001050 | AGGREGATE SUBGRADE 12" | SQ YD | 63,071 | 63,071 | | | | | | | | | | | | | | |
| | Z0013798 | CONSTRUCTION LAYOUT | L SUM | 1 | 1 | | | | | | | | | | | | | | |
| ○ | Z0018500 | DRAINAGE STRUCTURES TO BE CLEANED | EACH | 10 | 10 | | | | | | | | | | | | | | |
| | Z0018900 | DRILL AND GROUT DOWEL BARS | EACH | 922 | 922 | | | | | | | | | | | | | | |
| | Z0022800 | FENCE REMOVAL | FOOT | 1,284 | 1,284 | | | | | | | | | | | | | | |
| | Z0030250 | IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3 | EACH | 3 | 3 | | | | | | | | | | | | | | |
| | Z0030350 | IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3 | EACH | 3 | 3 | | | | | | | | | | | | | | |
| ● | Z0076600 | TRAINEES | HOUR | 3500 | 3500 | | | | | | | | | | | | | | |
| * | B2006116 | TREE, SYRINGA PEKINENSIS MORTON (CHINA SNOW PEKING LILAC), 2" CALIPER, TREE FORM, BALLED AND BURLAP | EACH | 5 | 5 | | | | | | | | | | | | | | |
| | XX001047 | VALVE VAULTS TO BE ABANDONED | EACH | 3 | | | | | | | | | | | | | | | 3 |
| | XX001446 | PLUG AND BLOCK WATER MAIN | EACH | 6 | | | | | | | | | | | | | | | 6 |
| * | XX003418 | ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 4, 2/C | FOOT | 595 | | | | | 595 | | | | | | | | | | |
| | XX003516 | CONNECTIONS TO EXISTING WATER MAINS (NON-PRESSURE) - 8" | EACH | 1 | | | | | | | | | | | | | | | 1 |
| | XX004907 | GATE VALVE 12" WITH VAULT, 5' DIAMETER | EACH | 2 | | | | | | | | | | | | | | | 2 |
| | XX005628 | TREE, QUERCUS IMBRICARIA, (SHINGLE OAK) 2 1/2" CALIPER,BALLED AND BURLAPPED | EACH | 12 | 12 | | | | | | | | | | | | | | |
| | XX006088 | GATE VALVE WITH BOX 12" | EACH | 1 | | | | | | | | | | | | | | | 1 |
| | XX006241 | GATE VALVE AND BOX 8" | EACH | 1 | | | | | | | | | | | | | | | 1 |
| * | XX006937 | GROUND ROD, 5/8" DIA. X 10 FT. | EACH | 52 | | | 52 | | | | | | | | | | | | |
| | X0321100 | GEOTEXTILE RETAINING WALL | SQ FT | 6,175 | 6,175 | | | | | | | | | | | | | | |
| | X0322033 | STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH | FOOT | 340.5 | | | | | | | | | | | | | 340.5 | | |
| | X0322034 | STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH | FOOT | 126.0 | | | | | | | | | | | | | 126.0 | | |
| | X0322035 | STORM SEWER (WATER MAIN REQUIREMENTS) 18 INCH | FOOT | 337.5 | | | | | | | | | | | | | 337.5 | | |
| | X0322092 | STORM SEWER (WATER MAIN REQUIREMENTS) 48 INCH | FOOT | 80.0 | | | | | | | | | | | | | 80.0 | | |
| | X0322125 | STORM SEWER (WATER MAIN REQUIREMENTS) 24 INCH | FOOT | 250.0 | | | | | | | | | | | | | 250.0 | | |
| | X0322127 | STORM SEWER (WATER MAIN REQUIREMENTS) 30 INCH | FOOT | 285.0 | | | | | | | | | | | | | 285.0 | | |
| | X0322141 | REMOVE TEMPORARY WOOD POLE | EACH | 28 | | | 28 | | | | | | | | | | | | |
| | X0322256 | TEMPORARY INFORMATION SIGNING | SQ FT | 301.5 | 301.5 | | | | | | | | | | | | | | |
| | X0322525 | STORM SEWER (WATER MAIN REQUIREMENTS) 21 INCH | FOOT | 200.0 | | | | | | | | | | | | | 200.0 | | |
| | X0322642 | STORM SEWER (WATER MAIN REQUIREMENTS) 54 INCH | FOOT | 378.0 | | | | | | | | | | | | | 378.0 | | |
| * | X0322925 | ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C | FOOT | 2,828 | | | | 2,828 | | | | | | | | | | | |
| * | X0323003 | TEMPORARY ELECTRIC SERVICE INSTALLATION | EACH | 2 | | | 2 | | | | | | | | | | | | |
| * | X0323574 | MAINTENANCE OF LIGHTING SYSTEM | CAL MO | 12 | | | 12 | | | | | | | | | | | | |
| * | X0323670 | PREFORMED DETECTOR LOOP | FOOT | 826 | | | | | 383 | 79 | 298 | 66 | | | | | | | |
| | X0323829 | WATER MAIN TO BE ABANDONED, 12" | FOOT | 1,700 | | | | | | | | | | | | | | | 1,700 |

○ NON-PARTICIPATING

* SPECIALTY ITEM

| REVISIONS | |
|---|---|
| NAME | DATE |

STV Incorporated
engineers/architects/scientists/construction managers
200 W Monroe - Suite 1650
Chicago, Illinois 60606

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES - 8

SCALE: NTS
DATE 02/05/08

DRAWN BY RDT
CHECKED BY GC