

TEMPORARY PAVEMENT

LOCATION	AREA - STAGE I (SQ. YD.)	AREA - STAGE II (SQ. YD.)	AREA - POST STAGE II (SQ. YD.)
IL ROUTE 21			
101+55.37 TO 103+13.38		163	
101+61.58 TO 103+13.38			90
103+71.21 TO 106+46.86	498		
110+56.92 TO 114+44.17	261		
113+00.00 TO 116+01.00		1,119	
138+76.18 TO 146+15.00	467		
156+00.00 TO 161+00.00	383		
161+00.00 TO 168+51.00	527		
179+00.00 TO 179+80.00		35	
181+24.53 TO 185+06.54	176		
EXISTING US ROUTE 45			
19+05.45 TO 22+00.00	547		
PROPOSED US ROUTE 45			
303+43.33 TO 304+84.00		194	

BITUMINOUS CONCRETE PAVEMENT
(FULL-DEPTH) SUPERPAVE, 9 1/2"

2,859	1,511	90
SQ. YD.	SQ. YD.	SQ. YD.

TOTAL = 4,460
SQ. YD.

STUMP REMOVAL ONLY
UNIT=1 INCH

LOCATION	SIZE (INCH)	UNIT
IL ROUTE 21		
STA. 131+84.38	44.59 RT.	20
STA. 159+55.52	23.91 LT.	12
STA. 159+67.85	23.07 LT.	12
STA. 159+70.81	25.57 LT.	12
STA. 159+80.78	28.38 LT.	10
STA. 160+25.92	39.75 LT.	20
STA. 160+49.09	40.86 RT.	6
STA. 160+61.02	30.82 LT.	20
STA. 161+23.70	24.55 LT.	20
STA. 161+45.62	29.59 LT.	20
STA. 161+88.18	41.72 LT.	10
STA. 161+99.94	41.10 LT.	6
STA. 163+30.95	43.92 LT.	9
STA. 163+39.82	41.69 LT.	8
STA. 163+61.74	42.65 LT.	15
STA. 164+06.60	42.58 LT.	15
STA. 164+47.71	51.22 LT.	7
STA. 164+56.10	46.35 LT.	7
STA. 166+78.75	42.04 RT.	18
STA. 174+38.69	40.51 LT.	8
STA. 174+47.37	43.21 LT.	9
EXISTING US ROUTE 45		
STA. 24+04.61	40.95 LT.	11
STA. 24+09.00	41.15 LT.	11
STA. 24+12.55	41.22 LT.	13
STA. 24+16.32	41.47 LT.	13
STA. 24+21.28	41.19 LT.	11
STA. 24+26.85	41.62 LT.	12
STA. 24+30.84	42.21 LT.	13
6 INCHES TO 15 INCHES		5,111
GREATER THAN 15 INCHES		1,892

STUMP REMOVAL ONLY, TOTAL = 7,351

AGGREGATE SUBGRADE 12"

LOCATION	AREA (SQ. YD.)
IL ROUTE 21	
105+50.00 TO 116+00.00	9,452
116+00.00 TO 129+00.00	11,679
129+00.00 TO 129+70.94	545
131+94.05 TO 142+00.00	8,401
142+00.00 TO 155+00.00	9,991
155+00.00 TO 168+00.00	9,991
168+00.00 TO 178+00.00	7,685
US ROUTE 45	
300+00.00 TO 305+00.00	3,895
PROPOSED ACCESS ROAD	
10+06.87 TO 13+47.41	1,432

AGGREGATE SUBGRADE, 12", TOTAL = 63,071
SQ. YD.

DRILL AND GROUT DOWEL BARS

LOCATION	EACH
IL ROUTE 21	
101+53.50 TO 103+09.34	160
103+74.47 TO 105+50.00	176
178+10.00 TO 180+14.70	204
181+24.03 TO 185+06.28	382

DRILL AND GROUT DOWEL BARS, TOTAL = 922
EACH

FENCE REMOVAL

LOCATION	LENGTH (FEET)
IL ROUTE 21	
138+83.24 TO 140+82.50	198
143+07.22 TO 144+73.91	172
156+62.67 TO 157+26.87	66
158+51.66 TO 159+04.25	54
159+24.25 TO 160+46.03	122
159+63.08 TO 160+35.40	72
159+88.26 TO 162+30.07	285
161+49.58 TO 162+09.25	60
170+50.22 TO 170+53.23	6
172+47.00 TO 173+04.06	57
173+34.82 TO 175+27.17	192

FENCE REMOVAL, TOTAL = 1,284
FEET

DRAINAGE STRUCTURES TO BE CLEANED

LOCATION	EACH
IL 21	
104+30.38	45.30 RT 1
104+76.33	6.54 RT 1
104+90.38	5.30 LT 1
104+94.29	43.47 LT 1
106+21.94	69.51 RT 1
107+31.27	64.56 RT 1
114+27.71	49.31 RT 1
114+39.94	57.84 RT 1
143+87.28	58.59 RT 1
164+12.24	75.30 RT 1

DRAINAGE STRUCTURES TO BE CLEANED, TOTAL = 10
EACH

BOX CULVERT REMOVAL

LOCATION	LENGTH (FEET)	DIRECTION
IL 21		
164+43.50	57	E/W

BOX CULVERTS REMOVAL, TOTAL = 57
FEET

TEMPORARY FENCE

LOCATION	LENGTH (FEET)
IL ROUTE 21	
111+84.00 TO 113+09.00	LT 125
117+80.00 TO 130+30.00	LT 1,250
119+45.00 TO 130+30.00	RT 1085
131+30.00 TO 141+00.00	RT 970
EXISTING US ROUTE 45	
22+00.00 TO 27+00.00	LT 584

TEMPORARY FENCE, TOTAL = 4,014
FEET

TEMPORARY INFORMATION SIGNING

LOCATION	AREA (SQ. FT)
IL ROUTE 21 STAGE I	
DISTRICT 1 STANDARD TC-22	51.4
105+61.00	RT 6.3
109+14.00	RT 6.3
110+43.00	RT 6.3
112+00.00	RT 6.3
112+52.00	RT 6.3
113+38.00	RT 6.3
143+50.00	RT 12.5
153+24.00	RT 12.5
157+28.00	RT 12.5
161+18.00	RT 6.3
165+10.00	RT 12.5
169+80.00	RT 12.5
171+14.00	RT 12.5
172+18.00	RT 12.5
172+89.00	RT 12.5
176+82.00	RT 6.3
IL ROUTE 21 STAGE II	
136+33.00	LT 12.5
141+21.00	LT 12.5
143+22.00	LT 12.5
152+18.00	LT 12.5
165+85.00	LT 12.5
170+20.00	LT 6.3
172+62.00	LT 12.5
175+70.00	LT 12.5
ACCESS ROAD STAGE II	
11+97.00	LT 6.3

TEMPORARY INFORMATION SIGNING, TOTAL = 301.5
SQ. FT.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES - 8