F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
374	3268F-R-1	COOK	279	69
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 62387

DRAINAGE STRUCTURE SCHEDULE

NO	STRUCTURE TYPE				DIA (FT)	FRAME & GRATE	GRATING FOR FES	PR.RIM ELEV.	PROPOSED INVERT ELEVATION				STATION	OFFSET (FT)
	CB TYPE	MH TYPE	INLET TYPE	FES					N	S	W	E		
1	C				2	24		639.85		636.21			105+50	39.4 LT
2	A				4	24		639.07	635.87			635.77	106+20	44.0 RT
3		A			4	1 (CLOSED)		639.79			635.57	635.07	106+30	CL
4	A				4	24		639.26	635.16		634.86	634.66	106+40	39.5 LT
5	C				2	24		640.34		635.55			105+50	44.0 RT
6		A			4	1 (CLOSED)		639.70		634.50	634.60		106+40	47.6 LT
7		A			5	1 (CLOSED)		639.50	634.07	632.57	633.36		107+30	47.7 LT
8		A			5	1 (CLOSED)		639.66	632.24	632.04	634.08		108+00	48.0 LT
9		A			5	1 (CLOSED)		639.42	631.52	631.32	633.90		109+10	48.0 LT
10		A			5	1 (CLOSED)		638.99	630.80	630.60	633.53		110+20	46.9 LT
11		A			5	1 (CLOSED)		638.66	630.08	629.88	633.20		111+30	46.7 LT
**Closure 9									629.54				111+93.37	
**Closure 8											628.35		114+59.62	
12	A				4	24		637.77			633.43	633.43	112+00	43.5 RT
12A		A			4	1 (CLOSED)		639.03		631.45	633.22	633.22	112+02.47	CL
13	A				4	24		638.94			633.38	633.38	107+30	39.1 LT
14	A				5	24		638.94				633.80	107+30	44.0 RT
15	A				4	24		639.10			634.10	634.10	108+00	39.1 LT
16	C				2	24		638.86				634.52	108+00	44.0 RT
17		A			5	1 (CLOSED)		641.02	630.77	630.87	630.77	630.27	US 45 305+65.97	62.3 RT
18	A				4	24		638.88			633.88	633.88	109+10	39.5 LT
19	C				2	24		638.64				634.30	109+10	44.0 RT
20	A				4	24		638.55			633.55	633.55	110+20	39.5 LT
21	C				2	24		638.31				633.97	110+20	44.0 RT
22	A				4	24		638.22			633.22	633.22	111+30	38.6 LT
23	C				2	24		637.98				633.64	111+30	44.0 RT
24	A				4	24		638.01			633.04	633.04	112+04.27	36.6 LT
25		A			4	1 (CLOSED)		638.51				633.45	112+00	51.6 RT
26	C				2	24		637.78				631.38	113+30	44.0 RT
27	A				4	24		638.14			631.23	631.23	113+30	6.0 RT
28	C				2	24		637.62			631.29		113+30	36.0 LT
29		A			4	1 (CLOSED)		638.64	632.00	631.02	631.22	631.22	113+30	5.4 LT
30		A			5	1 (CLOSED)		638.37	630.41	629.66	628.61	628.41	114+51.20	5.5 LT
31	C				2	24		637.36					114+58.98	36.0 LT
32	C				2	24		637.35					114+34.82	36.0 LT
33	A				5	24		637.87	630.63		628.83	628.63	114+51.08	5.92 RT
34	C				2	24		637.87		630.65			114+40	5.92 RT
35		A			5	1 (CLOSED)		637.93	629.93	629.43		628.93	114+51.65	51.09 RT
36	C				2	24		637.87		629.97			114+40	44.0 RT
37	A				4	24		639.92		631.80		631.70	116+95.96	42.0 RT
38	A				4	24		639.11			631.19	631.19	116+50	6.0 RT
39		A			4	24		639.61	630.66	630.86	631.16	631.16	116+50	4.7 LT
40	C				2	24		638.23			631.29		116+50	36.0 LT
41	A				5	8		636.50	629.89	629.89			116+25	68.1 RT
42	NOT USED													
43	C				2	24		641.69			634.01		120+50	36.0 LT
44	C				2	24		639.91			632.95		118+38.87	36.0 LT
45		A			5	24		639.79	632.41	632.61	632.61	632.61	118+38.87	42.0 RT
46	A				4	24		640.50	632.96	633.06			119+20	40.6 RT
47	A				4	24		641.69			633.73	633.73	120+50	32.0 RT
48		A			4	1 (CLOSED)		642.25	633.62			633.72	120+50	40.0 RT
49	C				2	24		642.32				637.64	125+10	32.0 LT
50	A				4	24		642.32			637.32	637.32	125+10	32.0 RT
51		A			4	1 (CLOSED)		642.88		635.98		637.30	125+10	40.2 RT
52		A			4	1 (CLOSED)		642.64	635.61	635.36		637.08	125+89.33	39.4 RT
53		A			4	1 (CLOSED)		642.90	634.98	634.78		637.32	126+70	39.4 RT
54		A			4	1 (CLOSED)		644.16	634.00	633.80		638.58	128+30	39.5 RT
55	C				2	24		642.09	637.44				125+79.33	32.0 LT
56	A				4	24		642.08	637.42		637.42		125+89.33	32.0 LT
57	C				2	24		642.09	637.13				125+79.33	32.0 RT
58	A				4	24		642.08	637.10		637.10		125+89.33	32.0 RT
59	C				2	24		642.34			637.66		126+70	32.0 LT
60	A				4	24		642.34			637.34	637.34	126+70	32.0 RT

REVISIONS	
NAME	DATE

STV Incorporated
engineers/architects/scientists/construction managers
200 W Monroe - Suite 1650
Chicago, Illinois 60606

ILLINOIS DEPARTMENT OF TRANSPORTATION

DRAINAGE SCHEDULE OF QUANTITIES - 1

SCALE: NTS

DATE 02/05/08

DRAWN BY RDT

CHECKED BY GC