

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
374	3268F-R-1	COOK	279	72
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 62387				

NO	STRUCTURE TYPE				DIA (FT)	FRAME & GRATE	GRATING FOR FES	PR. RIM ELEV.	PROPOSED INVERT ELEVATION				STATION	OFFSET (FT)
	CB TYPE	MH TYPE	INLET TYPE	FES					N	S	W	E		
	192	C								2	24			
193		A			5	1 (CLOSED)		639.75		634.17	631.59	631.39	US 45 303+76	44.3 LT
194		A			5	1 (CLOSED)		637.27		632.36	632.86	632.36	US 45 300+76.09	40.9 LT
195		A			4	8		635.95				633.22	At Existing Structure for 45	
196	A				4	24		636.67		632.38		632.38	US 45 300+76.09	32.9 LT
197	A				4	24		636.58	632.64			632.64	US 45 300+76.09	30.5 RT
198		A			4	1 (CLOSED)		636.48	631.19	631.09	631.19		Access Road 12+88.37	24.8 RT
199	A				4	24		635.92		631.21	631.21		Access Road 12+87.01	18.0 RT
200		A			4	1 (CLOSED)		636.26	631.64			631.54	Access Road 12+07.14	27.4 RT
201	A				4	24		635.70	631.66	631.66			Access Road 12+07.14	18.0 RT
202		A			4	1 (CLOSED)		643.28			634.77	634.87	Winkelman Road 401+40.30	16.3 LT
203	A				4	24		640.41		635.41	635.41		Winkelman Road 402+50	10.7 LT
204	C				2	24		640.43	635.52				Winkelman Road 402+50	10.0 RT
205	C				2	24		637.48			630.64		115+00	35.6 LT
206		A			5	1 (CLOSED)		638.50	629.77	630.02	630.52	630.52	115+00	2.0 LT
207	A				4	24		638.00			630.54	630.54	115+00	6.4 RT
208	C				2	24		638.77				630.71	115+00	44.2 RT
209	C				2	24		636.60			632.70		US 45 300+90.68	32.9 RT
210	C				2	24		636.70			632.43		US 45 300+90.68	30.6 RT
211	C				2	24		639.19	634.19				US 45 303+75.57	36.6 LT
212		A			4	1 (CLOSED)		644.74	633.18	633.08			129+47.09	40.3 RT
212A				18					632.81				130+32.10	55.0 RT
213	A				4	24		635.70		631.82			Access Road 12+07.14	18.0 LT
213A	C				2	24		635.72		631.86			Access Road 11+94.67	18.0 LT
214	C				2	24		635.90			631.36		Access Road 12+79.70	18.0 LT
215	A				4	24		639.49			631.56	631.56	116+95.96	6.0 RT
216		A			4	1 (CLOSED)		639.49	631.05		631.55		116+95.96	2.3 LT

NOTE:
 * JUNCTION CHAMBER (SPECIAL)
 ** BY OTHERS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
**DRAINAGE SCHEDULE
 OF QUANTITIES - 4**
 SCALE: NTS
 DATE 02/05/08
 DRAWN BY RDT
 CHECKED BY GC

