

SUMMARY OF QUANTITIES

CODE	PAY ITEM	UNIT	TOTAL QUANTITY	1000 60% FEDERAL 40% VILLAGE
20800150	TRENCH BACKFILL	CUYD	25	25
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQYD	300	300
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	5	5
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	5	5
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	5	5
25200100	SODDING	SQYD	300	300
25200200	SUPPLEMENTAL WATERING	UNIT	20	20
40201000	AGGREGATE SURFACE COURSE FOR TEMPORARY ACCESS	TON	50	50
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	800	800
40600300	AGGREGATE (PRIME COAT)	TON	20	20
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	30	30
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQYD	250	250
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX D, N50	TON	1,200	1,200
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	10	10
42101300	PROTECTIVE COAT	SQYD	450	450
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQYD	150	150
42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SQFT	800	800
42400800	DETECTABLE WARNINGS	SQFT	100	100
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQYD	10,500	10,500
44000200	DRIVEWAY PAVEMENT REMOVAL	SQYD	125	125
44000600	SIDEWALK REMOVAL	SQFT	900	900
44001700	COMBINATION CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	650	650
44200948	CLASS B PATCHES, TYPE I, 9 INCH	SQYD	40	40
44200956	CLASS B PATCHES, TYPE II, 9 INCH	SQYD	150	150
44200962	CLASS B PATCHES, TYPE III, 9 INCH	SQYD	75	75
44200964	CLASS B PATCHES, TYPE IV, 9 INCH	SQYD	410	410
60213800	RESTRICTED DEPTH CATCH BASINS, 4' DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1
60228110	MANHOLES, SANITARY, 4' DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	1	1
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	1	1
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	18	18
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	17	17
60404300	FRAMES AND GRATES, TYPE 3	EACH	12	12
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	6	6
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	13	13
60500405	FILLING VALVE VAULTS	EACH	1	1
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	1
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	900	900
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	800	800
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	175	175
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	525	525
X7015000	CHANGEABLE MESSAGE SIGN	CAL-MO	2	2
Z0004900	BITUMINOUS MIXTURE FOR PATCHING POTHOLES (HOT MIX)	TON	20	20
XX006203	STORM SEWERS, PVC SDR 26, 8"	FOOT	90	90
XX104100	CONNECTION TO EXISTING MANHOLE	EACH	3	3

* DENOTES SPECIALTY ITEM



♦ Civil Engineers
 ♦ Municipal Consultants
 ♦ Established 1911
 9933 Roosevelt Road
 Westchester, Illinois 60154-2780
 Phone: 708/865-0300
 Fax: 708/865-1212

WASHINGTON AVENUE
PROJECT NO. M- 8003(902)
VILLAGE SECTION 07-00123-00-RS
VILLAGE OF BROOKFIELD, ILLINOIS

SUMMARY OF QUANTITIES

SCALE:	NONE	SHEET 4 OF 20
DRAWN BY:	LEV/MK	
BOOK NO.:	SCANS/BP/LS	
DATE:	1-16-08	
REVISION:	E.H.E. NO.: 125-07-13601	