



**WEST ABUTMENT PLAN**

Notes:  
 Space reinforcement in top of abutment wall to miss anchor bolts.  
 Reinforcement bars designated (E) shall be epoxy coated.  
 Pour steps monolithically with abutment stem  
 See S-23 for Section D-D  
 See S-24 for Section E-E & F-F  
 See S-26 for Bill of Material and Pipe Underdrain Details.

| REV. NO. | DATE | REVISION RECORD | MADE BY | CHECKED BY |
|----------|------|-----------------|---------|------------|
| △        |      |                 |         |            |
| △        |      |                 |         |            |
| △        |      |                 |         |            |
| △        |      |                 |         |            |
| △        |      |                 |         |            |

|   |   |
|---|---|
|   | <b>Wiss, Janney, Elstner Associates, Inc.</b><br>Engineers, Architects, Material Scientists<br>330 Pfingsten Road, Northbrook, IL 60062<br>(847) 272-7400, Fax: (847) 291-4813<br>WJE No. 2006.2324 |
|   | <b>THE CITY OF LAKE FOREST</b><br>CHARTERED 1861<br>ILLINOIS DEPARTMENT OF TRANSPORTATION<br>BUREAU OF LOCAL ROADS AND STREETS  |
| PROJECT:<br><b>OLD ELM ROAD OVER EAST SKOKIE DITCH</b><br>STA. 187+46 LAKE COUNTY<br>STRUCTURE NO. 049-6870 | TITLE:<br><b>WEST ABUTMENT STEM WALL PLAN</b>   |
| SCALE: N.T.S.<br>DATE: JANUARY 2008   | DRAWN BY: IMG<br>CHECKED BY: NSA  |

DATE: 2/2/2008  
 FILENAME: p:\2006\2301-2400\2006.2324-anderson-old elm design\microstation-final\p-22.dgn