

40603310 HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50

TON	LOCATION	THICKNESS (in)	REMARKS
12.50	LT Sta. 432+37.0 TO 433+47.0	1.5	110 x 12 - One Lane
12.50	RT Sta. 432+37.0 TO 433+47.0	1.5	110 x 12 - One Lane
<u>25.00</u>	TOTAL		

42001200 PAVEMENT FABRIC

SQ. YD.	LOCATION	REMARKS
150.0	LT Sta. 432+37.0 TO 433+47.0	110 x 12 - One Lane
150.0	RT Sta. 432+37.0 TO 433+47.0	110 x 12 - One Lane
<u>300.0</u>	TOTAL	

44000400 GUTTER REMOVAL

FOOT	LOCATION	REMARKS
153.0	LT Sta. 432+12.0 TO 433+65.0	
153.0	RT Sta. 432+12.0 TO 433+65.0	
<u>306.0</u>	TOTAL	

44002500 GUTTER OUTLET REMOVAL

EACH	LOCATION	REMARKS
1.0	LT Sta. 434+03.0	
1.0	RT Sta. 434+03.0	
<u>2.0</u>	TOTAL	

44201421 CLASS C PATCHES, TYPE IV, 15 INCH

SQ. YD.	LOCATION	REMARKS
150.0	LT Sta. 432+37.0 TO 433+47.0	110 x 12 - One Lane
150.0	RT Sta. 432+37.0 TO 433+47.0	110 x 12 - One Lane
<u>300.0</u>	TOTAL	

48102100 AGGREGATE WEDGE SHOULDER, TYPE B

TON	LOCATION	REMARKS
17.5	RT Sta. 434+39.0 TO 437+00.0	
17.5	LT Sta. 434+39.0 TO 437+00.0	
75.0	DETOUR ROUTE	IF NEEDED
<u>110.0</u>	TOTAL	

50100100 REMOVAL OF EXISTING STRUCTURES

EACH	LOCATION	REMARKS
1.0	Sta. 432+95.0	EXISTING 10' X 8' BOX CULVERT
<u>1.0</u>	TOTAL	

51500100 NAME PLATES

EACH	LOCATION	REMARKS
1.0	Sta. 432+95.0	10' X 8' PRE-CAST BOX CULVERT
<u>1.0</u>	TOTAL	

54001001 BOX CULVERT END SECTION, CULVERT NO. 1

EACH	LOCATION	REMARKS
1.0	Sta. 432+95.0	10' X 8' PRE-CAST BOX CULVERT
<u>1.0</u>	TOTAL	

54011008 PRECAST CONCRETE BOX CULVERT 10' X 8'

FOOT	LOCATION	REMARKS
140.0	Sta. 432+95.0	
<u>140.0</u>	TOTAL	

54201270 PIPE CULVERTS, TYPE 2 RCCP 15"

FOOT	LOCATION	REMARKS
22.0	LT Sta. 434+01.0	GUTTER OUTLETS
28.0	RT Sta. 434+01.0	GUTTER OUTLETS
<u>50.0</u>	TOTAL	

54213453 END SECTIONS 18"

EACH	LOCATION	REMARKS
1.0	RT Sta. 436+49.0	FIELD ENTRANCE
1.0	RT Sta. 436+89.0	FIELD ENTRANCE
<u>2.0</u>	TOTAL	

54213660 PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"

EACH	LOCATION	REMARKS
1.0	LT Sta. 434+01.0	GUTTER OUTLETS
1.0	RT Sta. 434+01.0	GUTTER OUTLETS
<u>2.0</u>	TOTAL	

542D0223 PIPE CULVERTS CLASS D, TYPE 1, 18"

FOOT	LOCATION	REMARKS
40.0	RT Sta. 436+69.0	FIELD ENTRANCE
<u>40.0</u>	TOTAL	

60405800 GRATES AND COVERS, TYPE 2A

EACH	LOCATION	REMARKS
1.0	LT Sta. 434+01.0	OUTLETS TY 2 FOR TY A GUTTER--STD. 606111
1.0	RT Sta. 434+01.0	OUTLETS TY 2 FOR TY A GUTTER--STD. 606111
<u>2.0</u>	TOTAL	

60600095 CLASS SI CONCRETE (OUTLET)

CU. YD.	LOCATION	REMARKS
3.1	LT Sta. 433+65.0 TO 434+39.0	OUTLETS TY 2 FOR TY A GUTTER--STD. 606111
3.1	RT Sta. 433+65.0 TO 434+39.0	OUTLETS TY 2 FOR TY A GUTTER--STD. 606111
<u>6.2</u>	TOTAL	

60602500 CONCRETE GUTTER, TYPE A

FOOT	LOCATION	REMARKS
153.0	LT Sta. 432+12.0 TO 433+65.0	PATCH AREA
153.0	RT Sta. 432+12.0 TO 433+65.0	PATCH AREA
<u>306.0</u>	TOTAL	

61100500 EXPLORATION TRENCH 52" DEPTH

FOOT	LOCATION	REMARKS
50.0	RT/LT Sta. 432+95.0	ESTIMATED
<u>50.0</u>	TOTAL	

61100605 MISCELLANEOUS CONCRETE

CU. YD.	LOCATION	REMARKS
1.0	RT Sta. 432+95.0	SLOPE WALL FOR FIELD TILE OUTLETS (ESTIMATED)
1.0	LT Sta. 432+95.0	SLOPE WALL FOR FIELD TILE OUTLETS (ESTIMATED)
<u>2.0</u>	TOTAL	

61133100 FIELD TILE JUNCTION VAULTS, 2' DIA

EACH	LOCATION	REMARKS
1.0	RT Sta. 432+95.0	ESTIMATED
1.0	LT Sta. 432+95.0	ESTIMATED
<u>2.0</u>	TOTAL	

61140000 STORM SEWERS (SPECIAL) 8"

FOOT	LOCATION	REMARKS
50.0	LT Sta. 432+95.0	ESTIMATED
50.0	RT Sta. 432+95.0	ESTIMATED
<u>100.0</u>	TOTAL	