

61140100 STORM SEWERS (SPECIAL) 10"

FOOT	LOCATION
50.0	LT Sta. 432+95.0
50.0	RT. Sta. 432+95.0
<u>100.0</u>	TOTAL

REMARKS
ESTIMATED
ESTIMATED

61140200 STORM SEWERS (SPECIAL) 12"

FOOT	LOCATION
50.0	LT Sta. 432+95.0
50.0	RT. Sta. 432+95.0
<u>100.0</u>	TOTAL

REMARKS
ESTIMATED
ESTIMATED

63200310 GUARDRAIL REMOVAL

FOOT	LOCATION
115.0	LT Sta. 432+85.0 TO 434+00.0
228.0	RT. Sta. 431+71.0 TO 434+00.0
<u>343.0</u>	TOTAL

REMARKS

63500105 DELINEATORS

EACH	LOCATION
4.0	LT Sta. 432+37.0 TO 433+47.0
<u>4.0</u>	TOTAL

REMARKS
AT BOX CULVERT

66411900 TEMPORARY FENCE

FOOT	LOCATION
545.0	LT Sta. 430+30.0 TO 435+50.0
<u>545.0</u>	TOTAL

REMARKS
ON PROPOSED RIGHT OF WAY

66600105 FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS

EACH	LOCATION	OFFSET (ft)
1	LT Sta. 430+30.0	48' LT
1	LT Sta. 432+40.0	110' LT
1	LT Sta. 433+35.0	110' LT
1	LT Sta. 433+75.0	80' LT
1	LT Sta. 435+50.0	42' LT
1	RT Sta. 430+15.0	44' RT
1	RT Sta. 432+51.9	130' RT
1	RT Sta. 433+75.0	130' RT
1	RT Sta. 434+75.0	75' RT
1	RT Sta. 436+60.0	44' RT
<u>10.0</u>	TOTAL	

REMARKS

66700305 PERMANENT SURVEY MARKERS, TYPE II

EACH	LOCATION
2.0	ENTIRE JOB
<u>2.0</u>	TOTAL

REMARKS
LOCATION TO BE DETERMINED IN FIELD

70300100 SHORT-TERM PAVEMENT MARKING

FOOT	LOCATION
675.0	Sta. 430+25.0 TO 437+00.0
1350.0	Sta. 430+25.0 TO 437+00.0
170.0	Sta. 430+25.0 TO 437+00.0
<u>2195.0</u>	TOTAL

REMARKS
YELLOW CENTERLINE
2 WHITE EDGE LINES
YELLOW SKIP DASH

70301000 WORK ZONE PAVEMENT MARKING REMOVAL

SQ FT	LOCATION
223.0	Sta. 430+25.0 TO 437+00.0
446.0	Sta. 430+25.0 TO 437+00.0
56.0	Sta. 430+25.0 TO 437+00.0
<u>725.0</u>	TOTAL

REMARKS
YELLOW CENTERLINE
2 WHITE EDGE LINES
YELLOW SKIP DASH

78001110 PAINT PAVEMENT MARKING - LINE 4" (TWO COATS)

FOOT	LOCATION
1350.0	Sta. 430+25.0 TO 437+00.0
2700.0	Sta. 430+25.0 TO 437+00.0
340.0	Sta. 430+25.0 TO 437+00.0
<u>4390.0</u>	TOTAL

REMARKS
YELLOW CENTERLINE
2 WHITE EDGE LINES
YELLOW SKIP DASH

Z0005400 BREAKER-RUN CRUSHED STONE

TON	LOCATION
531.0	Sta. 432+95.0
<u>531.0</u>	TOTAL

REMARKS
16 x 175 UNDER CULVERT AND DROP BOX

Z0028415 GEOTECHNICAL REINFORCEMENT

SQ YD	LOCATION
380.0	Sta. 432+37.0 TO 433+47.0
<u>380.0</u>	TOTAL

REMARKS
UNDER PATCH AND CURB & GUTTER

X0322263 CULVERT DROP BOX

EACH	LOCATION
1.0	LT Sta. 432+95.0
<u>1.0</u>	TOTAL

REMARKS
10'X27'X4' DROP BOX

X0325911 HOT-MIX ASPHALT SURFACE COURSE, SPECIAL

TON	LOCATION
200.0	DETOUR ROUTE
<u>200.0</u>	TOTAL

REMARKS
IF NEEDED

FILE NAME =	USER NAME = grantpm	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ca\projects\p203705\ad03705ovr.dgn		DRAWN -	REVISED -		634	138T	HENRY	42	10				
	PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -		CONTRACT NO. 64A77								
	PLOT DATE = Wed Jan 23 08:48:08 2008	DATE -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	