63500105 DELINEATORS

EACH	LOCATION	REMARKS
2	LT & RT Sta 775+56.5	At ends of culvert
2 TOTAL		

66600105 FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS

EACH	LOCATION		OFFSET (ft)	REMARKS
1	LT Sta.	775+00.94	55' LT	
1	LT Sta.	775+35.00	70' LT	
1	LT Sta.	775+80.00	70' LT	
1	LT Sta.	776+50.00	60' LT	
1	LT Sta.	777+50.00	85' LT	
1	LT Sta.	778+50.00	45' LT	
1	LT Sta.	779+00.00	40' LT	
1	RT Sta.	773+00.00	40' RT	
1	RT Sta.	774+00.00	45' RT	
1	RT Sta.	775+00.19	65' RT	
1	RT Sta.	775+35.00	105' RT	
1	RT Sta.	775+80.00	105' RT	
1	RT Sta.	776+00.00	65' RT	
1	RT Sta.	777+00.00	60' RT	
1	RT Sta.	778+00.00	40' RT	
15 TOTAL				

66700305 PERMANENT SURVEY MARKERS, TYPE II

EACH	LOCATION	REMARKS
2.0	ENTIRE JOB	
2.0 TOTAL		

70106700 TEMPORARY RUMBLE STRIP

EACH	LOCATION	
1	RT Sta.	754+51.7
1	RT Sta.	759+51.7
1	RT Sta.	764+51.7
1	LT Sta.	786+09.7
1	LT Sta.	791+09.7
1	LT Sta.	796+09.7
6 TOTAL		

70300100 SHORT-TERM PAVEMENT MARKING

FOOT	LOCATION				REMARKS
90.0	Sta.	771+00.0	TO	780+00.0	CL - Use between staging & permanent paint
180.0	Sta.	771+00.0	TO	780+00.0	2 Edge Lines - Use between staging & permanent paint
270.0 TOTAL					

70300520 PAVEMENT MARKING TAPE, TYPE III 4"

FOOT	LOCATION				REMARKS
689.0	RT Sta.	772+11.6	TO	778+98.3	STAGE 1 - Inside, white
456.0	RT Sta.	773+26.5	TO	777+60.4	STAGE 1 - Outside, white
613.0	LT Sta.	772+28.2	TO	778+39.3	STAGE 2 - Inside, white
325.0	LT Sta.	773+93.8	TO	777+18.5	STAGE 2 - Outside, white
2083.0 TOTAL					

70300570 PAVEMENT MARKING TAPE, TYPE III 24"

FOOT	LOCATION				REMARKS
12.0	RT Sta.	771+51.8			STOP BAR STAGE 1 & 2
12.0	LT Sta.	779+09.1			STOP BAR STAGE 1 & 2
24.0 TOTAL					

70301000 WORK ZONE PAVEMENT MARKING REMOVAL

SQ FT	LOCATION				
230.0	LT Sta.	772+11.6	TO	778+98.3	STAGE 1 - Inside, white
152.0	RT Sta.	773+26.5	TO	777+60.4	STAGE 1 - Outside, white
205.0	RT Sta.	772+28.2	TO	778+39.3	STAGE 2 - Inside, white
109.0	LT Sta.	773+93.8	TO	777+18.5	STAGE 2 - Outside, white
24.0	RT Sta.	771+51.8			STOP BAR STAGE 1 & 2
24.0	LT Sta.	779+09.1			STOP BAR STAGE 1 & 2
30.0	Sta.	775+31.5	TO	775+81.5	CL dbl yellow - Use between staging & permanent paint
60.0	Sta.	775+31.5	TO	775+81.5	2 Edge Lines - Use between staging & permanent paint
834.0 TOTAL					

70400100 TEMPORARY CONCRETE BARRIER

FOOT	LOCATION				
437.5	RT Sta.	772+44.5	TO	777+68.5	STAGE 1
437.5 TOTAL					

70400200 RELOCATE TEMPORARY CONCRETE BARRIER

FOOT	LOCATION				
325.0	RT Sta.	773+94.3	TO	777+18.7	STAGE 2
325.0 TOTAL					

78001110 PAINT PAVEMENT MARKING - LINE 4"

FOOT	LOCATION				REMARKS
3600.0	Sta.	771+00.0	TO	780+00.0	2 YELLOW CENTERLINE - TWO COATS
3600.0	Sta.	771+00.0	TO	780+00.0	2 WHITE EDGE LINES - TWO COATS
7200.0 TOTAL					

78300100 PAVEMENT MARKING REMOVAL

SQ FT	LOCATION				REMARKS
206.0	Sta.	771+51.8	TO	774+60.0	Existing CL - Dbl Yellow (STAGE 1)(will also rem for stage 2)
174.0	Sta.	776+50.0	TO	779+09.1	Existing CL - Dbl Yellow (STAGE 1)(will also rem for stage 2)
146.0	Sta.	773+26.4	TO	777+60.4	Existing Edgeline RT (STAGE 1)
110.0	Sta.	773+93.8	TO	777+18.6	Existing Edgeline LT (STAGE 2)
636.0 TOTAL					

Z0005400 BREAKER-RUN CRUSHED STONE

TON	LOCATION		THICKNESS (In)	REMARKS
229.6	Sta.	775+56.5	36	9 x 112 UNDER CULVERT & DROP BOX (Includes 3" of Porous Granular Material)
229.6 TOTAL				

Z0023600 FILLING EXISTING CULVERTS

EACH	LOCATION		
1	Sta.	775+56.5	TO MAINTAIN DRAINAGE DURING CONSTRUCTION
1 TOTAL			