

PAVEMENT PATCHING SCHEDULE						
LOCATION	44213200	Z0017202	44213100	44200988	Z0075300	40603310
	SAW CUTS	DOWEL BARS 1 1/2"	PAVEMENT FABRIC	CLASS B PATCHES TYPE M 11"	TIE BARS	HOT-MX ASPHALT SURF CSE MX "C", N50
	(FT)	(EACH)	(SY)	(SY)	(EACH)	TON
STA 600+52.00 TO STA 600+83.00	120	80	82.7	82.7	31	9.3
STA 604+04.40 TO STA 604+20.40	120	40	42.7	42.7	16	4.8
STA 607+60.00 TO STA 608+22.00	120	120	165.3	165.3	62	18.5
STA 609+36.00 TO STA 610+29.00	120	160	248.0	248.0	93	27.8
<b>TOTAL</b>	<b>480</b>	<b>400</b>	<b>539</b>	<b>539</b>	<b>202</b>	<b>60</b>

SEE SHOULDER SCHEDULE FOR ADDITIONAL HMA SURFACE COURSE

SHOULDER SCHEDULE			
LOCATION	48203021	48101200	40603310
	HOT-MX ASPHALT SHOULDERS 6"	AGGREGATE SHOULDERS TYPE B, 8"	HOT-MX ASPHALT SURF CSE MX "C", N50
	SY	TON	TON
RT STA 600+31.45 TO STA 600+52.00	3.5	4.9	0.4
STA 600+52.00 TO STA 600+83.00	29.5	15.3	3.2
RT STA 600+83.00 TO STA 604+04.40	113.2	97.6	12.3
LT STA 600+83.00 TO STA 604+04.40	113.2	97.6	12.3
STA 604+04.40 TO STA 604+20.40	11.3	9.7	1.2
RT STA 604+20.40 TO STA 607+60.00	119.6	103.1	13.0
LT STA 604+20.40 TO STA 607+60.00	119.6	103.1	13.0
STA 607+60.00 TO STA 608+22.00	43.7	37.7	4.8
RT STA 608+22.00 TO STA 609+36.00	40.2	34.6	4.4
LT STA 608+22.00 TO STA 609+36.00	40.2	34.6	4.4
STA 609+36.00 TO STA 610+29.00	65.5	56.5	7.1
RT STA 610+29.00 TO STA 612+50.00	60.2	62.0	6.6
LT STA 610+29.00 TO STA 613+00.00	77.8	77.2	8.5
<b>TOTAL</b>	<b>838</b>	<b>734</b>	<b>91</b>

HMA SHOULDER BEGINS RT STA 600+42.00 AND ENDS RT STA 612+00.00  
HMA SHOULDER BEGINS LT STA 600+52.00 AND ENDS LT STA 612+50.00

PAVEMENT MARKING SCHEDULE						
LOCATION	78001110		78001180	78001100	70300100	70301000
	PAINT PAVEMENT MARKING - LINE 4"					
	CENTERLINE DOUBLE LINE	EDGE LINE	PAINT PAVEMENT MARKING - LINE 24"	PAINT PAVEMENT MARKING - LETTERS & SYMBOLS	SHORT TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL
	SOLID - YELLOW	SOLID - WHITE			YELLOW	
	FOOT	FOOT	FOOT	SF	FOOT	SF
STA 600+52 TO STA 613+00	4992	4992	-	-	-	-
STA 600+52 TO STA 600+83	-	-	-	-	4	1.33
STA 604+04.40 TO STA 604+20.40	-	-	-	-	4	1.33
STA 607+60 TO STA 608+22	-	-	-	-	8	2.67
STA 609+36 TO STA 610+29	-	-	-	-	12	4.0
RR CROSSING - WEST GALENA RD	-	-	72	122.4	-	-
<b>TOTAL</b>		9984 *	72	123	28	10

\* ASSUMES 2 APPLICATIONS, SEE GOOD NEIGHBOR POLICY SCHEDULE FOR ADDITIONAL PAINT PAVEMENT MARKING - LINE 4"

RIGHT-OF-WAY MARKER SCHEDULE		
LOCATION	OFFSET (FT)	66600105
		(EACH)
RT STA 600+30.30	153.52	1
RT STA 600+58.77	110.20	1
LT STA 600+75.68	60.00	1
LT STA 601+00.00	60.00	1
RT STA 601+00.00	75.00	1
LT STA 602+00.00	45.00	1
RT STA 603+00.00	70.00	1
LT STA 604+00.00	45.00	1
RT STA 606+00.00	70.00	1
RT STA 609+00.00	110.00	1
LT STA 609+00.00	100.00	1
RT STA 610+00.00	110.00	1
LT STA 610+50.00	105.00	1
LT STA 611+00.00	70.00	1
LT STA 612+00.00	45.00	1
LT STA 613+00.00	35.00	1
RT STA 613+00.00	50.00	1
<b>TOTAL</b>		<b>17</b>

RELOCATE EXISTING SURVEY MARKER SCHEDULE	
LOCATION	Z0049800
	EACH
STA 606+29.19, 17.02' RT	1
<b>TOTAL</b>	<b>1</b>

REMOVAL OF EXISTING STRUCTURES SCHEDULE			
NUMBER	PAY CODE	LOCATION	DESCRIPTION
1	50100300	STA 600+62.28	2 FT SPAN x 2' RISE RCBC
2	50100400	STA 604+12.40	3 FT SPAN x 2' RISE RCBC
3	50100500	STA 607+90.44	7 FT SPAN x 4.5' RISE RCBC EX SN 089-1031

EARTHWORK SCHEDULE			
LOCATION	20200100	NOT A PAY ITEM	NOT A PAY ITEM
	EARTH EXCAVATION	EMBANKMENT	WASTE EXCAVATION
	CU YD	CU YD	CU YD
STA 599+94 TO STA 605+00 (INCLUDES GODDARD ROAD)	1540	974	274
STA 605+00 TO STA 611+00	4434	786	3412
STA 611+00 TO STA 613+00	352	11	338
<b>TOTALS</b>	<b>6325</b>	<b>1771</b>	<b>4024</b>

ITEMS ASSUME 30% SHRINKAGE FACTOR

**COOMBE-BLOXDORF P.C.**  
Engineers / Land Surveyors  
Springfield, Illinois  
Design Firm License No. 184-002703

FILE NAME =	USER NAME = CFC-na	DESIGNED -	REVISED -
...\\07\07075\vr-na\z11306evr4.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES**

SCALE: SHEET NO. 1 OF 2 SHEETS STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1087	107T-1	STEPHENSON	47	6
				CONTRACT NO. 64C64
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		