| FINAL SURVEY | BY | DATE |
|---|---|---|
| NOTE BOOK | SURVEYED | |
| NO. | PLOTTED | |
| | TEMPLATE | |
| | AREAS | |
| | AREAS CHECKED | |

| ORIGINAL SURVEY | BY | DATE |
|---|---|---|
| NOTE BOOK | SURVEYED | |
| NO. | PLOTTED | |
| | TEMPLATE | |
| | AREAS | |
| | AREAS CHECKED | |

150 140 130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150

900
895
890

EX ROW
SPECIAL DITCH RT
STA. 609+39.56 - 600+50.00
R ELEV = 888.40 - 881.13
SLOPE = 0.82%
896.26
1.50 %
896.09
4.00 %
1:3
S.D.888.40
EX ROW

**609 + 39.56**

900
895
890

EX ROW
C=240 F=42
1:3
1:4
S.D.889.14
EX ROW
4.00 %
895.77
895.88
895.69
4.00 %
1:4.6
1:3
S.D.888.08

**609 + 00.00**

905
900
895
890

PR ROW
EX ROW
C=228 F=40
1:3
1:4
S.D.889.35
EX ROW
4.00 %
895.37
895.49
895.34
4.00 %
1:4
1:3
S.D.887.67

**608 + 50.00**

150 140 130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150

| | | | |
|---|---|---|---|
| FILE NAME = k:\07\07075\w8-ns\xl1306xml.dgn | USER NAME = CFC-ns | DESIGNED - | REVISED - |
| | | DRAWN - | REVISED - |
| | PLOT SCALE = 10.0000 ' / IN. | CHECKED - | REVISED - |
| | PLOT DATE = 01/21/2008 | DATE - | REVISED - |

**STATE OF ILLINOIS**
**DEPARTMENT OF TRANSPORTATION**

**IL ROUTE 73 CROSS SECTIONS**

SCALE: | SHEET NO. 8 OF 11 SHEETS | STA. 608+50.00 | TO STA. 609+39.56

| F.A.S RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 1087 | 107T-1 | STEPHENSON | 47 | 43 |
| | | CONTRACT NO. 64C64 | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |