

CODE NO	ITEM	UNIT	FEDERAL 80%
			STATE 20% Y007 TOTAL QUANTITY
20100110	TREE REMOVAL (6 TO 15 DIAMETER UNITS)	UNIT	28
20200100	EARTH EXCAVATION	CU YD	326
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	109
20400800	FURNISHED EXCAVATION	CU YD	20
21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	100
25100630	EROSION CONTROL BLANKET	SQ YD	131
28000300	TEMPORARY DITCH CHECKS	EACH	13
28000400	PERIMETER EROSION BARRIER	FOOT	819
28000500	INLET AND PIPE PROTECTION	EACH	2
28100107	STONE RIPRAP, CLASS A4	SQ YD	71
28200200	FILTER FABRIC	SQ YD	110.0
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	16
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	46.3
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	115.6
44201421	CLASS C PATCHES, TYPE IV, 15 INCH	SQ YD	162
48101200	AGGREGATE SHOULDERS, TYPE B	TON	22
48203019	HOT-MIX ASPHALT SHOULDERS, 5 1/2"	SQ YD	137
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1
50800105	REINFORCEMENT BARS	POUND	9,090
50800515	BAR SPLICERS	EACH	34
51205200	TEMPORARY SHEET PILING	SQ FT	619.2
51500100	NAME PLATES	EACH	1
54002010	EXPANSION BOLTS 1/2 INCH	EACH	24
54003000	CONCRETE BOX CULVERTS	CU YD	39.6
5421A036	PIPE CULVERTS, CLASS A, TYPE 1 36" (TEMPORARY)	FOOT	5
54248510	CONCRETE COLLAR	CU YD	3.1
61133100	FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	2
61139900	STORM SEWERS (SPECIAL) 6"	FOOT	100

CODE NO	ITEM	UNIT	FEDERAL 80%
			STATE 20% Y007 TOTAL QUANTITY
61140000	STORM SEWERS (SPECIAL) 8"	FOOT	100
61140100	STORM SEWERS (SPECIAL) 10"	FOOT	100
63200310	GUARDRAIL REMOVAL	FOOT	626
63500105	DELINEATORS	EACH	2
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	7
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2
67100100	MOBILIZATION	L SUM	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
70106700	TEMPORARY RUMBLE STRIP	EACH	6
70300220	TEMPORARY PAVEMENT MARKING-LINE 4"	FOOT	1137
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	1784
70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	24
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1006.9
70400100	TEMPORARY CONCRETE BARRIER	FOOT	362.5
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	350
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	4200
78300100	PAVEMENT MARKING REMOVAL	SQ FT	636
* B2000116	TREE, ACER CAMPESTRIS (HEDGE MAPLE), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	4
X0712400	TEMPORARY PAVEMENT	SQ YD	282.4
X0919000	TEMPORARY PAVEMENT REMOVAL	SQ YD	29.6
X7013015	TRAFFIC CONTROL FOR ROAD CLOSURE	L SUM	1
Z0005400	BREAKER-RUN CRUSHED STONE	TON	224
Z0013798	CONSTRUCTION LAYOUT	L SUM	1
* Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2
* Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2

\* SPECIALTY ITEM

FILE NAME = C:\Projects\p211986\d11986crr.dgn	USER NAME = jordanhd	DESIGNED - _____	REvised - _____	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.E. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - _____	REvised - _____		SCALE: _____	SHEET NO. _____ OF _____ SHEETS	STA. _____ TO STA. _____	611	102T	HENRY	41	2
		CHECKED - _____	REvised - _____		FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT							
		DATE - _____	REvised - _____		CONTRACT NO. 64C70							