

20100110 Tree Removal (6 to 15 Units Diameter)

Location	Unit
Sta. 284+62 Lt	7
285+24 Lt	6
285+41 Lt	6
285+60 Lt	9
<b>Total =</b>	<b>28</b>

20200100 Earth Excavation

Location	Cu. Yd.
Sta. 281+90.00 to 287+25.00 Lt & Rt	326
<b>Total =</b>	<b>326</b>

20201200 Removal and Disposal of Unsuitable Material

Location	Cu. Yd.
Sta. 284+80.47	109.3
<b>Total =</b>	<b>109</b>

15' wide x 98.34' long x 2' deep

20400800 Furnished Excavation

Location	Cu. Yd.
Sta. 281+90.00 to 287+25.00	20
<b>Total =</b>	<b>20</b>

21301052 Exploration Trench 52" Depth

Location	Foot
Sta. 281+90.00 to 287+25.00	100
<b>Total =</b>	<b>100</b>

25100630 Erosion Control Blanket

Location	Sq. Yd.
Sta. 284+00.00 to 284+80.47 Lt	35
284+00.00 to 284+80.47 Rt	36
284+80.47 to 285+75.00 Lt	41
284+80.47 to 285+25.00 Rt	19
<b>Total =</b>	<b>131</b>

28000300 Temporary Ditch Checks

Location	Each
Sta. 283+00.00 Lt & Rt	2
284+00.00 Lt & Rt	2
284+50.00 Lt & Rt	2
285+00.00 Lt & Rt	2
285+50.00 Lt & Rt	2
286+00.00 Lt	1
286+50.00 Lt & Rt	2
<b>Total =</b>	<b>13</b>

28000400 Perimeter Erosion Barrier

Location	Foot
Sta. 283+40.00 to 287+00.00 Lt	416
282+65.00 to 286+20.00 Rt	403
<b>Total =</b>	<b>819</b>

28000500 Inlet and Pipe Protection

Location	Each
Sta. 284+80.47 Lt	1 Stage I
284+80.47 Lt	1 Stage III
<b>Total =</b>	<b>2</b>

28100107 Stone Riprap, Class A4

Location	Sq. Yd.
Sta. 284+80.60 49' Lt	41 11' x 33'
284+80.60 49' Rt	31 11' x 25'
<b>Total =</b>	<b>71</b>

28200200 Filter Fabric

Location	Sq. Yd.
Sta. 284+80.60 49' Lt	40 11' x 33'
284+80.60 49' Rt	31 11' x 25'
<b>Total =</b>	<b>71</b>

40600625 Leveling Binder (Machine Method), N50

Location	Ton
Sta. 284+32.47 to 285+28.48	16
<b>Total =</b>	<b>16</b>

40603310 Hot-Mix Asphalt Surface Course, Mix "C", N50

Location	Ton
Sta. 283+00.00 to 286+50.00 Rt-Stage 2	16.3 3' Shoulder
284+50.00 to 285+10.00 Lt-Stage 3	2.8 3' Shoulder
284+32.47 to 285+28.48 Stage 2 & 3	27.2 Mainline
<b>Total =</b>	<b>46.3</b>

44000159 Hot-Mix Asphalt Surface Removal, 2 1/2"

Location	Sq. Yd.
Sta. 284+32.47 284+52.47	57.8
285+08.47 285+28.48	57.8
<b>Total =</b>	<b>115.6</b>

44201421 Class C Patches, Type IV, 15"

Location	Sq. Yd.
Sta. 284+52.47 to 285+08.47	162
<b>Total =</b>	<b>162</b>

48101200 Aggregate Shoulders, Type B

Location	Ton
Sta. 281+90.00 to 283+00.00 Rt	13
286+50.00 to 287+12.35 Rt	7
<b>Total =</b>	<b>22</b>

48203019 Hot-Mix Asphalt Shoulders, 5 1/2"

Location	Sq. Yd.
Sta. 284+52.47 to 285+08.47 Lt	20.0 Stage III
283+00.00 to 286+50.00 Rt	116.7 Stage II
<b>Total =</b>	<b>137</b>

50100100 Removal of Existing Structures

Location	Each
Sta. 284+80.47	1
<b>Total =</b>	<b>1</b>

50800105 Reinforcement Bars

Location	Pounds
Sta. 284+80.47	11809
<b>Total =</b>	<b>11809</b>

50800515 Bar Splicers

Location	Each
Sta. 284+80.47	29
<b>Total =</b>	<b>29</b>

51205200 Temporary Sheet Piling

Location	Sq. Ft.
Sta. 284+57.47 to 285+03.47 Lt	619.2
<b>Total =</b>	<b>619.2</b>

51500100 Name Plates

Location	Each
Sta. 284+80.47	1
<b>Total =</b>	<b>1</b>