

54003000 Concrete Box Culverts

| Location | Sta. | Cu. Yds. |
|-----------|------|----------|
| 284+80.47 | | 53.6 |
| Total = | | 53.6 |

5421A036 Pipe Culverts, Class A, Type 1 36" (Temporary)

| Location | Sta. | Foot | Description |
|-----------|------|------|-----------------------------|
| 284+80.47 | | 5 | Culvert Extension (Stage I) |
| Total = | | 5 | |

54248510 Concrete Collar

| Location | Sta. | Cu. Yd. | Description |
|-----------|------|---------|-----------------------------|
| 284+80.47 | | 3.1 | Culvert Extension (Stage I) |
| Total = | | 3.1 | |

61133100 Field Tile Junction Vaults, 2' Dia.

| Location | Sta. | Each | Description |
|-----------|-------------------|------|---------------|
| 281+90.00 | 287+25.00 Lt & Rt | 2 | (Contingency) |
| Total = | | 2 | |

61139900 Storm Sewers (Special) 6"

| Location | Sta. | Foot | Description |
|-----------|-------------------|------|---------------|
| 281+90.00 | 287+25.00 Lt & Rt | 100 | (Contingency) |
| Total = | | 100 | |

61140000 Storm Sewers (Special) 8"

| Location | Sta. | Foot | Description |
|-----------|-------------------|------|---------------|
| 281+90.00 | 287+25.00 Lt & Rt | 100 | (Contingency) |
| Total = | | 100 | |

61140100 Storm Sewers (Special) 10"

| Location | Sta. | Foot | Description |
|-----------|-------------------|------|---------------|
| 281+90.00 | 287+25.00 Lt & Rt | 100 | (Contingency) |
| Total = | | 100 | |

63200310 Guardrail Removal

| Location | Sta. | Foot |
|-----------|-----------------|------|
| 283+64.70 | to 286+77.50 Lt | 312 |
| 282+84.30 | to 285+96.00 Rt | 313 |
| Total = | | 626 |

63500105 Delineators

| Location | Sta. | Each |
|-----------|------|------|
| 284+80.60 | | 2 |
| Total = | | 2 |

66600105 Furnishing and Erecting Right-of-Way Markers

| Location | Sta. | Each | Description |
|-----------|---------|------|-------------|
| 284+00.00 | Lt & Rt | 2 | 35' RT |
| 284+50.00 | Lt | 1 | 100' LT |
| 284+50.00 | Rt | 1 | 90' RT |
| 284+80.63 | Lt | 1 | 100' LT |
| 285+10.00 | Rt | 1 | 90' RT |
| 285+60.00 | Rt | 1 | 35' RT |
| Total = | | 7 | |

66700305 Permanent Survey Markers, Type II

| Location | Sta. | Each | Description |
|-----------|----------------------|------|---------------------------------|
| 281+90.00 | to 287+25.00 Lt & Rt | 2 | RE & D2 Survey Approve location |
| Total = | | 2 | |

70106700 Temporary Rumble Strips

| Location | Sta. | Each |
|----------|-----------|------|
| | 264+40.70 | Rt 1 |
| | 269+40.70 | Rt 1 |
| | 274+40.70 | Rt 1 |
| | 295+90.50 | Lt 1 |
| | 300+90.50 | Lt 1 |
| | 305+90.50 | Lt 1 |
| Total = | | 6 |

70300220 Temporary Pavement Marking

| Location | Sta. | Foot | Description |
|----------|---------------------------------------|------|-------------------|
| | 281+40.70 to 283+04.50 Lt - Stage II | 164 | 4" White Edgeline |
| | 283+04.50 to 283+57.50 Lt - Stage II | 53 | 4" White Edgeline |
| | 283+57.50 to 286+03.50 Lt - Stage II | 246 | 4" White Edgeline |
| | 286+03.50 to 287+53.50 Lt - Stage II | 150 | 4" White Edgeline |
| | 287+53.50 to 288+90.50 Lt - Stage II | 141 | 4" White Edgeline |
| | 281+40.70 to 283+07.10 Rt - Stage III | 167 | 4" White Edgeline |
| | 286+47.50 to 288+91.50 Rt - Stage III | 216 | 4" White Edgeline |
| Total = | | 1137 | |

70300520 Pavement Marking Tape, Type III 4"

| Location | Sta. | Foot | Description |
|----------|---------------------------------------|------|--------------------|
| | 281+40.70 to 281+57.50 Rt - Stage II | 18 | 4" Yellow Edgeline |
| | 281+57.50 to 283+57.50 Rt - Stage II | 200 | 4" Yellow Edgeline |
| | 283+57.50 to 286+03.50 Rt - Stage II | 246 | 4" Yellow Edgeline |
| | 286+03.50 to 287+28.50 Rt - Stage II | 125 | 4" Yellow Edgeline |
| | 287+28.50 to 288+28.50 Rt - Stage II | 100 | 4" Yellow Edgeline |
| | 281+40.70 to 282+00.70 Lt - Stage III | 60 | 4" Yellow Edgeline |
| | 282+00.70 to 283+57.50 Lt - Stage III | 158 | 4" Yellow Edgeline |
| | 283+57.50 to 286+03.50 Lt - Stage III | 246 | 4" Yellow Edgeline |
| | 286+03.50 to 286+60.24 Lt - Stage III | 57 | 4" Yellow Edgeline |
| | 286+60.24 to 288+90.50 Lt - Stage III | 234 | 4" Yellow Edgeline |
| | 283+07.10 to 283+57.50 Rt - Stage III | 51 | 4" White Edgeline |
| | 283+57.50 to 286+03.50 Rt - Stage III | 246 | 4" White Edgeline |
| | 286+03.50 to 286+47.50 Rt - Stage III | 44 | 4" White Edgeline |
| Total = | | 1784 | |

70300570 Pavement Marking Tape, Type III 24"

| Location | Sta. | Foot | Description |
|----------|--------------|------|-------------|
| | 281+40.70 Rt | 12 | Solid White |
| | 288+90.50 Lt | 12 | Solid White |
| Total = | | 24 | |

70301000 Work Zone Pavement Marking Removal

| Location | Sta. | Sq. Ft. | Description |
|----------|---------------------------------------|---------|----------------------|
| | 281+40.70 to 283+04.50 Lt - Stage II | 54.1 | 4" White Edgeline |
| | 283+04.50 to 283+57.50 Lt - Stage II | 17.5 | 4" White Edgeline |
| | 283+57.50 to 286+03.50 Lt - Stage II | 81.2 | 4" White Edgeline |
| | 286+03.50 to 287+53.50 Lt - Stage II | 49.5 | 4" White Edgeline |
| | 287+53.50 to 288+90.50 Lt - Stage II | 46.5 | 4" White Edgeline |
| | 281+40.70 to 283+07.10 Rt - Stage III | 55.1 | 4" White Edgeline |
| | 286+47.50 to 288+91.50 Rt - Stage III | 71.3 | 4" White Edgeline |
| | 281+40.70 to 281+57.50 Rt - Stage II | 5.9 | 4" Yellow Edgeline |
| | 281+57.50 to 283+57.50 Rt - Stage II | 66.0 | 4" Yellow Edgeline |
| | 283+57.50 to 286+03.50 Rt - Stage II | 81.2 | 4" Yellow Edgeline |
| | 286+03.50 to 287+28.50 Rt - Stage II | 41.3 | 4" Yellow Edgeline |
| | 287+28.50 to 288+28.50 Rt - Stage II | 32.8 | 4" Yellow Edgeline |
| | 281+40.70 to 282+00.70 Lt - Stage III | 19.8 | 4" Yellow Edgeline |
| | 282+00.70 to 283+57.50 Lt - Stage III | 52.0 | 4" Yellow Edgeline |
| | 283+57.50 to 286+03.50 Lt - Stage III | 81.2 | 4" Yellow Edgeline |
| | 286+03.50 to 286+60.24 Lt - Stage III | 17.8 | 4" Yellow Edgeline |
| | 286+60.24 to 288+90.50 Lt - Stage III | 77.3 | 4" Yellow Edgeline |
| | 283+07.10 to 283+57.50 Rt - Stage III | 16.8 | 4" White Edgeline |
| | 283+57.50 to 286+03.50 Rt - Stage III | 77.3 | 4" White Edgeline |
| | 286+03.50 to 286+47.50 Rt - Stage III | 14.5 | 4" White Edgeline |
| | 281+40.70 Rt | 24.0 | Solid White Stop Bar |
| | 288+90.50 Lt | 24.0 | Solid White Stop Bar |
| Total = | | 1006.9 | |