

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
U.S. 20	6B1M	WINNEBAGO COUNTY	13	2.
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT-		

CONTRACT • 64074

SUMMARY OF QUANTITY

SFTY-2A
100% STATE

CODE NO.	ITEM	UNIT	QUANTITY
Z0006220	BRIDGE DECK HYDROSCARIFICATION 2 1/4"	SQ YD	1,463
50300260	BRIDGE DECK GROOVING	SQ YD	1,366
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	1
67100100	MOBILIZATION	L SUM	1
70100325	TRAFFIC CONTROL AND PROTECTION, STANDARD 701423	EACH	1
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1
70100805	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	L SUM	1
* 70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	21,030
70400100	TEMPORARY CONCRETE BARRIER	FOOT	700
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1400
* 78001110	PAINT PAVEMENT MARKING-LINE 4"	FOOT	5,000
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1,485
X0322185	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/4 INCHES	SQ YD	1,463
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	8
* Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2
* Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	4
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	151
X0636700	CLEANING AND PAINTING BEARINGS	EACH	24

*SPECIALTY ITEM

DESIGNED	M.R./M.A.
CHECKED	M.S./H.T.
DRAWN	R.K./M.A.
CHECKED	M.S./H.T./M.R.

SUMMARY OF QUANTITIES
US 20 OVER KISHWAUKEE RIVER
FAP ROUTE 525 (US20), SECTION (6B)M
WINNEBAGO COUNTY
STATION 84+88.30
STRUCTURE NO. 101-0073 & 101-0074

SCALE: NONE DATE: JANUARY, 2008
Soodan & Associates, Inc.
100 North LaSalle Street, Suite 1800
Chicago, Illinois 60602

Soodan