

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
U.S. 20	6B1M	WINNEBAGO COUNTY	13	3
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT-	

CONTRACT # 64074

SHEET NO. 1  
4 SHEETS

GENERAL NOTES

Plan dimensions and details relative to existing plans are subject to routine variations. The Contractor shall field verify existing dimensions and details affecting new construction and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in scope of the work, however, the Contractor will be paid for the quantity actually furnished based upon the unit price bid for the work.

Engineer should record the deck repair areas in order to document as-built conditions for future reference.

The existing structural steel coating contains lead. The Contractor shall take appropriate precautions to deal with the presence of lead on this project.

Color of the paint used shall be Interstate Green, Munsell No. 7.5G 4/8.

SCOPE OF WORK

Utilizing staged construction remove & replace existing wearing surface with new Bridge Deck Latex Concrete Overlay, 2 1/4".  
Clean & paint existing rocker bearing assembly at abutments.

DESIGNED	M.R./M.A.
CHECKED	M.S./H.T.
DRAWN	R.K./M.A.
CHECKED	M.S./H.T./M.R.

GENERAL NOTES

US 20 OVER KISHWAUKEE RIVER  
FAP ROUTE 525 (US20), SECTION (6B1M)  
WINNEBAGO COUNTY  
STATION 84+88.30  
STRUCTURE NO. 101-0073 & 101-0074

SCALE: NONE DATE: JANUARY, 2008  
**Soodan** Soodan & Associates, Inc.  
100 North LaSalle Street, Suite 1800  
Chicago, Illinois 60602