

SUMMARY OF QUANTITIES

CONSTRUCTION CODE TYPE: SFTY-2A

| CODE NO. | ITEM | UNIT | RURAL 100% STATE TOTAL QUANTITY |
|-----------|--|-------|---------------------------------|
| 50102400 | CONCRETE REMOVAL | CU YD | 1.4 |
| 50300255 | CONCRETE SUPERSTRUCTURE | CU YD | 1.4 |
| 50500405 | FURNISHING AND ERECTING STRUCTURAL STEEL | POUND | 7350 |
| 50501110 | STRUCTURAL STEEL REMOVAL | POUND | 6670 |
| 67100100 | MOBILIZATION | L SUM | 1 |
| 70100100 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701316 | EACH | 1 |
| 70100205 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701401 | EACH | 1 |
| 70100450 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701201 | L SUM | 1 |
| 70103820 | TRAFFIC CONTROL TEMPORARY FREEWAY ENDING | EACH | 1 |
| 70106500 | TEMPORARY BRIDGE TRAFFIC SIGNALS | EACH | 1 |
| *78001110 | PAINT PAVEMENT MARKING - LINE 4" | FOOT | 1020 |
| 78300100 | PAVEMENT MARKING REMOVAL | SQ FT | 340 |
| *X0324952 | DETOUR SIGNING | L SUM | 1 |
| *X7200201 | WIDTH RESTRICTION SIGNING | L SUM | 1 |
| *Z0030250 | IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3 | EACH | 3 |
| Z0073300 | TEMPORARY SHORING AND CRIBBING | L SUM | 1 |
| Z0073351 | TEMPORARY SLAB SUPPORT SYSTEM | L SUM | 1 |

***SPECIALTY ITEM**

| | | | | | | | | | | | |
|--|---------------------------|-----------------------------|-----------|---|------------------------------|-------------------------|--------------------------|---------------------------|--------------------|--------------------|--|
| FILE NAME : c:\projects\mhd07\05000051\05000051.dgn | USER NAME : vaninger.j | DESIGNED - RON WOODSHANK | REVISED - | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | SUMMARY OF QUANTITIES | F.A.I. RTE. 80 | SECTION (50-3HB-F-1)I | COUNTY LASALLE | TOTAL SHEETS 11 | SHEET NO. 3 | |
| PLOT SCALE = 1/8" = 100'-0" | | | | SCALE: | | SHEET NO. 1 OF 1 SHEETS | | STA. | | TO STA. | |
| PLOT DATE = Feb 11, 2008 - 07:21:02 AM | | | | DATE | | FED. ROAD DIST. NO. | | ILLINOIS FED. AID PROJECT | | CONTRACT NO. 66758 | |