

SUMMARY OF QUANTITIES			100% STATE TOTAL QUANTITIES		CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		Y030-1E LIGHTING			
67100100	MOBILIZATION	L SUM	1	1			
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1			
80400100	ELECTRIC SERVICE INSTALLATION	EACH	5	5			
81021330	CONDUIT PUSHED, 2" DIA., PVC	FOOT	1419	1419			
81021350	CONDUIT PUSHED, 3" DIA., PVC	FOOT	68	68			
81603010	UNIT DUCT, 600V, 2-1C NO.10, 1/C NO.10 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT	7554	7554			
81603025	UNIT DUCT, 600V, 2-1C NO.4, 1/C NO.4 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	1156	1156			
81603035	UNIT DUCT, 600V, 2-1C NO.6, 1/C NO.6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	1316	1316			
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	7909	7909			
82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	48	48			
82500510	LIGHTING CONTROLLER TYPE CB-RCS 60AMP - 240VOLT	EACH	1	1			
82500605	LIGHTING CONTROLLER PHOTOCCELL RELAY	EACH	4	4			
83003600	LIGHT POLE, ALUMINUM, 45 FT. M.H., 15 FT. DAVIT ARM	EACH	48	48			
83600355	LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 8" X 6'	EACH	48	48			
83800650	BREAKAWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN	EACH	192	192			
84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	8	8			