

SUMMARY OF QUANTITIES

FAP ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
592	121-1R, 121HVB	ST CLAIR	239	5

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		I000-2A	X171-5B	Y031-1F			
				80% FEDERAL / 20% IDOT	80% FEDERAL / 20% IDOT	ST. PAUL DR. 80% FED. / 13% IDOT / 7% CAHOKIA	RANGE LANE 80% FED. / 10% IDOT / 10% CAHOKIA	RESURFACING / INNERCONNECT 80% FEDERAL / 20% IDOT	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	216	216					
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	542	542					
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	100	100					
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	1,358	1,358					
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	9,458	9,458					
42400440	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH, SPECIAL	SQ FT	807	807					
42400800	DETECTABLE WARNINGS	SQ FT	70	70					
44000100	PAVEMENT REMOVAL	SQ YD	29,909	29,909					
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	51,364	51,364					
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	1,164	1,164					
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	8,650	8,650					
44000300	CURB REMOVAL	FOOT	723	723					
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	11,749	11,749					
44000600	SIDEWALK REMOVAL	SQ FT	15,417	15,417					
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	32,588	32,588					
44002805	ISLAND REMOVAL	SQ FT	188	188					
44003100	MEDIAN REMOVAL	SQ FT	4,703	4,703					
44004250	PAVED SHOULDER REMOVAL	SQ YD	5,955	5,955					
44200089	PAVEMENT PATCHING, TYPE I, 8 INCH	SQ YD	50	50					
44200094	PAVEMENT PATCHING, TYPE II, 8 INCH	SQ YD	53	53					
44200099	PAVEMENT PATCHING, TYPE III, 8 INCH	SQ YD	36	36					
44200101	PAVEMENT PATCHING, TYPE IV, 8 INCH	SQ YD	354	354					
44200188	PAVEMENT PATCHING, TYPE I, 16 INCH	SQ YD	50	50					
44200192	PAVEMENT PATCHING, TYPE II, 16 INCH	SQ YD	392	392					
44200196	PAVEMENT PATCHING, TYPE III, 16 INCH	SQ YD	784	784					
44200198	PAVEMENT PATCHING, TYPE IV, 16 INCH	SQ YD	1,500	1,500					
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	34,038	34,038					
48101600	AGGREGATE SHOULDERS, TYPE B 8"	SQ YD	1,501	1,501					
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	237	237					
48203054	HOT-MIX ASPHALT SHOULDERS, 14 1/4"	SQ YD	5,995	5,995					
48203100	HOT-MIX ASPHALT SHOULDERS	TON	665	665					
50105220	PIPE CULVERT REMOVAL	FOOT	274	274					
50200100	STRUCTURE EXCAVATION	CU YD	502		502				
50300225	CONCRETE STRUCTURES	CU YD	506.0		506.0				
50300255	CONCRETE SUPERSTRUCTURE	CU YD	479.0		479.0				
50300260	BRIDGE DECK GROOVING	SQ YD	1,094		1,094				
50300300	PROTECTIVE COAT	SQ YD	1,639		1,639				
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1				
50500505	STUD SHEAR CONNECTORS	EACH	6,204		6,204				
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	142,480		142,480				

PLOT DATE = 1/30/2008
 FILE NAME = H:\P\21015\1\1\01015\1\1\01015.dgn
 PLOT SCALE = 0.0000 / IN.
 USER NAME = MUSER8