

SUMMARY OF QUANTITIES

FAP NO	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
592	121-1R, 121HVB	ST CLAIR	239	6

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		I000-2A	X171-5B	Y031-1F		
				80% FEDERAL / 20% IDOT	80% FEDERAL / 20% IDOT	ST. PAUL DR. 80% FED. / 13% IDOT / 7% CAHOKIA	RANGE LANE 80% FED. / 10% IDOT / 10% CAHOKIA	RESURFACING / INNERCONNECT 80% FEDERAL / 20% IDOT
50800515	BAR SPLICERS	EACH	160		160			
50901730	BRIDGE FENCE RAILING	FOOT	324		324			
51100100	SLOPE WALL 4 INCH	SQ YD	119		119			
51100500	BITUMINOUS COATED AGGREGATE SLOPEWALL 6"	SQ YD	1,014		1,014			
51200958	FURNISHING METAL PILES(SHELL) 14" X 0.250"	FOOT	5,426		5,426			
51202305	DRIVING PILES	FOOT	5,426		5,426			
51203200	TEST PILE METAL SHELLS	EACH	4		4			
51500100	NAME PLATES	EACH	1		1			
54001000	BOX CULVERT END SECTIONS	EACH	2	2				
54010402	PRECAST CONCRETE BOX CULVERT 4' X 2'	FOOT	59.0	59.0				
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	110	110				
542A0235	PIPE CULVERTS, CLASS A, TYPE 1 30"	FOOT	432	432				
542A1069	PIPE CULVERTS, CLASS A, TYPE 2 24"	FOOT	112	112				
542A2761	PIPE CULVERTS, CLASS A, TYPE 4 36"	FOOT	189	189				
542A2773	PIPE CULVERTS, CLASS A, TYPE 4 48"	FOOT	166	166				
542A5479	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 24"	FOOT	49	49				
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	151	151				
54213450	END SECTIONS 15"	EACH	6	6				
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	3	3				
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	7	7				
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	2	2				
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	2	2				
54213693	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 48"	EACH	2	2				
54214509	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 24"	EACH	2	2				
54215547	METAL END SECTIONS 12"	EACH	4	4				
55019500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	FOOT	698	698				
55019600	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 15"	FOOT	205	205				
55019700	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 18"	FOOT	107	107				
55021600	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 12"	FOOT	87	87				
55021700	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 15"	FOOT	380	380				
55022000	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 24"	FOOT	273	273				
55100200	STORM SEWER REMOVAL 6"	FOOT	134	134				
55100500	STORM SEWER REMOVAL 12"	FOOT	1,307	1,307				
55100700	STORM SEWER REMOVAL 15"	FOOT	826	826				
55100900	STORM SEWER REMOVAL 18"	FOOT	427	427				
55101100	STORM SEWER REMOVAL 21"	FOOT	133	133				

PLOT DATE = 1/30/2008
 FILE NAME = H:\P\210105\Micro-cast\Design\plc062.dgn
 PLOT SCALE = 100.0000 / IN.
 USER NAME = BUSERB