

# SUMMARY OF QUANTITIES

FAP ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
592	121-1R, 121HVB	ST CLAIR	239	9

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		1000-2A	X171-5B	Y031-1F			
				80% FEDERAL / 20% IDOT	80% FEDERAL / 20% IDOT	ST. PAUL DR. 80% FED. / 13% IDOT / 7% CAHOKIA	RANGE LANE 80% FED. / 10% IDOT / 10% CAHOKIA	RESURFACING / INNERCONNECT 80% FEDERAL / 20% IDOT	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	30	30					
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2					
* 80500100	SERVICE INSTALLATION, TYPE A	EACH	2			1	1		
* 81000300	CONDUIT IN TRENCH, 1" DIA., GALVANIZED STEEL	FOOT	31			15	16		
* 81000500	CONDUIT IN TRENCH, 1 1/2" DIA., GALVANIZED STEEL	FOOT	31			15	16		
* 81012300	CONDUIT IN TRENCH, 1" DIA., PVC	FOOT	1,454			939	515		
* 81012400	CONDUIT IN TRENCH, 1 1/4" DIA., PVC	FOOT	274			48	226		
* 81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	82			35	47		
* 81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	2,637			205	291	2,141	
* 81012700	CONDUIT IN TRENCH, 2 1/2" DIA., PVC	FOOT	54				54		
* 81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	301			95	206		
* 81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	94				94		
* 81013100	CONDUIT IN TRENCH, 5" DIA., PVC	FOOT	174			9	165		
* 81013200	CONDUIT IN TRENCH, 6" DIA., PVC	FOOT	16				16		
* 81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	23			6	10	7	
* 81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	2			1	1		
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	4,894			1,272	1,481	2,141	
* 85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	2			1	1		
* 85900100	TRANSCEIVER	EACH	2			1	1		
* 87301115	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 12 2C	FOOT	1,642				1,642		
* 87301125	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 12 3C	FOOT	1,698				1,698		
* 87301145	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 12 5C	FOOT	3,936			1,521	2,367	48	
* 87301155	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 12 7C	FOOT	2,370			452	1,918		
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	9,585			3,037	6,548		
* 87301615	ELECTRIC CABLE IN CONDUIT, COMMUNICATION NO. 16 6 PAIR	FOOT	2,854					2,854	
* 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	31			15	16		
* 87502680	TRAFFIC SIGNAL POST, ALUMINUM 14 FT.	EACH	1			1			
* 87700240	STEEL MAST ARM ASSEMBLY AND POLE, 40 FT.	EACH	3			2	1		
* 87700280	STEEL MAST ARM ASSEMBLY AND POLE, 48 FT.	EACH	1				1		
* 87700290	STEEL MAST ARM ASSEMBLY AND POLE, 50 FT.	EACH	1				1		
* 87700310	STEEL MAST ARM ASSEMBLY AND POLE, 54 FT.	EACH	2			1	1		
* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	3			3			
* 87800200	CONCRETE FOUNDATION, TYPE D	FOOT	8			4	4		
* 87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	111			47	64		
* 88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	8			3	4	1	
* 88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	12			6	6		
* 88040150	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	5			1	4		

\* SPECIALTY ITEM