

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
270	60-1,2,3,4,51	MADISON	46	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		90% FED 10% STATE SFTY-4A	-----	-----
20200100	EARTH EXCAVATION	CU YD	1541	1541		
25000210	SEEDING, CLASS 2A	ACRE	5.7	5.7		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	513	513		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	513	513		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	513	513		
25100105	MULCH, METHOD 1	ACRE	5.7	5.7		
28000500	INLET AND PIPE PROTECTION	EACH	8	8		
28000700	MULCH, METHOD 1	ACRE	5.7	5.7		
48203013	HOT-MIX ASPHALT SHOULDERS, 4"	SQ YD	14023	14023		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3		
67100100	MOBILIZATION	L SUM	1	1		
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1		
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	40	40		
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	20	20		
80300100	LOCATING UNDERGROUND CABLE	FOOT	100	100		
X0321472	REMOVE TEMPORARY CONCRETE BARRIER	FOOT	180	180		
X0325589	HIGH TENSION CABLE MEDIAN BARRIER	FOOT	32025	32025		
X0325590	HIGH TENSION CABLE MEDIAN BARRIER TERMINAL	EACH	28	28		
Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	24	24		
© 20076600	TRAINERS	HOUR	500	500		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		-----	-----	-----