

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	***	22	13
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		

- * FAS 1909 & FAP 322
- ** D9 PAVEMENT PRESERVATION FY08
- *** JACKSON AND UNION COUNTIES

FAS 1909 (IL 127) PAVEMENT MARKING SCHEDULE
LOCATION 3

STATION TO STATION	PAINT PAVEMENT MARKING			TEMPORARY	NOTES		
	4 INCH WHITE	4 INCH YELLOW	4 INCH SKIP-DASH YELLOW	4 INCH			
	FOOT	FOOT	FOOT	FOOT			
IL 127 - STA. 335+53 TO STA. 227+32							
LT & RT	335+53.0	TO	344+07.4	1,709	1,709	Edge line	
EQ STA 344+07.4 (BK.) = STA. 6+06.7 (AH.)							
LT & RT	6+06.7	TO	79+77.7	14,742	14,742	Edge line	
EQ STA 79+77.7 (BK.) = STA. 80+07.7 (AH.)							
LT & RT	80+07.7	TO	138+96.2	11,777	11,777	Edge line	
EQ STA 138+96.2 (BK.) = STA. 139+83.1 (AH.)							
LT & RT	139+83.1	TO	227+32.0	17,498	17,498	Edge line	
LT	335+53.0	TO	22+71.2		2,519	No Passing Zone	
LT	31+76.9	TO	131+96.1		9,989	No Passing Zone	
LT	142+64.7	TO	186+77.4		4,413	No Passing Zone	
LT	195+93.5	TO	227+32.0		3,139	No Passing Zone	
RT	335+53.0	TO	12+72.7		1,520	No Passing Zone	
RT	23+05.5	TO	118+55.0		9,520	No Passing Zone	
RT	128+73.6	TO	176+59.3		4,699	No Passing Zone	
RT	185+92.2	TO	227+32.0		4,140	No Passing Zone	
	12+72.0	TO	31+76.9		476		
	118+55.0	TO	128+73.6		255		
	131+96.2	TO	142+64.7		982		
	176+59.3	TO	185+92.2		933		
	186+77.4	TO	195+93.5		916		
SUB-TOTALS				45,726	39,939	3,562	89,227
TOTALS				89,227	89,227		

PLT FILE NAME = 12/27/2007
 FILE NAME = 186487.mxd
 PLOT SCALE = 1/8" = 1'-0"
 USER NAME = moorchr