

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
F.A.P. 782	115BR-1	HARDIN	83	6
FED. ROAD DIST. NO.		ILLINOIS	CONTRACT NO. 78026	

MAINTENANCE OF TRAFFIC								
LOCATION	TEMPORARY CONCRETE BARRIER	TEMPORARY TRAFFIC BARRIER TERMINAL TYPE 11	RELOCATE TEMPORARY CONCRETE BARRIER	BARRIER WALL MARKERS	TEMPORARY BRIDGE TRAFFIC SIGNALS	TEMPORARY RUMBLE STRIPS	IMPACT ATTENUATORS TEMPORARY (NON-REDIRECTIVE) TEST LEVEL 3	IMPACT ATTENUATORS RELOCATE (NON-REDIRECTIVE) TEST LEVEL 3
	FOOT	EACH	FOOT	EACH	EACH	EACH	EACH	EACH
STAGE I								
924+09.00 TO 931+80.00					1	6	2	
925+86.98 TO 927+24.48	137.5			7				
927+14.19 TO 927+24.48		1						
928+07.40 TO 928+17.69		1						
928+07.40 TO 929+57.40	150			7				
STAGE II								
924+59.00 TO 931+30.00								2
925+70.00 TO 927+07.50			137.5					
927+07.50 TO 928+20.00	112.5			5				
928+20.00 TO 929+70.00			150					
TOTAL	400	2	287.5	19	1	6	2	2

PAVEMENT MARKING SCHEDULE									
LOCATION	TEMPORARY			EPOXY PAVEMENT MARKING PERMANENT		WORK ZONE PAVEMENT MARKING REMOVAL	PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL
	24" SINGLE WHITE STOP BAR	4" SINGLE WHITE EDGE LINE	4" SKIPPED DASHED YELLOW CENTERLINE	4" SINGLE WHITE EDGE LINE	4" SKIPPED DASHED YELLOW CENTERLINE				
	FOOT	FOOT	FOOT	FOOT	FOOT				
FAP 782 IL RTE 1									
STAGE I									
RT. STA. 924+09 TO RT. STA. 931+80							206		
LT. STA. 924+09 TO LT. STA. 931+80							257		
CL. STA. 924+09 TO CL. STA. 931+80							45		11
RT. STA. 925+65 TO RT. STA. 928+50							95		
RT. STA. 925+65							24		
LT. STA. 929+85							24		
RT STA. 924+09	12								
LT. STA. 924+09 TO RT. STA. 931+80		771					254		
RT. STA. 924+09 TO LT. STA. 926+24		215					71		
LT. STA. 926+24 TO LT. STA. 929+20		296					98		
LT. STA. 929+20 TO RT. STA. 931+80		260					86		
LT STA. 931+80	12								
STAGE II									
RT STA. 924+09							24		
RT. STA. 924+42 TO RT. STA. 930+58		616					203		
LT. STA. 924+69 TO RT. STA. 926+20		151					50		
RT. STA. 926+20 TO RT. STA. 929+20		300					99		
RT. STA. 929+20 TO LT. STA. 931+15		195					64		
LT STA. 931+80							24		
RT. STA. 924+09 TO RT. STA. 931+80		771		771					
LT. STA. 924+09 TO LT. STA. 931+80		771		771					
CL. STA. 924+09 TO CL. STA. 931+80			193		193			11	
SUBTOTAL	24	4346	193	1542	193	973	651	11	11
TOTAL	24		4539		1735	973	651	11	11

GUARDRAIL				
	GUARDRAIL REMOVAL	* VERTICAL ADJUSTMENT OF GUARDRAIL	TRAFFIC BARRIER TERMINAL TYPE 6A	GUARDRAIL MARKERS
	FOOT	FOOT	EACH	EACH
STAGE I				
RT. STA. 926+40.76 TO RT. STA. 926+84.66	44			
RT. STA. 926+40.76 TO RT. STA. 926+84.66			1	
RT. STA. 926+15.76 TO RT. STA. 926+40.76		25		
RT. STA. 928+29.57 TO RT. STA. 928+73.47	44			
RT. STA. 928+29.57 TO RT. STA. 928+73.47			1	
RT. STA. 928+73.47 TO RT. STA. 928+98.47		25		
RT. STA. 926+40.76 TO RT. STA. 928+73.47				4
STAGE II				
LT. STA. 926+56.53 TO LT. STA. 927+00.43	44			
LT. STA. 926+56.53 TO LT. STA. 927+00.43			1	
LT. STA. 926+31.53 TO LT. STA. 926+56.53		25		
LT. STA. 928+45.34 TO LT. STA. 928+89.24	44			
LT. STA. 928+45.34 TO LT. STA. 928+89.24			1	
LT. STA. 928+89.24 TO LT. STA. 929+14.24		25		
LT. STA. 926+56.53 TO LT. STA. 928+89.24				4
TOTAL	176	100	4	8

* COST OF VERTICAL ADJUSTMENT OF GUARDRAIL IS INCLUDED IN TRAFFIC BARRIER TERMINAL TYPE 6A

HAMPTON, LENZINI & RENWICK, INC.
 CIVIL & STRUCTURAL ENGINEERS
 LAND SURVEYORS

HLR

3085 STEVENSON DRIVE, SUITE 201
 SPRINGFIELD, ILLINOIS 62703
 (217) 546-3400

ELGIN • SPRINGFIELD

PROJECT NUMBER: 12-98-0916-1 DATE: 01/18/08
 DESIGNED: L.P.S. CHECKED: S.W.M. DRAWN: D.T.M.

SCHEDULE OF QUANTITIES

IL. ROUTE 1 OVER HARRIS CREEK
F.A.P. ROUTE 782 / SECTION 115BR-1
HARDIN COUNTY
STATION 927+65
STRUCTURE NO. 035-0001