

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
F.A.P. 782	115BR-2	HARDIN	83	8
FED. ROAD DIST. NO.		ILLINOIS	CONTRACT NO. 78026	

MAINTENANCE OF TRAFFIC								
LOCATION	TEMPORARY CONCRETE BARRIER	TEMPORARY TRAFFIC BARRIER TERMINAL TYPE 11	RELOCATE TEMPORARY CONCRETE BARRIER	BARRIER WALL MARKERS	TEMPORARY BRIDGE TRAFFIC SIGNALS	TEMPORARY RUMBLE STRIPS	IMPACT ATTENUATORS TEMPORARY (NON-REDIRECTIVE) TEST LEVEL 3	IMPACT ATTENUATORS RELOCATE (NON-REDIRECTIVE) TEST LEVEL 3
	FOOT	EACH	FOOT	EACH	EACH	EACH	EACH	EACH
STAGE I								
1013+59.75 TO 1017+87.92					1	6	2	
1013+99.75 TO 1015+49.75	150			7				
1015+39.75 TO 1015+49.75		1						
1015+97.92 TO 1016+07.92		1						
1015+97.92 TO 1017+47.92	150			7				
STAGE II								
1013+57.52 TO 1017+92.50								2
1013+87.50 TO 1015+37.5			150					
1015+37.5 TO 1016+12.5	75			4				
1016+12.5 TO 1017+62.50			150					
TOTAL	375	2	300	18	1	6	2	2

PAVEMENT MARKING SCHEDULE											
LOCATION	TEMPORARY				EPOXY PAVEMENT MARKING PERMANENT			WORK ZONE PAVEMENT MARKING REMOVAL	PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL
	24" SINGLE WHITE STOP BAR	4" SINGLE WHITE EDGE LINE	4" SKIPPED DASHED YELLOW CENTERLINE	4" SOLID YELLOW CENTERLINE	4" SINGLE WHITE EDGE LINE	4" SKIPPED DASHED YELLOW CENTERLINE	4" SOLID YELLOW CENTERLINE				
	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT				
FAP 782 IL RTE 1											
STAGE I											
RT. STA. 1012+32.50 TO RT. STA. 1019+23.50									230		
LT. STA. 1012+29.21 TO LT. STA. 1015+04.00									91		
LT. STA. 1016+27.00 TO LT. STA. 1019+12.46									99		
CL. STA. 1012+32.50 TO CL. STA. 1019+23.50									340		10
RT. STA. 1012+32.50 TO RT. STA. 1019+23.50	12	691						205			
LT. STA. 1012+32.50 TO RT. STA. 1014+37.25		205						46			
RT. STA. 1014+37.25 TO RT. STA. 1017+10.42		273						90			
RT. STA. 1017+10.42 TO LT. STA. 1019+23.50	12	213						60			
STAGE II											
RT STA. 1012+32.50								24			
RT. STA. 1012+32.50 TO RT. STA. 1019+23.50								228			
LT. STA. 1012+99.21 TO LT. STA. 1018+92.46		593									
RT. STA. 1012+42.50 TO LT. STA. 1014+37.50		195									
LT. STA. 1014+37.50 TO LT. STA. 1017+12.50		275									
LT. STA. 1017+12.50 TO RT. STA. 1018+63.60		151									
LT. STA. 1012+32.50 TO LT. STA. 1019+23.50								228			
LT STA. 1019+23.50								24			
RT. STA. 1012+32.50 TO RT. STA. 1019+23.50		691			691						
LT. STA. 1012+32.50 TO LT. STA. 1019+23.50		691			691						
LT. CL STA. 1012+32.50 TO LT. CL STA. 1018+00.00				568							
CL STA. 1012+32.50 TO CL STA. 1014+20.00			47			47					
RT. CL STA. 1014+20.00 TO RT. CL STA. 1019+23.50				504			504				
CL STA. 1018+00.00 TO LT. CL STA. 1019+23.50			31				31				
CL STA. 1012+32.50 TO LT. CL STA. 1019+23.50										10	
SUBTOTAL	24	3978	78	1072	1382	78	1072	905	760	10	10
TOTAL	24		5128			2532		905	760	10	10

GUARDRAIL				
	GUARDRAIL REMOVAL	*VERTICAL ADJUSTMENT OF GUARDRAIL	TRAFFIC BARRIER TERMINAL TYPE 6A	GUARDRAIL MARKERS
	FOOT	FOOT	EACH	EACH
STAGE I				
LT. STA. 1014+70.84 TO LT. STA. 1015+14.74	44			
LT. STA. 1014+70.84 TO LT. STA. 1015+14.74			1	
LT. STA. 1014+45.84 TO LT. STA. 1014+70.84		25		
LT. STA. 1016+03.89 TO LT. STA. 1016+47.79	44			
LT. STA. 1016+03.89 TO LT. STA. 1016+47.79			1	
LT. STA. 1016+47.79 TO LT. STA. 1016+72.79		25		
LT. STA. 1014+70.84 TO LT. STA. 1016+47.79				3
STAGE II				
RT. STA. 1014+95.65 TO RT. STA. 1015+39.55	44			
RT. STA. 1014+95.65 TO RT. STA. 1015+39.55			1	
RT. STA. 1014+70.65 TO RT. STA. 1014+95.65		25		
RT. STA. 1016+28.70 TO RT. STA. 1016+72.60	44			
RT. STA. 1016+28.70 TO RT. STA. 1016+72.60			1	
RT. STA. 1016+72.60 TO RT. STA. 1016+97.60		25		
RT. STA. 1014+95.65 TO RT. STA. 1016+72.60				3
TOTAL	176	100	4	6
* COST OF VERTICAL ADJUSTMENT OF GUARDRAIL IS INCLUDED IN TRAFFIC BARRIER TERMINAL TYPE 6A				

HAMPTON, LENZINI & RENWICK, INC.
 CIVIL & STRUCTURAL ENGINEERS
 LAND SURVEYORS

HLR

3085 STEVENSON DRIVE, SUITE 201
 SPRINGFIELD, ILLINOIS 62703
 (217) 546-3400

ELGIN • SPRINGFIELD

PROJECT NUMBER: 12-98-0016-1 DATE: 01/18/08
 DESIGNED: L.F.S. CHECKED: S.W.M. DRAWN: D.T.M.

SCHEDULE OF QUANTITIES

IL. ROUTE 1 OVER BRANCH OF ROCK CREEK
 F.A.P. ROUTE 782 / SECTION 115BR-2
 HARDIN COUNTY
 STATION 1015+71.72
 STRUCTURE NO. 035-0003