

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	*	VARIOUS	17	3
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS	FED. AID PROJECT	

* D-9 SAFETY FY 08-2

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION CONSTRUCTION TYPE CODE	UNIT	TOTAL QUANTITY	HSIP 90% FEDERAL / 10% STATE				
				JEFFERSON COUNTY I-57	JEFFERSON COUNTY I-64	JOHNSON COUNTY I-24	MASSAC COUNTY I-24	WHITE COUNTY I-64
				SFTY-2A	SFTY-2A	SFTY-3N	SFTY-2A	SFTY-2A
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	4.5	1.25	1.25	0.5	0.5	1
Z0030150	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	14			6	8	
20400800	FURNISHED EXCAVATION	CU YD	1040			495	545	
25000350	SEEDING, CLASS 7	ACRE	0.7			0.3	0.4	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	112			48	64	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	84			36	48	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	84			36	48	
25000700	AGRICULTURAL GROUND LIMESTONE	TON	1.4			0.6	0.8	
25001010	SEEDING, CLASS 2 (MODIFIED)	ACRE	0.7			0.3	0.4	
25100115	MULCH, METHOD 2	ACRE	1.4			0.6	0.8	
28000300	TEMPORARY DITCH CHECKS	EACH	7			3	4	
50300225	CONCRETE STRUCTURES	CU YD	17.4			13.3	4.1	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1,714			1257	457	
64200105	SHOULDER RUMBLE STRIP	FOOT	1,271,956	428210	246,845		300,484	296,417
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	1	1	2	3	2
67100100	MOBILIZATION	L SUM	1	0.10	0.10	0.20	0.40	0.20

PLOT DATE: 1/22/2008
 FILE NAME: c:\projects\78045\78045.dwg
 PLOT SCALE: 1/8"=1'-0"
 USER NAME: steph-dg