

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	*	VARIOUS	17	4
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS	FED. AID PROJECT	

* D-9 SAFETY FY 08-2

SEEDING AND EROSION CONTROL SCHEDULE

LOCATION	SEEDING CLASS 2 (MODIFIED) ACRE	SEEDING CLASS 7 (TEMPORARY) ACRE	NITROGEN FERTILIZER NUTRIENTS		PHOSPHORUS FERTILIZER NUTRIENTS POUND	POTASSIUM FERTILIZER NUTRIENTS POUND	AGRICULTURAL GROUND LIMESTONE TON	MULCH METHOD 2 FOR CLASS 2 ACRE	MULCH METHOD 2 FOR CLASS 7 ACRE	TEMPORARY DITCH CHECKS EACH
			CLASS 2 POUND	CLASS 7 POUND						
PIER PROTECTION										
JOHNSON COUNTY										
044-0033	I-24	0.1	12	4	12	12	0.2	0.1	0.1	1
044-0035	I-24	0.1	12	4	12	12	0.2	0.1	0.1	1
044-0036	I-24	0.1	12	4	12	12	0.2	0.1	0.1	1
COUNTY TOTAL		0.3	36	12	36	36	0.6	0.3	0.3	3
MASSAC COUNTY										
064-0013	I-24	0.1	12	4	12	12	0.2	0.1	0.1	1
064-0016	I-24	0.1	12	4	12	12	0.2	0.1	0.1	1
064-0019	I-24	0.1	12	4	12	12	0.2	0.1	0.1	1
064-0022	I-24	0.1	12	4	12	12	0.2	0.1	0.1	1
COUNTY TOTAL		0.4	48	16	48	48	0.8	0.4	0.4	4
TOTALS		0.7	84	28	84	84	1.4	0.7	0.7	7

PIER PROTECTION SCHEDULE

STRUCTURE NUMBER	ROUTE	MILE POST	STATION	COUNTY	SAND MODULE IMPACT ATTENUATOR	FURNISHED EXCAVATION	REINFORCEMENT BARS, EPOXY COATED	CONCRETE STRUCTURES
					EACH	CU YD	POUND	CU YD
044-0033	I-24	MP 3.55	226+34.36	JOHNSON	2	180.00	462	4.1
044-0035	I-24	MP 7.45	431+72.72	JOHNSON	2	155	376	4.3
044-0036	I-24	MP 8.90	508+10.00	JOHNSON	2	160	419	4.9
064-0013	I-24	MP 24.74	95+73.00	MASSAC	2	90		
064-0016	I-24	MP 26.80	204+27.00	MASSAC	2	305		
064-0019	I-24	MP 28.60	298+82.00	MASSAC	2	75.00		
064-0022	I-24	MP 30.80	417+88.45	MASSAC	2	75	457	4.1
TOTALS					14	1040	1714	17.4

PLOT DATE: 1/15/08
 FILE NAME: I:\Projects\78045\080107.dwg
 PLOT SCALE: 1/8"=1'-0"
 USER NAME: jpharrell