

SUMMARY OF QUANTITIES

CODE NO.	ITEM	CONSTRUCTION TYPE CODE	
		UNIT	TOTAL QUANTITIES 90 % FED 10 % STATE
20101400	NITROGEN FERTILIZER NUTRIENT	POUND	23
20101500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	18
20101600	POTASSIUM FERTILIZER NUTRIENT	POUND	18
20200100	EARTH EXCAVATION	CU YD	91
20400800	FURNISHED EXCAVATION	CU YD	135
25000115	SEEDING, CLASS 1B	ACRE	0.25
25000350	SEEDING, CLASS 7	ACRE	0.25
25000700	AGRICULTURAL GROUND LIMESTONE	TON	0.3
25100115	MULCH, METHOD 2	ACRE	0.5
25100630	EROSION CONTROL BLANKET	SQ YD	706
28000300	TEMPORARY DITCH CHECKS	EACH	3
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	804
35300300	PORTLAND CEMENT CONCRETE BASE COURSE 8"	SQ YD	707
40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GALLON	64
40603245	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N105	TON	89
40603575	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N105	TON	59
42001200	PAVEMENT FABRIC	SQ YD	21
44000100	PAVEMENT REMOVAL	SQ YD	242
44004250	PAVED SHOULDER REMOVAL	SQ YD	294
44200942	CLASS B PATCHES, TYPE III, 8 INCH	SQ YD	21
44213200	SAW CUTS	FOOT	84
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	289
67100100	MOBILIZATION	L SUM	1
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	21
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	883
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	12
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	339
* 78000100	THERMOPLASTIC PAVEMENT MARKING-LETTERS AND SYMBOLS	SQ FT	21
* 78000200	THERMOPLASTIC PAVEMENT MARKING-LINE 4"	FOOT	883
* 78000650	THERMOPLASTIC PAVEMENT MARKING-LINE 24"	FOOT	12
78300105	PAVEMENT MARKING REMOVAL	FOOT	336
* 88600100	DETECTOR LOOP, TYPE I	FOOT	80
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	1
Z0017100	DOWEL BARS	EACH	20

*SPECIALTY ITEMS