CONTRACT NO. 83998

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2793	06-00109-00-WR	COOK	24	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

	CODE NUMBER	ITEM	UNIT	CONSTRUCTION TYPE CODE (1000) TOTAL QUANTITY
	20101100	TREE TRUNK PROTECTION	EACH	8
	20101400	NITROGEN FERTILIZER NUTRIENT	POUND	30
	20101500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	30
	20101600	POTASSIUM FERTILIZER NUTRIENT	POUND	30
*	20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	36
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	2,040
	25200100	SODDING	SQ YD	2,040
	28000510	INLET FILTERS	EACH	3
	31101700	SUB-BASE GRANULAR MATERIAL, TYPE B 9"	SQ YD	1,575
	35501312	HOT-MIX ASPHALT BASE COURSE, 7"	SQ YD	793
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	564
	40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	1,350
	40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2,917
	42001300	PROTECTIVE COAT	SQ YD	2,127
	42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	444
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	9,726
	42400800	DETECTABLE WARNINGS	SQ FT	1,000
	44000100	PAVEMENT REMOVAL	SQ YD	300
	44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1½"	SQ YD	2,037
	44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	31,629
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	541
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2,781
	44000600	SIDEWALK REMOVAL	SQ FT	5,709
*	44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	2,000
	44201725	CLASS D PATCHES, TYPE I, 7 INCH	SQ YD	1,690
	44201729	CLASS D PATCHES, TYPE II, 7 INCH	SQ YD	1,010
	44201733	CLASS D PATCHES, TYPE III, 7 INCH	SQ YD	680
*	55019500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	FOOT	16
	55039700	STORM SEWERS TO BE CLEANED	FOOT	500
	60201105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 11 FRAME AND GRATE	EACH	3
	60250200	CATCH BASINS TO BE ADJUSTED	EACH	2

	CODE NUMBER	ITEM	UNIT	CONSTRUCTION TYPE CODE (1000) TOTAL QUANTITY
	60253100	CATCH BASINS TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1
	60255500	MANHOLES TO BE ADJUSTED	EACH	31
	60265700	VALVE VAULTS TO BE ADJUSTED	EACH	32
*	60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	65
	60500080	REMOVING CATCH BASINS TO MAINTAIN FLOW	EACH	1
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	2,784
	67100100	MOBILIZATION	L SUM	1
*	70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4,920
	72000100	SIGN PANEL - TYPE 1	SQ FT	16
	72900100	METAL POST - TYPE A	FOOT	17
△	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	220
△	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4,930
△	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2,450
△	78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	700
△	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1,430
△	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	715
△*	88600600	DETECTOR LOOP REPLACEMENT	FOOT	895
*	X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	6
*	X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	3
*	XX001306	SIDEWALK REMOVAL AND REPLACEMENT	SQ FT	3,412
	XX005656	INLET FILTER CLEANING	EACH	3
+	Z0076600	TRAINEES	HOUR	500

* ITEM REQUIRING SPECIAL PROVISIONS

△ DENOTES SPECIALTY ITEMS

+ Y080

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

VILLAGE OF NILES
CUMBERLAND AVENUE RESURFACING/WIDENING
OAKTON STREET TO CHURCH STREET

SUMMARY OF QUANTITIES

SCALE: VERT. N.T.S. HORIZ. N.T.S.

DRAWN BY JTF

DATE

CHECKED BY BA

PLOT DATE = 2/7/2008
FILE NAME = $$$$035$
PLOT SCALE = $$SCALE$
USER NAME = $$USER$