

SCHEDULES

PLAN
 DESIGNED BY: _____ DATE: _____
 CHECKED BY: _____
 DATE: _____
 PLOTTED BY: _____
 DATE: _____
 NOTE BOOK NO. _____
 DATE OF CHECK: _____
 INC. _____
 CAD FILE NAME: _____

PROFILE
 DESIGNED BY: _____ DATE: _____
 CHECKED BY: _____
 DATE: _____
 PLOTTED BY: _____
 DATE: _____
 NOTE BOOK NO. _____
 DATE OF CHECK: _____
 INC. _____
 CAD FILE NAME: _____

DETECTABLE WARNINGS		
STATION	SQ FT	REMARKS
BOYD ST.		
17+31	8	2'X4'
17+40	8	2'X4'
20+74	8	2'X4'
21+24	8	2'X4'
24+65	8	2'X4'
PROJECT TOTAL	40	

FIRE HYDRANT AND VALVE TO BE MOVED		
STATION	EACH	REMARKS
BOYD STREET		
LT 25+16.35 / LT 25+10	1	
PROJECT TOTAL	1	

MANHOLES, TYPE A, 4' - DIAMETER, TYPE 1 FRAME, CLOSED LID		
STATION	EACH	REMARKS
BOYD ST.		
RT 40+76.88	1	
PROJECT TOTAL	1	

INLETS, SPECIAL		
STATION	EACH	REMARKS
BOYD ST.		
LT 19+00	1	
RT 19+00	1	
LT 20+34	1	
RT 20+34	1	
LT 20+80.50	1	
LT 21+20.50	1	
LT 21+36.53	1	
LT 23+20	1	
RT 23+20	1	
LT 25+33	1	
RT 25+33	1	
DEMENT AVE.		
LT 40+72.38	1	
RT 40+76.88	1	
PROJECT TOTAL	13	

MANHOLES TO BE ADJUSTED		
STATION	EACH	REMARKS
BOYD ST.		
17+27	1	
17+40	1	
20+26	1	
20+92	1	
23+46	1	
24+53	1	
24+72	1	
24+75	1	
27+28	1	
DEMENT AVE.		
40+81	1	
PROJECT TOTAL	10	

INLETS TO BE ADJUSTED		
STATION	EACH	REMARKS
BOYD ST.		
17+57.35	1	
27+93	1	
PROJECT TOTAL	2	

VALVE BOXES TO BE ADJUSTED		
STATION	EACH	REMARKS
BOYD ST.		
17+31	1	Water
17+42.50	1	Water
21+20	1	Water
23+70	1	Water
24+96	1	Water
PROJECT TOTAL	5	

FILLING INLETS		
STATION	EACH	REMARKS
BOYD ST.		
RT 17+43	1	
LT 20+74	1	
RT 20+82	1	
LT 21+12	1	
RT 21+96	1	
LT 24+71	1	
RT 24+77	1	
LT 25+06	1	
PROJECT TOTAL	8	

COMBINATION CONCRETE CURB & GUTTER, TYPE B - 6.18		
STATION	FOOT	REMARKS
BOYD ST.		
NORTH BRINTON - DIXON	426	
NORTH DIXON - DEMENT	512	
NORTH DEMENT - EVERETT	382	
SOUTH BRINTON - EVERETT	1,101	
PROJECT TOTAL	2,421	

STORM SEWERS, SPECIAL 12"		
STATION	FOOT	REMARKS
BOYD ST.		
LT 19+00 - RT 19+00	30	
RT 19+00 - RT 20+13	114	
LT 20+13 - RT 20+13	28	
LT 20+80.50 - LT 20+92.02	26	
LT 21+20.50 - LT 21+36.53	28	
LT 21+36.53 - LT 20+92.02	46	
LT 23+20 - RT 23+20	34	
RT 23+20 - RT 23+45.82	30	
LT 40+72.38 - RT 24+72.14	34	
LT 40+96.68 - LT 40+76.88	20	
LT 25+33 - LT 40+76.88	24	
LT 40+76.88 - RT 24+72.14	46	
RT 25+33 - RT 24+72.14	62	
PROJECT TOTAL	522	

STORM SEWERS, SPECIAL 15"		
STATION	FOOT	REMARKS
BOYD ST.		
RT 20+13 - LT 20+92.02	84	
PROJECT TOTAL	84	

SIGN PANEL - TYPE 1		
STATION	SQ FT	REMARKS
BOYD ST.		
RT 16+69	0.50	4-WAY SIGN
LT 16+86	0.50	4-WAY SIGN
RT 17+24	0.50	4-WAY SIGN
RT 17+25	6.25	30" STOP SIGN
LT 17+49	0.50	4-WAY SIGN
LT 20+80.50	6.25	30" STOP SIGN
DEMENT ST.		
LT 40+81	6.25	30" STOP SIGN
PROJECT TOTAL	21	

METAL POST - TYPE A		
STATION	SQ FT	REMARKS
BOYD ST.		
RT 17+25	12	
LT 20+80.50	12	
DEMENT ST.		
LT 40+81	12	
PROJECT TOTAL	36	

PAINT PAVEMENT MARKING LINE 4"		
STATION	FOOT	REMARKS
BOYD ST.		
LT 21+18 - 22+34.88	130	WHITE LINE
RT 23+74.19 - 24+88	126	WHITE LINE
PROJECT TOTAL	256	

PAINT PAVEMENT MARKING LINE 12"		
STATION	FOOT	REMARKS
BOYD ST.		
LT 21+36 - 22+02	13	WHITE LINE DIAGONALS
RT 23+74.19 - 24+88	35	WHITE LINE DIAGONALS
PROJECT TOTAL	48	

PAINT PAVEMENT MARKING LINE 24"		
STATION	FOOT	REMARKS
BOYD ST.		
LT 17+52	41	STOP BAR
PROJECT TOTAL	41	

ORNAMENTAL FENCE COMPLETE		
STATION	FOOT	REMARKS
BOYD ST.		
RT 23+66 - 24+82	108	
PROJECT TOTAL	108	

BREAKER-RUN CRUSHED STONE		
STATION	TON	REMARKS
BOYD STREET		
CONTINGENCY ITEM	506	AS DIRECTED BY THE ENGINEER
PROJECT TOTAL	506	

CONCRETE STEPS		
STATION	CU YD	REMARKS
BOYD STREET		
RT 20+39	0.44	4' WIDE
RT 23+90.67	0.26	4' WIDE
RT 24+59.54	0.26	4' WIDE
PROJECT TOTAL	0.96	

S:/TRANS/1050D07/COVERETC.DGN

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	WILLET, HOFMANN & ASSOCIATES, INC CONSULTING ENGINEERS DIXON, IL	SCHEDULES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN -	REVISED -			5482	07-00171-00-FP	LEE	25	8	
		CHECKED -	REVISED -			CONTRACT NO. 85429					
		DATE -	REVISED -			FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT					

SCALE: _____ SHEET NO. ____ OF ____ SHEETS STA. _____ TO STA. _____