SUMMARY OF QUANTITIES

I000-1A

	PAY ITEM NUMBER	PAY ITEM NAME	Unit	Quantity
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	74.0
	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	28.0
	20101100	TREE TRUNK PROTECTION	EACH	14.0
	20200100	EARTH EXCAVATION	CU YD	16735.0
	20800150	TRENCH BACKFILL	CU YD	13.9
*	25000200	SEEDING, CLASS 2	ACRE	2.5
*	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	225.2
*	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	225.2
*	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	225.2
	25100115	MULCH, METHOD 2	ACRE	2.5
	25100630	EROSION CONTROL BLANKET	SQ YD	6692.0
	28000300	TEMPORARY DITCH CHECKS	EACH	15.0
	28000500	INLET AND PIPE PROTECTION	EACH	5.0
	28000900	FENCE (EROSION CONTROL)	FOOT	1500.0
	28100201	STONE RIPRAP, CLASS A1	TON	33.9
	28100207	STONE RIPRAP, CLASS A4	TON	90.1
	28200200	FILTER FABRIC	SQ YD	229.0
	28500400	ARTICULATED BLOCK REVETMENT MAT	SQ YD	93.0
	31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	3562.9
	40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	553.3
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2784.5
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	80.0
	40600990	TEMPORARY RAMP	SQ YD	90.4
	40603230	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	1226.4
	40603510	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1041.8
	42001300	PROTECTIVE COAT	SQ YD	225.0
	44000080	HOT-MIX ASPHALT SURFACE REMOVAL (COLD MILLING)	SQ YD	2834.0
	44000100	PAVEMENT REMOVAL	SQ YD	3618.0
	44004000	PAVED DITCH REMOVAL	FOOT	410.0
	48100100	AGGREGATE SHOULDERS, TYPE A	TON	200.3
	48203100	HOT-MIX ASPHALT SHOULDERS, 6"	TON	360.1
	50105220	PIPE CULVERT REMOVAL	FOOT	67.0
	542A1060	PIPE CULVERTS, CLASS A, TYPE 2 15"	FOOT	85.5
	542A1069	PIPE CULVERTS, CLASS A, TYPE 2 24"	FOOT	192.0
	54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	4.0
	54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	3.0
	54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	2.0
	54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	3.0
	54247150	GRATING FOR CONCRETE FLARED END SECTION 30"	EACH	2.0
	54248515	CONCRETE COLLAR	EACH	1.0
	550A0430	STORM SEWER, CLASS A, TYPE 2 30"	FOOT	421.0
	60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1.0
	60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1.0
	60602400	CONCRETE GUTTER (SPECIAL)	FOOT	675.0
	60603300	GUTTER OUTLET	EACH	2.0
	60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	51.9
	60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	102.1
	60625610	ISLAND PAVEMENT (8")	SQ YD	32.2
	70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1.0
	72000100	SIGN PANEL - TYPE 1	SQ FT	79.8
	72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	100.0
*	78000100	THERMOPLASTIC PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	223.6
*	78000200	THERMOPLASTIC PAVEMENT MARKING LINE, 4"	FOOT	7520.0
*	78000600	THERMOPLASTIC PAVEMENT MARKING LINE, 12"	FOOT	227.0
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	126.0
*	78100100	RAISED REFLECTIVE PAVEMENT MARKERS	EACH	60.0
* △	80500200	SERVICE INSTALLATION, TYPE B	EACH	1.0
* △	81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	35.0
* △	81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	45.0
* △	81021350	CONDUIT PUSHED, 3" DIA. PVC	FOOT	200.0
* △	81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	3.0
* △	81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	50.0
* △	85800100	FLASHER CONTROLLER	EACH	1.0
* △	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	250.0
* △	88020110	SIGNAL HEAD, POLYCARONATE, 1-FACE, 1-SECTION, POST MOUNTED	EACH	2.0
* △	88020810	SIGNAL HEAD, POLYCARONATE, 4-FACE, 1-SECTION, SPAN WIRE MOUNTED	EACH	1.0
*	A2001710	TREE, ACER SACCHARUM (SUGAR MAPLE) 1 1/4" CALIPER, BALLED AND BURLAPPED	EACH	6.0
*	X2500200	TEMPORARY SEEDING	POUND	500.0
* △	X8730027	ELECTRIC CABLE IN CONDUIT, 1/C, NO. 6 GROUNDING	FOOT	250.0
	XX005314	BITUMINOUS DRIVEWAY REMOVAL	SQ YD	284
* △	XX005938	SOLAR-POWERED FLASHING BEACON ASSEMBLY	EACH	4
*	XX006733	TOPSOIL EXCAVATION AND PLACEMENT, 4"	SQ YD	12011
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1
	4710100	MOBILIZATION	L SUM	1

△ = Y031-1F

* = SPECIALTY ITEMS

NOTE:
LOCATION OF TREE, "ACER SACCHARUM (SUGAR MAPLE) 1 1/4" CALIPER, BALLED AND BURLAPPED" TO BE COORDINATED WITH ENGINEER.

FILE NAME =	USER NAME = Ander00846	DESIGNED - MPB	REVISED -
h:\85_jobs\05p2004b\Civil\Sheet\c-60lsum.dgn		DRAWN - RLA	REVISED -
	PLOT SCALE = 10.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 02\18\2008, 03:24 PM	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NTS | SHEET NO. OF SHEETS | STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
464	07-00014-00-SP	TAZEWELL	44	3
		CONTRACT NO. 89480		
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT	HS 1467-104	