DRAINAGE TABLE

STATION					PIPE CULVERTS, CLASS A, TYPE 2 15" (FOOT)	PIPE CULVERTS, CLASS A, TYPE 2 24" (FOOT)	PRECAST REINFORCED CONCRETE FLARED END SECTION 15" (EACH)	PRECAST REINFORCED CONCRETE FLARED END SECTION 24" (EACH)	PRECAST REINFORCED CONCRETE FLARED END SECTION 30" (EACH)	GRATING FOR CONC. FLARED END SECT. 24" (EACH)	GRATING FOR CONC. FLARED END SECT. 30" (EACH)	STORM SEWERS, CLASS A, TYPE 2 30" (FOOT)	MANHOLES, TYPE A, 4' DIAMETER, TYPE 1 FRAME, CLOSED LID (EACH)	MANHOLES, TYPE A, 5' DIAMETER, TYPE 1 FRAME, CLOSED LID (EACH)	TRENCH BACKFILL (CU YD)	CONCRETE COLLAR (EACH)
107+55.00	30.80' LT	TO	107+90.00	33.00' LT	35		2								3.8	
108+00.00	25.00' RT	TO	108+00.00	25.50' LT	50.5		2								10.2	
108+25.00	30.00' LT	TO	110+25.00	36.50' LT					1		1	198				
110+25.00	36.50' LT													1		
110+25.00	36.50' LT	TO	112+50.00	40.00' LT					1		1	223				
112+85.00	41.75' LT	TO	114+35.00	40.00' LT		150		1		1						
114+48.00	47.40' RT	TO	114+26.50	57.30' RT		22		1		1						
114+48.00	47.40' RT												1			
115+67.67	42.10' LT	TO	115+47.67	41.80' LT		20		1		1						1
			TOTAL		85.5	192	4	3	2	3	2	421	1	1	13.9	1

PAVEMENT MARKING TABLE

STATION					THERMOPLASTIC PAVEMENT MARKING LETTER & SYMBOLS (SQ FT)	4" YELLOW (FOOT)	4" WHITE (FOOT)	12" YELLOW (FOOT)	12" WHITE (FOOT)	24" WHITE (FOOT)	RAISED REFLECTIVE PAVEMENT MARKERS ONE-WAY CRYSTAL (EACH)	TWO-WAY AMBER (EACH)	ONE-WAY AMBER (EACH)
103+20.00	12.00' LT	TO	114+91.39	151.22' LT			1268						
103+20.00	12.00' RT	TO	114+60.12	172.16' RT			1261						
103+20.00	CL	TO	107+48.99	CL		858						10	
115+15.99	148.71' LT	TO	115+87.40	21.33' LT			167						
114+91.83	175.40' RT	TO	115+87.30	19.97' RT			208						
107+48.99	CL	TO	113+25.23	CL									30
113+25.23	CL	TO	114+57.24	CL								6	
113+25.00	12.00' RT	TO	114+57.24	12.00' RT							4		
114+71.88	173.37' RT	TO	114+84.83	41.93' RT								2	
114+84.49	174.61' RT	TO	114+97.44	43.07' RT							4		
115+03.43	150.00' LT	TO	114+91.79	39.55' LT								2	
115+33.98	9.45' LT	TO	115+87.37	9.33' LT			53					1	
115+32.95	2.54' RT	TO	115+87.34	2.67' RT		109					1		
107+48.99	CL	TO	114+57.00	CL		1416							
107+48.99	CL	TO	111+70.00	12.00' RT		842							
111+70.00	12.00' RT	TO	114+57.00	CL		310							
108+69.04	RT	TO	112+70.31	RT				141					
113+25.00	12.00' RT	TO	114+76.56	12.00' RT			152						
114+57.23	CL	TO	114+57.24	12.00' RT						12			
114+40.07	45.14' RT	TO	114+56.46	29.31' RT						23			
114+40.00	12.00' RT	TO	114+72.02	56.28' RT			55						
114+51.62	RT	TO	114+72.02	RT					43				
114+72.02	56.28' RT	TO	114+76.56	11.94' RT			45						
115+03.43	150.00' LT	TO	114+91.79	39.55' LT		222							
114+92.46	39.55' LT	TO	114+79.83	39.55' LT						13			
114+73.67	44.01' LT	TO	114+79.83	39.55' LT						8			
115+08.61	46.70' LT	TO	115+04.18	9.52' LT			37						
115+08.61	46.70' LT	TO	115+33.98	9.50' LT			45						
115+08.17	LT	TO	115+25.56	LT					43				
115+04.18	9.52' LT	TO	115+33.98	9.50' LT			30						
115+25.74	20.51' LT	TO	115+41.53	38.59' LT						24			
115+32.95	2.54' RT	TO	115+34.38	9.45' LT		45				12			
114+84.83	41.93' RT	TO	114+71.88	173.37' RT		264							
114+97.44	43.07' RT	TO	114+84.49	174.61' RT			132						
114+84.83	41.93' RT	TO	114+98.04	41.93' RT						13			
115+03.91	34.59' RT	TO	115+21.02	47.79' RT						22			
113+29.75	21.89' RT	TO			15.6								
113+95.12	21.46' RT	TO			15.6								
114+37.35	31.21' RT	TO			15.6								
113+29.85	2.56' RT	TO			26.0								
114+43.15	2.84' RT	TO			26.0								
114+86.49	56.18' RT	TO			26.0								
115+09.79	54.23' RT	TO			15.6								
115+48.37	1.33' RT	TO			26.0								
115+43.58	23.58' LT	TO			15.6								
114+76.99	155.75' RT	TO			26.0								
114+94.58	157.37' RT	TO			15.6								
			TOTAL		223.6	4066	3454	141	86	126	9	21	30

EROSION CONTROL TABLE

STATION					EROSION CONTROL BLANKET (SQ YD)	TEMPORARY DITCH CHECKS (EACH)	INLET AND PIPE PROTECTION (EACH)	FENCE (EROSION CONTROL) (FOOT)
103+50.00	LT					1		
104+00.00	LT					1		
105+20.00	LT					1		
105+80.50	LT					1		
106+30.00	LT					1		
106+70.00	LT					1		
107+08.00	LT					1		
107+46.00	LT					1		
104+40.00	RT					1		
105+15.00	RT					1		
105+87.50	RT					1		
106+63.00	RT					1		
107+01.00	RT					1		
107+39.00	RT					1		
107+55.00	LT						1	
107+77.00	RT					1		
108+25.00	LT						1	
108+00.00	RT						1	
112+79.75	LT						1	
112+19.92	LT	TO	114+50.00	LT				230
115+47.08	LT	TO	115+87.95	LT				110
115+67.67	LT						1	
103+50.00	LT	TO	113+00.00	LT	3670			
103+50.00	RT	TO	113+00.00	RT	3022			
102+50.00	RT	TO	108+50.00	RT				600
108+70.00	RT	TO	114+30.00	RT				560
TOTAL					6692	15	5	1500

FILE NAME =	USER NAME = Andar02846	DESIGNED - MPB	REVISED -
		DRAWN - RLA	REVISED -
	PLOT SCALE = 13.3423 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 02\14\2008. 11:18 AM	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NTS | SHEET NO. OF SHEETS | STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
464	07-00014-00-SP	TAZEWELL	44	4
		CONTRACT NO. 89480		
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT	HS 1467-104	