

**SUMMARY OF QUANTITIES**

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CH 11	*	EDGAR	160	3
FED. ROAD DIST. NO. 5		ILLINOIS	PROJECT	
* 05-00092-01-PV				

CODE NUMBER	DESCRIPTION	UNITS	80% FED 20% LOCAL 1000-2A QUANTITY
20200100	EARTH EXCAVATION	CU YD	13,017
20400800	FURNISHED EXCAVATION	CU YD	2,456
20800150	TRENCH BACKFILL	CU YD	71
21301048	EXPLORATION TRENCH 48" DEPTH	FOOT	15,947
25000200	SEEDING, CLASS 2	ACRE	13
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1,170
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1,170
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1,170
25100105	MULCH METHOD 1	ACRE	13
28000255	TEMPORARY EROSION CONTROL SEEDING	ACRE	13
28000500	INLET AND PIPE PROTECTION	EACH	32
28100205	STONE RIPRAP, CLASS A3	TON	6.5
28200200	FILTER FABRIC	SQ YD	13
30200550	PROCESSING MODIFIED SOIL 10"	SQ YD	43,766
30201500	LIME	TON	240
30201700	PORTLAND CEMENT	TON	1,329
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	532
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	157
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	41,490
40600300	AGGREGATE (PRIME COAT)	TON	166
40603235	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	10,455
40603515	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	3,972
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACE	TON	50
44000100	PAVEMENT REMOVAL	SQ YD	5,338
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2,946
48203015	HOT-MIX ASPHALT SHOULDERS 4 1/2"	SQ YD	6,636
50105200	REMOVE EXISTING CULVERTS	EACH	29
542A0223	PIPE CULVERTS, CLASS A, TYPE 1, 18"	FOOT	199
542A0229	PIPE CULVERTS, CLASS A, TYPE 1, 24"	FOOT	46
542A0235	PIPE CULVERTS, CLASS A, TYPE 1, 30"	FOOT	39
542A0241	PIPE CULVERTS, CLASS A, TYPE 1, 36"	FOOT	38
542A0253	PIPE CULVERTS, CLASS A, TYPE 1, 48"	FOOT	39
542D0217	PIPE CULVERTS, CLASS D, TYPE 1, 12"	FOOT	224
542D0220	PIPE CULVERTS, CLASS D, TYPE 1, 15"	FOOT	458
542D0223	PIPE CULVERTS, CLASS D, TYPE 1, 18"	FOOT	302

• SEE SPECIAL PROVISIONS

REVISIONS			SUMMARY OF QUANTITIES		DRAWN BY DATE
NO.	DATE	INITIALS	SHILOH ROAD (CH 11) EDGAR COUNTY, ILLINOIS		RLK 7/07
1					CHECKED BY DATE CAS 7/07
2					BOOK NUMBER 469
3					PROJECT NO. 5245
4					SHEET NO.
5					
6					
7					
8					
9					
10					

**HOMER L. CHASTAIN & ASSOCIATES, LLP**  
 CONSULTING ENGINEERS  
 184-00127  
 DECATUR CHICAGO  
 (317) 422-8644 (773) 714-0060  
 ROCKFORD  
 (815) 489-0060