

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CH 11	*	EDGAR	160	11

FED. ROAD DIST. NO. 5 ILLINOIS PROJECT
* 05-00092-01-PV


REMOVAL SCHEDULE

ALIGNMENT	STATION	LOCATION		PAVEMENT REMOVAL (SQ YD)	REMOVE EXISTING CULVERTS (EACH)	REMOVE RIGHT OF WAY MARKERS (EACH)	
		OFFSET	STATION				
SHILOH ROAD (CH11)							
	7+50.00	22.04' Lt	8+00.00	22.00' Rt	122.00		
	8+00.00	22.00' Lt	9+51.20	22.00' Rt	370.00		
CH11 & CH8 INTERSECTION							
			10+25.00	AR		1	
			12+82.00	26.0' Lt		1	
			14+50.00	27.0' Lt		1	
			16+78.00	AR		1	
			36+73.00	28.0' Rt		1	
			37+49.00	AR		1	
			50+11.00	23.5' Lt		1	
			54+24.00	AR		1	
			56+42.00	28.0' Rt		1	
			76+63.00	25.0' Lt		1	
			77+75.00	25.0' Lt		1	
			79+80.00	23.0' Lt		1	
			82+50.00	25.0' Lt		1	
			84+40.00	24.0' Lt		1	
			86+16.00	26.0' Lt		1	
			90+10.00	26.0' Lt		1	
			91+00.00	AR		1	
			102+69.00	AR		1	
			103+32.00	30.5' Lt		1	
			110+21.00	27.9' Lt		1	
			115+41.00	24.0' Lt		1	
			117+16.00	27.0' Rt		1	
			117+47.00	AR		1	
			129+95.00	15.0' Rt		1	
HORACE BROCTON ROAD (CH8)							
	296+00.00	21.00' Lt	296+46.00	22.00' Rt	110.00		
	296+46.00	22.00' Lt	308+00.00	22.00' Rt	2821.00		
			302+23.00	38.0' Rt		1	
			303+73.00	37.8' Rt		1	
			305+62.00	39.0' Rt		1	
			307+00.00	10.5' Lt		1	
			309+61.00	14.6' Lt		1	
	310+00.00	22.00' Lt	314+00.00	22.00' Rt	978.00		
	314+00.00	22.00' Lt	314+75.00	21.22' Rt	180.00		
1900TH ROAD							
	601+63.50	19.10' Rt				1	
PROJECT TOTAL					5,338.00	29	1

PAVEMENT MARKING SCHEDULE

STATION	ALIGNMENT	OFFSET	STATION	ALIGNMENT	OFFSET	POLYUREA PAVEMENT MARKING TYPE 1, LINE			RAISED REFLECTIVE PAVEMENT MARKER (EACH)
						4" WHITE SOLID (FOOT)	4" YELLOW SKIP-DASH (FOOT)	24" WHITE SOLID (FOOT)	
7+50.00	CH 11	LT	9+49.85	CH 11	LT	200.00			
7+50.00	CH 11	CL	9+85.00	CH 11	CL		59.00		3.00
9+49.85	CH 11	LT	308+37.13	CH 8	LT	79.00			
308+38.03	CH 8	LT	10+73.86	CH 11	LT	78.00			
9+91.00	CH 11							29.00	
10+30.00	CH 11	CL	136+00.00	CH 11	CL		3,143.00		157.00
10+33.00	CH 11							29.00	
10+73.86	CH 11	LT	116+29.25	CH 11	LT	10,555.00			
116+29.25	CH 11	LT	601+49.30	1900TH	LT	61.00			
601+52.15	1900TH	LT	117+32.98	CH 11	LT	59.00			
117+32.98	CH 11	LT	136+00.00	CH 11	LT	1,867.00			
7+50.00	CH 11	RT	9+50.03	CH 11	RT	200.00			
9+50.03	CH 11	RT	309+61.87	CH 8	RT	79.00			
309+61.31	CH 8	LT	10+74.03	CH 11	LT	78.00			
10+74.03	CH 11	RT	62+87.33	CH 11	RT	5,213.00			
62+87.33	CH 11	RT	500+47.47	1800TH	RT	59.00			
500+51.34	1800TH	LT	63+91.11	CH 11	LT	62.00			
63+91.11	CH 11	RT	116+32.11	CH 11	RT	5,241.00			
116+32.11	CH 11	RT	602+47.41	1900TH	RT	59.00			
602+50.82	1900TH	LT	117+35.85	CH 11	LT	61.00			
117+35.85	CH 11	RT	136+00.00	CH 11	RT	1,864.00			
296+00.00	CH 8	CL	314+75.00	CH 8	CL		470.00		24.00
296+00.00	CH 8	LT	308+38.03	CH 8	LT	1,238.00			
309+61.31	CH 8	LT	314+75.00	CH 8	LT	514.00			
296+00.00	CH 8	RT	308+37.13	CH 8	RT	1,237.00			
309+61.87	CH 8	RT	314+75.00	CH 8	RT	513.00			
500+22.00	1800TH							24.00	
500+23.00	1800TH	CL	501+48.03	1800TH	CL		125.00		
500+51.34	1800TH	LT	501+48.33	1800TH	LT	97.00			
500+47.47	1800TH	RT	501+48.31	1800TH	RT	101.00			
600+51.58	1900TH	CL	601+77.00	1900TH	CL		125.00		
600+51.58	1900TH	LT	601+52.15	1900TH	LT	101.00			
602+50.82	1900TH	LT	603+31.70	1900TH	LT	81.00			
600+51.58	1900TH	RT	601+49.30	1900TH	RT	98.00			
601+78.00								25.00	
602+22.00								25.00	
602+47.41	1900TH	RT	603+31.69	1900TH	RT	84.00			
602+23.00	1900TH	CL	603+31.67	1900TH	CL		109.00		
ITEM TOTAL						29,879.00	4,031.00	132.00	184.00
PROJECT TOTAL						33,910.00	132.00	184.00	

SCHEDULE OF QUANTITIES

REVISIONS		SHILOH ROAD (CH 11)		DRAWN BY DATE	
No.	DATE	INITIALS	EDGAR COUNTY, ILLINOIS	RLK	7/07
1				CHECKED BY DATE	
2				CAS	7/07
3				BOOK NUMBER	469
4				PROJECT No.	5245
5				SHEET No.	
6					
7				DECATUR CHICAGO (317) 422-8544 (773) 714-0060 ROCKFORD (815) 489-0050	
8				184-001297	
9					
10					