

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CH 11	*	EDGAR	160	12

ROADWAY SCHEDULE

FED. ROAD DIST. NO. 5 ILLINOIS PROJECT
* 05-00092-01-PV

ALIGNMENT	STATION	TO STATION	PROCESSING MODIFIED SOIL 10" (SQ YD)	LIME (TON)	PORTLAND CEMENT (TON)	BITUMINOUS MATERIALS PRIME COAT (GAL)	AGGREGATE PRIME COAT (TON)	AGGREGATE SHOULDERS, TYPE B (TON)	HOT-MIX ASPHALT SHOULDERS 4 1/2" (SQ YD)	POLYMERIZED HOT-MIX ASPHALT SURFACE CSE MIX "C", N70 (TON)	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE IL-19.0 N70 (TON)
SHILOH ROAD (CH 11)	7+50.00	8+00.00	139.00	5.00		131.00	0.50	10.00	22.00	13.00	33.00
	8+00.00	9+00.00	289.00	10.00		274.00	1.10	20.00	44.00	26.00	69.00
CH 11 & CH 8 INTERSECTION			1,309.00	47.00		1,262.00	5.00	60.00	136.00	117.00	318.00
	11+00.00	11+50.00	144.00	5.00		137.00	0.50	10.00	22.00	13.00	34.00
CH 11 & 1800TH ROAD INTERSECTION	11+50.00	62+00.00	14,589.00		523.00	13,820.00	55.40	997.00	2,245.00	1,325.00	3,483.00
			968.00		35.00	921.00	3.70	59.00	136.00	88.00	232.00
CH 11 & 1900TH ROAD INTERSECTION	64+00.00	116+00.00	15,022.00		539.00	14,231.00	56.90	1,026.00	2,311.00	1,365.00	3,586.00
			1,321.00		47.00	1,260.00	5.00	77.00	176.00	118.00	317.00
CH 8 - HORACE BROCTON ROAD	118+00.00	135+00.00	4,911.00		176.00	4,652.00	18.60	336.00	756.00	446.00	1,172.00
	135+00.00	136+00.00	254.00		9.00	238.00	1.00	20.00	44.00	23.00	60.00
CH 11 & CH 8 INTERSECTION	296+00.00	296+46.00	126.00	5.00		118.00	0.50	9.00	20.00	11.00	30.00
	296+46.00	308+00.00	3,334.00	120.00		3,158.00	12.60	228.00	513.00	303.00	796.00
CH 11 & CH 8 INTERSECTION	310+00.00	314+00.00	1,156.00	41.00		1,095.00	4.40	79.00	178.00	105.00	276.00
	314+00.00	314+75.00	204.00	7.00		193.00	0.80	15.00	33.00	19.00	49.00
PROJECT TOTAL			43,766.00	240.00	1,329.00	41,490.00	166.00	2,946.00	6,636.00	3,972.00	10,455.00

SIGNING SCHEDULE

LOCATION	STATION	O/S	SIGN TYPE	RE-ERECT LOCATION		SIGN PANEL TYPE 1 (SQ FT)	METAL POST TYPE B (FOOT)	REMOVE AND RE-ERECT EXISTING SIGN (EACH)	REMOVE AND REPLACE DELINEATORS (EACH)	SIGN REMOVAL
				STATION	O/S					
SHILOH ROAD (CH11)	9+10.80	19.4' LT	ROAD DESIGNATION	9+10.80	20' LT			1		
	9+65.50	19.7' RT	STOP							1
	9+76.55	33.3' RT	R1-1			6.40	11.50			
	10+23.26	33.6' RT	R1-1			6.40	11.50			
	10+32.80	33.6' RT	ROAD DESIGNATION	10+45.00	63' RT			1		
	10+35.30	19.3' LT	STOP							1
	10+44.00	LT & RT							2	
	10+91.00	16.4' RT	ROAD DESIGNATION	10+91.00	20' RT			1		
	14+26.10	16.4' LT	WARNING	14+26.10	20' LT			1		
	16+78.00	LT & RT							2	
37+49.00	LT & RT							2		
54+22.00	LT & RT							2		
75+78.00	LT & RT							2		
91+00.00	LT & RT							2		
102+69.00	LT & RT							2		
117+01.80	22.8' LT	ROAD DESIGNATION	117+30.00	20' LT			1			
HORACE BROCTON ROAD (CH8)	303+87.40	35.5' RT	WARNING	303+87.40	35.5' RT			1		
	308+07.30	2.5' LT	ROAD DESIGNATION	308+07.30	20' LT			1		
	309+89.70	27.8' RT	ROAD DESIGNATION	309+89.70	27.8' RT			1		
1800TH ROAD	500+24.30	28.2' LT	R1-1			6.40	11.50			
	500+35.40	16.1' LT	STOP							1
	500+36.60	23.8' RT	ROAD DESIGNATION	500+36.00	23.8' RT			1		
1900TH ROAD	601+74.50	28.7' RT	R1-1			6.40	11.50			
	601+64.70	19.6' LT	STOP							1
	602+24.10	29.2' LT	R1-1			6.40	11.50			
	602+46.30	15.4' LT	STOP							1
PROJECT TOTAL						32.00	58.00	9.00	14.00	5.00

SCHEDULE OF QUANTITIES

REVISIONS No. DATE INITIALS		SHILOH ROAD (CH 11) EDGAR COUNTY, ILLINOIS		DRAWN BY: RLK DATE: 7/07
				CHECKED BY: CAS DATE: 7/07
				BOOK NUMBER: 469
				PROJECT No.: 5245
				SHEET No.:
				DECATUR CHICAGO (817) 422-8544 (773) 714-0050
				ROCKFORD (815) 489-0050