

SUMMARY OF QUANTITIES

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
I-57	00-00374-03-LS	CHAMPAIGN	21	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO. 91382				

ITEM NUMBER	PAY ITEM	CONSTRUCTION CODE	UNIT	TOTAL QUANTITY
+ 21101615	TOPSOIL FURNISH AND PLACE, 4"	Y003	SO YD	970
+ 25000210	SEEDING, CLASS 2A	Y003	ACRE	0.2
+ 25000400	NITROGEN FERTILIZER NUTRIENT	Y003	POUND	18
+ 25000500	PHOSPHORUS FERTILIZER NUTRIENT	Y003	POUND	18
+ 25000600	POTASSIUM FERTILIZER NUTRIENT	Y003	POUND	18
+ 25100105	MULCH METHOD 1	Y003	ACRE	0.2
+ 25100635	HEAVY DUTY EROSION CONTROL BLANKET	Y003	SO YD	217
+ 25200200	SUPPLEMENTAL WATERING	Y003	UNIT	10
50200100	STRUCTURE EXCAVATION	Y003	CU YD	121
50300225	CONCRETE STRUCTURES	Y003	CU YD	155.6
50800205	REINFORCEMENT BARS, EPOXY COATED	Y003	POUND	10820
50901755	PARAPET RAILING, SPECIAL	Y003	FOOT	539
51201400	FURNISHING STEEL PILES HP10X42	Y003	FOOT	833
51202305	DRIVING PILES	Y003	FOOT	833
51203400	TEST PILE STEEL HP10X42	Y003	EACH	3
+ 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	Y003	EACH	1
+ 63304385	TRAFFIC BARRIER TERMINAL REMOVAL, TYPE 1	Y003	EACH	1
67100100	MOBILIZATION	Y003	L SUM	1
+ 78201000	TERMINAL MARKER - DIRECT APPLIED	Y003	EACH	1
+ 80400100 ⁵	ELECTRIC SERVICE INSTALLATION, SPECIAL	Y003	L SUM EACH	1
+ 81012200	CONDUIT IN TRENCH, 3/4" DIA., PVC	Y003	FOOT	354 317
+ 81012600	CONDUIT IN TRENCH, 2" DIA., PVC	Y003	FOOT	108 205
+ 81021330	CONDUIT PUSHED, 2" DIA., PVC	Y003	FOOT	100 160
+ 81300800	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 18" x 12" x 6"	Y003	EACH	1
81400730	HANDHOLE, COMPOSITE CONCRETE	Y003	EACH	1
+ 81603035	UNIT DUCT, 600V, 2-1C NO. 6, 1/C NO. 6 GROUND (XLP-TYPE USE), 1" DIA. POLYETHYLENE	Y003	FOOT	700
+ 81702450	ELECTRICAL CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3 1/C ^{NO.} 10	Y003	FOOT	1254 1252
+ 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	Y003	FOOT	1161 1171
+ 82500510	LIGHTING CONTROLLER TYPE CB-RCS 60 AMP-240 VOLT	Y003	EACH	1
+ A2002420	TREE, BETULA NIGRA HERITAGE (HERITAGE RIVER BIRCH), 2 1/2" CALIPER, BALLED AND BURLAPPED	Y003	EACH	12
+ D2015401	SHRUB, JUNIPERUS CHINENSIS 'KALLAY'S COMPACTA' (KALLAY COMPACT JUNIPER), 5 GALLON	Y003	EACH	84
+ X0325403	CONDUIT, FLEXIBLE NON-METALLIC, WEATHERPROOF, 2"	Y003	EACH	4
+ XX005856	MULCH - SHREDDED HARDWOOD BARK, 3" DEPTH	Y003	CU YD	40
+ XX006302	NEPETA X FAASSENII 'WALKERS LOW' (WALKERS LOW CATMINT)	Y003	EACH	1000
Z0013798	CONSTRUCTION LAYOUT	Y003	L SUM	1
Z0076600	TRAINEES	Y003	HOUR	
+ XX007293	PERENNIAL, FALLOPIA JAPONICA 'COMPACTA' (COMPACT FLEECE FLOWER), 1 GALLON	Y003	EACH	3480
+ XX007294	PERENNIAL, MISCANTHUS SINENSIS 'PURPURASCENS' (PURPLE SILVER GRASS), 2 GALLON	Y003	EACH	40


ITEM NUMBER	PAY ITEM	CONSTRUCTION CODE	UNIT	TOTAL QUANTITY
+ X8250500	LIGHTING UNIT X COMPLETE, SPECIAL	Y003	EACH	6
+ X0324390	FLOOD LIGHTING UNIT-B, COMPLETE	Y003	EACH	6
+ X007293	MASONRY COLUMN, LARGE	Y003	EACH	2
+ X007294	MASONRY COLUMN, SMALL	Y003	EACH	4
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	Y003	EACH	2
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	Y003	L SUM	1
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	Y003	L SUM	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	Y003	L SUM	1
+ 81018100	CONDUIT PUSHED, 3/4" DIA., GALVANIZED STEEL	Y003	FOOT	120

+ = SPECIALTY ITEMS

p:\d\359\plans\shema\Ssummary of Quantities.dgn 3/24/2008

Revised 3/28/08

* SEE SPECIAL PROVISIONS



DESIGN FIRM REGISTRATION
No. 184-000480
118 SOUTH CLINTON STREET
SUITE 900
CHICAGO, IL 60661
PHONE : 312.848.8900
FAX : 312.848.0204

REVISIONS	
NAME	DATE
RLH	3/18/08

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: As Noted
DATE: 01/04/08

DRAWN BY SLD
CHECKED BY JTP