

SUMMARY OF QUANTITIES


F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1-57	00-00374-03-LS	CHAMPAIGN	21	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CONTRACT NO. 91382

ITEM NUMBER	PAY ITEM	CONSTRUCTION CODE	Y003 TOTAL QUANTITY	ITEM NUMBER	PAY ITEM	CONSTRUCTION CODE	Y003 TOTAL QUANTITY
		UNIT				UNIT	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	970	* XX007295	LIGHTING UNIT A, COMPLETE	EACH	6
25000210	SEEDING, CLASS 2A	ACRE	0.2	* XX007296	LIGHTING UNIT B, COMPLETE	EACH	6
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	18	* XX007297	MASONRY COLUMN, LARGE	EACH	2
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	18	* XX007298	MASONRY COLUMN, SMALL	EACH	4
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	18	70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	2
25100105	MULCH METHOD 1	ACRE	0.2	70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1
* 25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	217	70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1
25200200	SUPPLEMENTAL WATERING	UNIT	10	70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1
50200100	STRUCTURE EXCAVATION	CU YD	121				
50300225	CONCRETE STRUCTURES	CU YD	155.6				
* 50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	10820				
* 50901755	PARAPET RAILING, SPECIAL	FOOT	539				
51201400	FURNISHING STEEL PILES HP10X42	FOOT	833				
51202305	DRIVING PILES	FOOT	833				
51203400	TEST PILE STEEL HP10X42	EACH	3				
63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	1				
* 63304385	TRAFFIC BARRIER TERMINAL REMOVAL, TYPE 1	EACH	1				
67100100	MOBILIZATION	L SUM	1				
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	1				
* 80400100	ELECTRIC SERVICE INSTALLATION	L SUM	1				
81012200	CONDUIT IN TRENCH, 3/4" DIA. PVC	FOOT	317				
81012600	CONDUIT IN TRENCH, 2" DIA. PVC	FOOT	205				
81021330	CONDUIT PUSHED, 2" DIA. PVC	FOOT	160				
81300800	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 18" x 12" x 6"	EACH	1				
81400730	HANDHOLE, COMPOSITE CONCRETE	EACH	1				
81603035	UNIT DUCT, 600V, 2-1C NO. 6, 1/C NO. 6 GROUND (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	700				
81702450	ELECTRICAL CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3 1/C #10	FOOT	1252				
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1171				
82500510	LIGHTING CONTROLLER TYPE CB-RCS 60 AMP 240 VOLT	EACH	1				
* A2002420	TREE, BETULA NIGRA HERITAGE (HERITAGE RIVER BIRCH), 2 1/2" CALIPER, BALLED AND BURLAPPED	EACH	12				
* 02015401	Evergreen JUNIPERUS CHINENSIS 'KALLAY'S COMPACTA' (KALLAY COMPACT JUNIPER), 24" width, balled and burlapped	EACH	84				
* XX005856	MULCH - SHREDDED HARDWOOD BARK, 3" DEPTH	CU YD	40				
* XX006302	NEPETA X FAASSENII 'WALKERS LOW' (WALKERS LOW CATMINT)	EACH	1000				
* Z0013798	CONSTRUCTION LAYOUT	L SUM	1				
* XX007293	PERENNIAL, FALLOPIA JAPONICA 'COMPACTA' (COMPACT FLEECE FLOWER), 1 GALLON	EACH	3480				
* XX007294	PERENNIAL, MISCANTHUS SINENSIS 'PURPURASCENS' (PURPLE SILVER GRASS), 2 GALLON	EACH	40				

* SPECIAL PROVISION

* SEE SPECIAL PROVISIONS



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: As Noted
DATE: 01/04/08

DRAWN BY SLD
CHECKED BY JTP