

SUMMARY OF QUANTITIES

FAU RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7982	*	SANGAMON	114	7
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* 05-00447-01-PV		CITY OF SPRINGFIELD		

CODE NO.	ITEM DESCRIPTION	UNIT	URBAN	ROADWAY			LANDSCAPING	TRAFFIC SIGNALS
				TOTAL QUANTITY	CAPITOL AVENUE 05-00447-01-PV	J000-2A		
(S) 78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT		168		168		
(S) 78005180	EPOXY PAVEMENT MARKING - LINE 24"	FOOT		174		174		
78300100	PAVEMENT MARKING REMOVAL	SQ FT		64		64		
* 81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT		223				223
* 81012700	CONDUIT IN TRENCH, 2 1/2" DIA., PVC	FOOT		58				58
* 81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT		62				62
* 81021550	CONDUIT, AUGERED 2" DIA., PVC	FOOT		343				343
* 81021560	CONDUIT, AUGERED 2 1/2" DIA., PVC	FOOT		173				173
* 81021570	CONDUIT, AUGERED 3" DIA., PVC	FOOT		162				162
81400730	HANDHOLE, COMPOSITE CONCRETE	EACH		12				12
* 81900205	TRENCH AND BACKFILL FOR ELECTRICAL WORK (SPECIAL)	FOOT		350				350
84400105	RELOCATE EXISTING LIGHTING UNIT	EACH		1		1		
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT		395				395
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT		199				199
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT		1552				1552
* 87301265	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 9C	FOOT		1200				1200
* 87301275	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 12C	FOOT		130				130
* 87301815	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 3 C	FOOT		43				43
* 87501100	TRAFFIC SIGNAL POST, 15 FT.	EACH		6				6
* 87501200	TRAFFIC SIGNAL POST, 16 FT.	EACH		2				2
* 87701190	STEEL MAST ARM ASSEMBLY AND POLE, 30 FT. (SPECIAL)	EACH		1				1
* 87701200	STEEL MAST ARM ASSEMBLY AND POLE, 32 FT. (SPECIAL)	EACH		1				1
* 87701210	STEEL MAST ARM ASSEMBLY AND POLE, 34 FT. (SPECIAL)	EACH		1				1
* 87701220	STEEL MAST ARM ASSEMBLY AND POLE, 36 FT. (SPECIAL)	EACH		1				1
* 87704020	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 18 FT. (SPECIAL)	EACH		1				1
* 87704040	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 22 FT. (SPECIAL)	EACH		1				1

* PAY ITEM REQUIRES A SPECIAL PROVISION

(S) DENOTES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 FAU RTE 7982 CAPITOL AVE
 SEC NO. 05-00447-01-PV
 SANGAMON COUNTY, ILLINOIS
 VERT. SCALE: 09/19/07
 DRAWN BY TCJ
 CHECKED BY MH



LAYOUT TCJ 03/27/07
 DRAWN TCJ 03/27/07
 REVIEWED MH 11/30/07
 PLOT DATE = 01/18/2008, 11:23 AM
 FILE NAME = h:\r2\p2\05-00447-01-pv\mcr\station\sheet\section_1_74h-11th\c-004_500.dgn
 PLOT SCALE = 50.0000 / IN.
 USER NAME = Pop0805