

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7982	*	SANGAMON	114	13
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* 05-00447-01-PV		CITY OF SPRINGFIELD		

TREE REMOVAL AND PROTECTION SCHEDULE

LOCATION	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	TREE REMOVAL (OVER 15 UNITS DIAMETER)	TREE TRUNK PROTECTION	
				UNIT
BEGIN STATION	OFFSET	UNIT	UNIT	EACH
CAPITOL AVENUE 7TH STREET - 9TH STREET				
52+25.60	27.51 RT			1
52+55.11	27.54 RT			1
52+88.24	27.78 RT			1
53+21.37	27.77 RT			1
53+54.11	27.69 RT			1
53+76.61	31.32 RT			1
54+26.36	29.9 RT			1
54+59.35	29.05 RT			1
54+88.43	28.39 RT			1
55+22.78	28.83 RT			1
55+54.74	28.26 RT			1
55+80.59	28.61 RT			1
56+54.69	28.95 RT		20	
56+79.35	29.14 RT			1
57+11.82	28.88 RT	12		
SUBTOTAL		12	20	13
CAPITOL AVENUE/9TH STREET INTERSECTION				
58+57.62	32.85 RT	12		
SUBTOTAL		12		
CAPITOL AVENUE 9TH STREET - 11TH STREET				
58+77.88	32.14 RT	12		
59+82.60	31.6 RT	12		
59+62.25	32.21 RT		16	
60+16.75	27.6 RT		16	
SUBTOTAL		24	32	
TOTAL		48	52	13

MISCELLANEOUS REMOVAL SCHEDULE

LOCATION	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	REMOVE AND REINSTALL PARKING BLOCKS	WOODEN FENCE REMOVAL	PLANTER REMOVAL	FENCE REMOVAL		
							SQ YD	SQ YD
BEGIN STATION	END STATION	OFFSET	SQ YD	SQ YD	FOOT	FOOT	EACH	FOOT
CAPITOL AVENUE/7TH STREET INTERSECTION								
48+85.00	49+60.70	LT/RT		441				
49+78.82	50+28.10	RT	55					
49+79.03	50+29.11	LT	56					
SUBTOTAL			110	441				
CAPITOL AVENUE 7TH STREET - 9TH STREET								
52+12.00	53+64.59	RT			153			
	50+74.20	33.50' LT				1		
	51+02.80	33.41' LT				1		
	51+30.64	33.32' LT				1		
	51+58.66	33.52' LT				1		
	52+14.23	33.34' LT				1		
	52+42.45	33.44' LT				1		
	52+70.57	33.64' LT				1		
	52+98.79	33.27' LT				1		
SUBTOTAL					153		8	
CAPITOL AVENUE/9TH STREET INTERSECTION								
57+76.71	58+36.78	LT	67					
57+79.68	58+33.19	RT	59					
SUBTOTAL			126					
CAPITOL AVENUE 9TH STREET - 11TH STREET								
60+07.50	61+39.49	RT						135
62+48.32	63+88.01	RT						140
63+88.16	65+55.65	RT						168
65+55.65	65+55.86	RT						37
	60+54.00	RT			1			
	60+66.00	RT			1			
	60+78.00	RT			1			
	60+90.00	RT			1			
	61+02.00	RT			1			
	61+14.00	RT			1			
	61+26.00	RT			1			
	61+34.00	RT			1			
SUBTOTAL					8			480
CAPITOL AVENUE/11TH STREET INTERSECTION								
65+65.03	66+14.91	RT	55					
65+65.47	66+15.35	LT	55					
66+75.50	67+40.00	LT/RT		269				
SUBTOTAL			111	269				
TOTAL			347	710	8	153	8	480

TEMPORARY ACCESS AND FENCING SCHEDULE

LOCATION	AGGREGATE FOR TEMPORARY ACCESS	TEMPORARY SIDEWALK	TEMPORARY CONSTRUCTION FENCE	NOTE
BEGIN STATION	OFFSET	END STATION	OFFSET	
CAPITOL AVENUE 7TH STREET - 9TH STREET				
50+34.44	34.08 RT	51+78.52	34.06 RT	
50+34.44	50.00 RT	51+78.52	40.00 RT	
50+36.94	42.16 RT	50+36.94	36.58 RT	
50+36.94	40.00 RT	50+36.94	40.00 RT	
50+43.14	48.00 LT	53+28.37	48.00 RT	
50+63.47	40.00 LT	54+42.83	40.00 LT	
50+63.47	40.00 RT	54+42.83	40.00 RT	
53+38.18	40.00 LT	53+38.18	RT	49
53+46.18	8.00 LT	53+65.07	8.00 LT	23
53+58.59	40.00 LT	53+58.59	16.00 LT	30
54+55.63	40.00 LT	54+55.63	RT	49
54+63.64	16.00 LT	54+76.59	LT	16
54+76.59	16.00 LT	55+07.02	LT	37
54+96.09	40.00 LT	54+96.09	16.00 LT	30
55+15.01	40.00 LT	55+15.01	RT	49
56+37.46	20.00 LT	57+08.71	20.00 LT	220
57+09.47	35.81 LT	57+66.74	35.81 LT	
57+09.47	32.50 LT	57+66.74	32.50 LT	
SUBTOTAL				503
CAPITOL AVENUE 9TH STREET - 11TH STREET				
53+23.53	16.00 RT	63+42.63	RT	24
58+42.30	37.85 LT	61+97.46	37.54 LT	
58+42.30	35.00 LT	61+97.46	35.00 LT	
58+46.99	36.77 RT	61+97.45	37.08 RT	
58+46.99	35.00 RT	61+97.45	35.00 RT	
59+93.79	40.00 LT	59+93.79	RT	49
60+01.76	16.00 LT	60+29.95	LT	34
60+29.93	16.00 RT	60+32.57	RT	5
60+29.95	16.00 LT	60+54.56	LT	30
60+41.54	40.00 RT	60+41.54	RT	49
60+54.57	40.00 LT	61+35.05	RT	251
62+06.26	37.50 RT	63+27.41	37.52 RT	
62+06.26	35.00 RT	63+27.41	35.00 RT	
62+06.32	37.50 LT	63+27.47	37.48 LT	
62+06.32	35.00 LT	63+27.47	35.00 LT	
63+15.53	40.00 RT	63+15.53	RT	49
63+23.25	40.00 LT	63+23.25	RT	49
63+31.24	16.00 LT	63+42.63	LT	14
63+88.76	83.00 RT	65+54.62	83.00 RT	
64+78.41	37.25 LT	65+61.14	37.24 LT	
64+78.41	35.00 LT	65+61.14	35.00 LT	
SUBTOTAL				552
TOTAL				1055
				5210
				1221
				1886

STREETSCAPE SCHEDULE

LOCATION	MARKER FOOTINGS	STONE BENCH	METAL BENCH, 6" SECTION	TRASH RECEPTACLES	RECYCLING RECEPTACLES	PRECAST PLANTER EDGE TYPE 1	PRECAST PLANTER EDGE TYPE 2	CUSTOM FENCE STONE PIER FOOTINGS	CUSTOM PLANTER FOOTINGS	DECORATIVE STEEL RAILING	STREET LIGHT FOR INFORMATION ONLY	PEDESTRIAN LIGHT FOR INFORMATION ONLY	LIMESTONE EDGER
BEGIN STATION	END STATION	OFFSET	EACH	EACH	EACH	EACH	EACH	EACH	EACH	FOOT	EACH	EACH	FOOT
CAPITOL AVENUE 7TH STREET - 8TH STREET													
49+61.00	53+59.00		4	6		9	5		7	72	6	12	
SUBTOTAL			4	6		9	5		7	72	6	12	
CAPITOL AVENUE 8TH STREET - 9TH STREET													
53+59.00	57+57.00		4	22	6	3	3		2	72	4	14	68
SUBTOTAL			4	22	6	3	3		2	72	4	14	68
CAPITOL AVENUE 9TH STREET - 10TH STREET													
57+57.00	62+00.00		4	11	4	2	2	6	8	8	6	72	7
SUBTOTAL			4	11	4	2	2	6	8	8	6	72	7
CAPITOL AVENUE/10TH STREET - 11TH STREET													
62+00.00	66+38.00		6		4	2	2	9	4	12	7	7	
SUBTOTAL			6		4	2	2	9	4	12	7	7	
TOTAL			18	39	14	7	7	27	17	20	22	42	68

PAVER PAVEMENT SCHEDULE

LOCATION	CONCRETE PAVER PAVEMENT	CONCRETE PAVER SIDEWALK	DETECTABLE WARNINGS	PAVE-EDGE PAVER RETAINING SYSTEM		
					SQ YD	SQ YD
BEGIN STATION	END STATION	OFFSET	SQ YD	SQ YD	SQ FT	FOOT
CAPITOL AVENUE 7TH STREET - 8TH STREET						
49+61.00	53+59.00		1183.3	477.1	96	42.0
SUBTOTAL			1183.3	477.1	96	42.0
CAPITOL AVENUE 8TH STREET - 9TH STREET						
53+59.00	57+57.00		1326.3	229.0		56.0
SUBTOTAL			1326.3	229.0		56.0
CAPITOL AVENUE 9TH STREET - 10TH STREET						
57+57.00	62+00.00		1323.2	574.2	140	72.0
SUBTOTAL			1323.2	574.2	140	72.0
CAPITOL AVENUE/10TH STREET - 11TH STREET						
62+00.00	66+38.00		1274.3	528.6	140	88.0
SUBTOTAL			1274.3	528.6	140	88.0
TOTAL			5107.1	1808.9	376.0	258.0

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 FAU RTE 7982 CAPITOL AVE
 SEC NO. 05-00447-01-PV
 SANGAMON COUNTY, ILLINOIS
 SCALE: VERT. DRAWN BY TCJ
 HORIZ. CHECKED BY MH
 DATE 09/19/07



LAYOUT: TCJ 03/21/07
 DRAWN: TCJ 03/21/07
 REVIEWED: MH 11/30/07
 PLOT DATE = 01/19/2008 10:20 AM
 FILE NAME = s:\02_jobs\02-2004\aedddr\road\microstation\sheet\section_117\h-11th-C-985-SCHED.dgn
 PLOT SCALE = 50:000 / IN
 USER NAME = Pcp60636