

FAU RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7982		SANGAMON	114	14
STA.	TO STA.			
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
05-00447-01-PV		CITY OF SPRINGFIELD		

PAVEMENT MARKING SCHEDULE

LOCATION				TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	TEMPORARY PAVEMENT MARKING - LINE 4"	WORK ZONE PAVEMENT MARKING REMOVAL	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	EPOXY PAVEMENT MARKING - LINE 5"	EPOXY PAVEMENT MARKING - LINE 6"	EPOXY PAVEMENT MARKING - LINE 24"	PAVEMENT MARKING REMOVAL	NOTE	
BEGIN STATION	OFFSET	END STATION	OFFSET	SQ FT	FOOT	SQ FT	SQ FT	FOOT	FOOT	FOOT	SQ FT		
CAPITOL AVENUE/7TH STREET INTERSECTION													
48+85.00	RT	49+58.35	RT					147				DOUBLE YELLOW	
49+58.35	RT	49+58.35	15.00	RT						15		STOP BAR	
49+78.62	83.52	LT	49+85.70	78.06	LT						11	HANDICAPPED PARKING	
49+79.11	68.00	LT	49+85.65	107.00	LT	80	27		52			HANDICAPPED PARKING	
49+85.93	42.00	LT	50+21.91	42.00	LT	216	72			36		STOP BAR	
49+97.68	38.00	RT	49+97.54	78.00	RT	10	3	10				SKIP DASH	
49+97.96	44.00	LT	49+98.07	78.00	LT	9	3	9				SKIP DASH	
50+09.68	38.00	RT	50+09.54	78.00	RT	10	3	10				SKIP DASH	
50+09.96	44.00	LT	50+10.07	78.00	LT	9	3	9				SKIP DASH	
50+19.81	109.65	LT	50+21.27	108.49	LT						2	PARKING	
50+19.82	68.00	LT	50+29.16	108.50	LT	99	33		60			HANDICAPPED PARKING	
50+20.74	154.58	LT	50+28.73	177.88	LT						36	HANDICAPPED PARKING	
SUBTOTAL						432	144		184	112	51	48	
CAPITOL AVENUE/9TH STREET INTERSECTION													
57+77.94	41.00	LT	58+12.70	41.00	LT	210	70			35		STOP BAR	
57+88.71	41.00	LT	57+88.72	55.00	LT	4	1	4				SKIP DASH	
57+90.70	38.00	RT	57+90.68	55.00	RT	4	1	4				SKIP DASH	
58+00.71	41.00	LT	58+00.72	55.00	LT	14	5		14			TURN LANE	
58+01.70	41.00	RT	58+01.68	55.00	RT	28	9	28				DOUBLE YELLOW	
58+01.71	41.00	RT	58+31.80	41.00	RT	180	60			30		STOP BAR	
58+11.14	41.00	RT	58+11.19	55.00	RT	14	5		14			TURN LANE	
58+12.71	41.00	LT	58+12.72	55.00	LT	28	9	28				DOUBLE YELLOW	
58+22.14	41.00	RT	58+22.19	55.00	RT	4	1	4				SKIP DASH	
58+24.71	38.00	LT	58+24.71	55.00	LT	4	1	4				SKIP DASH	
SUBTOTAL						490	163		72	28	65		
CAPITOL AVENUE/11TH STREET INTERSECTION													
65+66.71	41.00	LT	65+95.52	41.00	LT	174	58			29		STOP BAR	
65+75.18	36.43	RT	65+75.16	55.00	RT	4	1	5				SKIP DASH	
65+75.49	41.00	LT	65+75.43	55.00	LT	5	2	4				SKIP DASH	
65+85.17	41.00	RT	65+85.16	55.00	RT	28	9	28				DOUBLE YELLOW	
65+85.18	41.00	RT	65+13.95	41.00	RT	174	58			29		STOP BAR	
65+85.49	41.00	LT	65+85.43	55.00	LT	14	5		14			TURN LANE	
65+87.09	59.78	LT	65+87.09	55.86	LT						8	LEFT TURN ARROW	
65+89.46	59.00	LT				8		8				LEFT TURN ARROW	
65+91.49	59.39	RT				8		8				LEFT TURN ARROW	
65+92.63	59.07	RT	65+92.63	55.15	RT						8	LEFT TURN ARROW	
65+95.17	41.00	RT	65+95.16	55.00	RT	14	5		14			TURN LANE	
65+95.49	41.00	LT	65+95.43	55.00	LT	28	9	28				DOUBLE YELLOW	
66+05.17	41.00	RT	66+05.16	55.00	RT	5	2	4				SKIP DASH	
66+05.50	36.55	LT	66+05.44	55.00	LT	4	1	5				SKIP DASH	
66+75.50		RT	67+40.00		RT			16				SKIP DASH	
SUBTOTAL						16	448	166	16	88	58	16	
TOTAL						16	1370	473	16	344	168	174	64

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF QUANTITIES FAU RTE 7982 CAPITOL AVE SEC NO. 05-00447-01-PV SANGAMON COUNTY, ILLINOIS SCALE: VERT. / HORIZ. DATE 09/19/07	DRAWN BY TCJ CHECKED BY MH
NAME	DATE		



LAYOUT TCJ 03/27/07
 DRAWN TCJ 03/27/07
 REVIEWED MH 11/20/07
 PLOT DATE = 01/18/2008 10:20 AM
 FILE NAME = H:\2008\05-00447-01-PV\microstation\sheet\section.L7-11th-11th-005-SCHED.dgn
 PLOT SCALE = 50.0000 / IN.
 USER NAME = Pops0636

Copyright Hanson Professional Services Inc. 2008