

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7982	*	SANGAMON	114	16
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* 05-00447-01-PV		CITY OF SPRINGFIELD		

DRAINAGE STRUCTURE SCHEDULE

LOCATION								INLETS			FRAMES AND GRATES		CATCH BASIN SPECIAL	CATCH BASINS (CIRCULAR), SPECIAL WITH SPECIAL FRAME AND GRATE	MANHOLES, TYPE A, 4-DIAMETER		MANHOLES, TYPE A, 5-DIAMETER TYPE 1 FRAME, CLOSED LID	TRENCH DRAIN	INLET FILTERS
								ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	TYPE A, WITH SPECIAL FRAME AND GRATE	TYPE A, SALVAGED FRAME AND GRATE	REMOVE, SALVAGE AND REPLACE	TYPE 9			TYPE 1 FRAME, CLOSED LID	SPECIAL FRAME AND GRATE			
STR	STATION	OFFSET	RIM ELEV	N INVERT ELEV	S INVERT ELEV	E INVERT ELEV	W INVERT ELEV	EACH	EACH	EACH	EACH	EACH	EACH	EACH	FOOT	EACH			
7TH ST. INTERSECTION																			
S-70	49+84.49	50.01' LT	594.70		591.35								1			1			
S-71	50+23.49	49.18' LT	594.53		592.23	592.50							1			1			
S-72	50+28.93	49.54' LT	595.12				592.60	1											
SUBTOTAL								1				2				2			
MIDBLOCK OF 7TH ST. AND 9TH ST.																			
S-81	50+50.00	16.50' LT	594.96	591.75								1				1			
S-82	50+50.00	16.50' RT	595.03		590.26				1		1					1			
S-83	53+15.82	26.63' LT	595.83		593.00			1											
S-84	53+20.40	16.50' LT	595.32	592.91		592.81				1						1			
S-85	53+48.46	16.00' LT	594.92		592.45	592.55					1					1			
S-86	53+72.93	16.50' LT	594.70		592.13	592.23					1					1			
S-87	53+52.99	23.06' RT	595.65	592.35	587.67			1											
S-88	53+52.85	16.50' RT	594.93		592.39						1					1			
S-89	53+89.02	16.50' RT	594.71			590.28				1						1			
S-90	54+07.13	16.50' LT	594.62	589.56	589.66		589.89					1				1			
S-91	54+07.13	16.00' RT	594.68	589.98			589.68			1	1					1			
S-92	54+57.11	16.50' RT	594.91		592.29				1		1					1			
S-93	54+56.82	23.11' RT	595.51	592.25	588.55	589.45		1											
S-94	55+53.17	16.00' LT	595.58	589.40						1	1					1			
SUBTOTAL								3	2	1	2	2	4	3		1	11		
9TH ST. INTERSECTION																			
S-100	57+48.71	16.50' LT	595.10	591.13								1				1			
S-101	57+48.71	16.50' RT	594.98		589.86				1		1					1			
S-102	58+55.86	18.15' LT	595.49	592.04			590.19				1					1			
S-103	58+56.17	16.98' RT	595.44		591.62		588.71			1	1					1			
SUBTOTAL											2	2	2			4			
MIDBLOCK OF 9TH ST. AND 11TH ST.																			
S-110	60+64.71	16.00' LT	598.22		596.20					1	1					1			
S-111	60+67.09	16.00' RT	598.21	594.00						1	1					1			
S-112	63+75.51	16.50' LT	598.27		595.29						1					1			
S-113	63+75.51	3.46' LT	598.65	595.10	595.10	592.43						1							
S-114	63+75.51	16.50' RT	598.27	595.29							1					1			
S-115	61+39.61	39.00' RT	599.26	597.26										12		1			
S-116	65+26.27	16.50' LT	597.77		594.40						1					1			
S-117	65+26.27	3.45' LT	598.09	594.21	594.21	591.54	591.64					1				1			
S-118	65+26.27	16.50' RT	597.77	594.40								1				1			
SUBTOTAL											2	2	4	2		12	7		
11TH ST. INTERSECTION																			
S-120	65+90.17	3.45' LT	598.71	590.29	590.29 SE - 594.65	591.25	591.29									1			
S-133	66+64.69	16.50' LT	597.69		594.70							1				1			
S-134	66+64.69	16.50' RT	597.69	594.36			594.26					1				1			
SUBTOTAL								1					1			2			
TOTAL								4	3	1	4	4	8	12	2	1	1	12	26

STRUCTURE REMOVAL SCHEDULE

LOCATION		REMOVING INLETS	REMOVING MANHOLES	TRENCH BACKFILL
STATION	OFFSET	EACH	EACH	CU YD
7TH ST. INTERSECTION				
49+78.72	50.08' LT	1		1.9
SUBTOTAL		1		1.9
MIDBLOCK OF 7TH ST. AND 9TH ST.				
50+47.25	26.82' LT	1		1.9
50+54.64	23.32' RT	1		1.9
53+50.17	24.22' LT	1		1.9
53+63.79	26.30' RT	1		1.9
54+56.82	23.11' RT	1		1.9
55+36.72	26.96' LT	1		1.9
SUBTOTAL		6		11.4
9TH ST. INTERSECTION				
57+52.01	26.88' LT	1		1.9
57+57.16	23.10' RT	1		1.9
58+55.65	23.80' LT	1		1.9
58+56.14	22.71' RT	1		1.9
SUBTOTAL		4		7.6
MIDBLOCK OF 9TH ST. AND 11TH ST.				
60+63.79	24.14' LT	1		1.9
60+67.32	22.24' RT	1		1.9
63+11.11	21.56' LT		1	4.4
63+80.40	20.35' LT		1	4.4
63+85.57	27.48' RT		1	4.4
SUBTOTAL		2	3	17.0
11TH ST. INTERSECTION				
65+44.39	15.03' LT	1		1.9
65+44.25	15.36' RT	1		1.9
65+90.17	3.45' LT		1	4.4
66+34.37	17.82' RT	1		1.9
66+32.64	18.16' RT	1		1.9
SUBTOTAL		4	1	12.0
TOTAL		17	4	99.8

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 FAU RTE 7982 CAPITOL AVE
 SEC NO. 05-00447-01-PV
 SANGAMON COUNTY, ILLINOIS
 SCALE: VERT. / HORIZ.
 DATE 09/19/07
 DRAWN BY TCJ
 CHECKED BY MH



LAYOUT TCJ 03/27/07
 DRAWN TCJ 03/27/07
 REVIEWED MH 11/30/07
 PLOT DATE = 09/19/07 10:20 AM
 FILE NAME = I:\2005\05-00447-01-PV\road\mcor\station\sheet\section.L7-11\FAU-005_SCH.DWG
 PLOT SCALE = 3/8" = 1'-0"
 USER NAME = Pop20056

© Copyright Hanson Professional Services Inc. 2008