

RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
C.H. 17	*	MONTGOMERY	41	6

PROJECT \* 07-00125-01-RS

**HOT MIX ASPHALT SCHEDULE**

LOCATION	TEMPORARY RAMP (SQ. YD.)	AGGREGATE PRIME COAT (TON)	HOT MIX ASPHALT SURFACE COURSE, MIX "D", N70 (TON)	HOT MIX ASPHALT BINDER COURSE, IL-19.0 N70 (TON)	BITUMINOUS MATERIALS (PRIME COAT) (TON)	HOT MIX ASPHALT SHOULDERS (TON)	LEVELING BINDER MACHINE METHOD (TON)
STA. 22+40 TO STA. 22+80		0.21	9		0.04	10	6
STA. 22+80 TO STA. 24+06		1.11	22		0.21	34	28
STA. 24+06 TO STA. 31+56.35		7.00	168		0.03	351	252
STA. 31+56.35 TO STA. 33+92		2.20	53		0.41	108	105
STA. 33+92 TO STA. 34+50		0.41	73		0.08	28	24
STA. 34+50 TO STA. 39+54.5		7.40	86		1.41	309	318
STA. 39+54.5 TO STA. 48+45.3		10.11	262		1.92	491	569
STA. 51+46 TO STA. 67+00		15.31	492		2.91	421	277
STA. 67+00 TO STA. 67+82		0.60	16		0.11	20	23
STA. 67+82 TO STA. 68+55		0.52	18		0.10	31	77
STA. 68+55 TO STA. 72+74.3		2.23	94		0.42	19	362
REMOVED MEDIAN AREA (STA. 35+89 TO STA. 38+78)		1.10	47		0.21		
C.E. STA. 22+95 LT.			6				1
C.E. STA. 23+09 RT.		0.14	6	34	0.03		
C.E. STA. 23+17.5 RT.	19		3				1
STA. 23+82.5 RT. NEWTON ST.	21		4				1
STA. 25+29 LT. NEWTON ST.	22		4				1
STA. 27+58 LT. & RT. CLEVELAND ST.	56		11				2
STA. 31+90 LT. & RT. EAST ST.	47		9				2
STA. 35+51.50 RT. SEDENTOP RD.	19		2				1
STA. 35+89 TO STA. 38+78				263			
STA. 39+01 LT. & RT. FRONTAGE RD.	123		27				26
I-55 SOUTHBOUND RAMPS	87		15				29
I-55 NORTHBOUND RAMPS	110		31				28
STA. 62+00 & 63+08 LT. FRONTAGE RD.	92		12				0
STA. 63+15 RT. MINE RD.	82		10				0
<b>TOTAL</b>	<b>678</b>	<b>48.34</b>	<b>1418</b>	<b>297</b>	<b>7.86</b>	<b>1822</b>	<b>2133</b>

**SCHEDULE PERMANENT SEEDING**

LOCATION	SEEDING CLASS 2 (SPECIAL) (ACRE)	NITROGEN FERT. NUT. (POUND)	PHOSPHORUS FERT. NUT. (POUND)	POTASSIUM FERT. NUT. (POUND)	MULCH METHOD 2 (ACRE)	AGRICULTURAL GROUND LIMESTONE (TON)
MEDIAN & DISTURBED AREAS	0.4	**36	**36	**36	**0.8	**0.8
<b>TOTAL</b>						

\*\* - THESE QUANTITIES ARE INCLUDED IN THE CONTRACT UNIT PRICE FOR SEEDING CLASS 2 (SPECIAL).

**EARTHWORK SCHEDULE**

LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD
STA. 22+40 TO STA. 48+45.3	0	0	65	-65
STA. 51+46 TO STA. 72+74.3	0	0	162	-162
TURF MEDIAN	0	0	320	-320
<b>TOTAL</b>	<b>0</b>	<b>0</b>	<b>547</b>	<b>-547</b>

**SCHEDULE INLETS TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME OPEN LID**

LOCATION	QUANTITY (EACH)
STA. 36+58	1
<b>TOTAL</b>	<b>1</b>

**SCHEDULE INLETS, TYPE A, TYPE 1 FRAME OPEN LID**

LOCATION	QUANTITY (EACH)
STA. 38+15	1
<b>TOTAL</b>	<b>1</b>

**SCHEDULE INLETS, TYPE A, TYPE 1 FRAME CLOSED LID**

LOCATION	QUANTITY (EACH)
STA. 40+00	1
STA. 41+50	1
STA. 47+00	1
<b>TOTAL</b>	<b>3</b>

**SCHEDULE INLETS TO BE RECONSTRUCTED WITH NEW TYPE 15 FRAME & LID**

LOCATION	QUANTITY (EACH)
STA. 47+00	1
STA. 55+73	1
<b>TOTAL</b>	<b>2</b>

**SCHEDULE PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT**

LOCATION	QUANTITY (SQ. YD.)
I-55 SOUTHBOUND RAMP	97
I-55 NORTHBOUND RAMP	76
<b>TOTAL</b>	<b>173</b>

**SCHEDULE REMOVING AND RE-ERECTING EXISTING GUARDRAIL**

LOCATION	QUANTITY (FOOT)
STA. 38+12 TO STA. 38+37	25
<b>TOTAL</b>	<b>25</b>

**SCHEDULE PAVED SHOULDER REMOVAL**

LOCATION	QUANTITY (SQ. YD.)
STA. 34+50 TO STA. 38+72.1 RT.	188
STA. 34+50 TO STA. 38+61.3 LT.	183
STA. 39+80.2 TO STA. 48+30 RT.	378
STA. 39+74.8 TO STA. 44+18.1 LT.	197
STA. 46+12.3 TO STA. 48+56 LT.	108
STA. 51+45.7 TO STA. 58+00 RT.	291
STA. 51+48.2 TO STA. 55+30.7 LT.	170
STA. 56+99 TO STA. 58+00 LT.	45
<b>TOTAL</b>	<b>1560</b>

**SCHEDULE COMBINATION CURB AND GUTTER REMOVAL & CONCRETE MEDIAN SURFACE REMOVAL**

LOCATION	CURB & GUTTER REM. QUANTITY (FOOT)	CONC. MED. SURF. REM. QUANTITY (SQ. FT.)
STA. 35+89 TO STA. 38+78	590	3513
STA. 39+45 TO STA. 44+95	1106	4558
STA. 45+61.5 TO STA. 48+45.3	576	3967
STA. 51+46 TO STA. 55+00	707	2530
STA. 55+00 TO STA. 55+99	202	338
<b>TOTAL</b>	<b>3181</b>	<b>14906</b>

**SCHEDULE FRAME AND LIDS TO BE ADJUSTED**

LOCATION	QUANTITY (EACH)
STA. 23+78 18' LT. WATER	1
STA. 25+40 18' LT. MANHOLE	1
STA. 25+46 21' LT. GAS	1
STA. 28+94 14' LT. MANHOLE	1
STA. 31+16 14' LT. MANHOLE	1
STA. 31+68 18' LT. GAS	1
STA. 31+68 16' RT. GAS	1
STA. 32+10 19' LT. GAS	1
STA. 32+21 19' RT. GAS	1
<b>TOTAL</b>	<b>9</b>

QUANTITY SCHEDULES  
F.A.S. 732 (C.H. 17)  
(FARMERSVILLE OVERPASS)  
SECTION 07-00125-01-RS  
MONTGOMERY COUNTY

FILE NAME: M00125-S0 (REV. 2/14/03)