

RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
C.H. 17	*	MONTGOMERY	41	7

PROJECT * 07-00125-01-RS

**SCHEDULE
CLASS B PATCHES (SPECIAL)
SAW CUTS AND TIE BARS**

LOCATION	PATCHING QUANTITY (SQ. YD.)	SAW CUTS QUANTITY (FOOT)	TIE BARS QUANTITY (EACH)
STA. 38+25 LT.	3	32	24
STA. 38+25 RT.	3	32	24
STA. 39+45 TO STA. 39+54 MEDIAN AREA	12	**	44
STA. 41+50 LT.	3	32	24
STA. 41+50 RT.	4	36	28
STA. 45+20 RT.	10	98	88
STA. 55+00 LT.	3	32	24
STA. 55+00 RT.	6	52	44
TOTAL	44	314	300

** QUANTITY INCLUDED IN COMBINATION CURB AND GUTTER REMOVAL (SPECIAL)

**SCHEDULE
AGGREGATE SHOULDERS TYPE B**

LOCATION	QUANTITY (TON)
P.E. STA. 22+61 RT.	2
STA. 58+00 TO STA. 72+74.3	302
F.E. STA. 70+13 LT.	18
TOTAL	322

**SCHEDULE
PIPE UNDERDRAINS 4" (SPECIAL)**

LOCATION	QUANTITY (FOOT)
STA. 40+00	21
STA. 38+25 1' LT. TO 47' LT.	46
STA. 38+25 1' RT. TO 43' RT.	42
STA. 41+50 1' LT. TO 47' LT.	46
STA. 41+50 1' RT. TO 47' RT.	46
STA. 40+01 TO STA. 41+49	148
STA. 41+51 TO STA. 44+81	330
STA. 45+20 21' LT. TO 49' RT.	70
STA. 45+83 TO STA. 46+99	116
STA. 47+01 TO STA. 48+45	144
STA. 51+49 TO STA. 54+99	350
STA. 55+00 4' LT. TO 44' LT.	40
STA. 55+00 2' RT. TO 48' RT.	46
STA. 55+01 TO STA. 55+81	80
TOTAL	1525

**SCHEDULE
CONCRETE HEADWALL FOR PIPE DRAINS**

LOCATION	QUANTITY (EACH)
STA. 38+25 47' LT.	1
STA. 38+25 43' RT.	1
STA. 45+20 49' RT.	1
STA. 55+00 44' LT.	1
STA. 55+00 48' RT.	1
TOTAL	5

**SCHEDULE
COMBINATION CONCRETE CURB AND GUTTER
TYPE M6.06 (SPECIAL)**

LOCATION	QUANTITY (CU. YD.)
STA. 39+54 TO STA. 44+95	1097
STA. 45+61.5 TO STA. 48+45.3	576
STA. 51+46 TO STA. 55+00	707
STA. 55+00 TO STA. 55+99	202
TOTAL	2582

**SCHEDULE
CLASS D PATCHES 10"**

LOCATION	TYPE II QUANTITY (SQ. YD.)	TYPE III QUANTITY (SQ. YD.)
STA. 25+61 TO STA. 25+76	10	
STA. 26+89 TO STA. 27+07		19
TOTAL	10	19

PAVEMENT MARKING SCHEDULE

LOCATION	LENGTH (FT.)	SHORT TERM PVMT. MARKING		PAINT PVMT. MK. LINE - 4"		PAINT PVMT. MK. LINE - 12"		PAINT PVMT. MK. LINE - 24"		PAINT PVMT. MK. LETTERS AND SYMBOLS	
		WHITE (FT.)	YELLOW (FT.)	WHITE (FT.)	YELLOW NO PASSING (FT.)	WHITE (FT.)	YELLOW (FT.)	WHITE (FT.)	YELLOW (FT.)	WHITE (FT.)	YELLOW (FT.)
STA. 22+40 TO STA. 48+30 RT. (EDGE)	2590			2319							
STA. 22+40 TO STA. 48+56 LT. (EDGE)	2616			2371							
STA. 42+50 TO STA. 45+00 TURN LANE	250			250							
STA. 51+46 TO STA. 72+70 RT. (EDGE)	2124			1976							
STA. 51+48 TO STA. 72+85 LT. (EDGE)	2137			1618							
STA. 52+50 TO STA. 55+00 TURN LANE	250			250							
STA. 22+40 TO STA. 48+45.3											
DOUBLE YELLOW AND MEDIAN EDGE	2605				4920						
INSIDE PAINTED MEDIAN - STA. 35+89 TO STA. 38+78							268				
STA. 51+46 TO STA. 72+74.3	2128				4153						
STA. 22+40 TO STA. 72+74.3	4733.6	*878									
STA. 22+55 LT.	12							24			
STA. 23+05 LT.	12							24			
STA. 23+55 LT.	12							24			
STA. 27+22 CLEVELAND ST. PEDESTRIAN CROSSING	40							80			
STA. 27+28 CLEVELAND ST. PEDESTRIAN CROSSING	40							80			
STA. 22+75 C R.R. SYMBOLS								48		63	
SUB - TOTAL		878		8784	9073		268	280		63	
TOTAL		878			17857		268	280		63	

NOTE: SHORT-TERM PAVEMENT MARKING QUANTITIES ARE FOR TWO APPLICATIONS. SIDEROADS AND RAMPS DO NOT HAVE EDGE LINES APPLIED ACROSS THEM.
* 10% OF TOTAL LENGTH FOR SHORT-TERM PAVEMENT MARKING

**SCHEDULE
HOT MIX ASPHALT SURFACE REMOVAL - BUTT JOINT**

LOCATION	QUANTITY (SQ. YD.)
STA. 22+40 (PROJECT BEGINS)	81
C.E. STA. 22+45 LT.	31
C.E. STA. 23+17.5 RT.	47
STA. 23+82.5 RT. NEWTON ST.	21
STA. 25+29 LT. NEWTON ST.	22
STA. 27+58 LT. & RT. CLEVELAND ST.	67
STA. 31+90 LT. & RT. EAST ST.	47
STA. 35+51.5 RT. SEDENTOP RD.	28
STA. 39+01 LT. & RT. FRONTAGE RD.	87
STA. 47+70.3 TO STA. 48+45.3	111
STA. 51+46 TO STA. 52+19.8	141
STA. 62+00 & STA. 63+08 LT. FRONTAGE RD.	231
STA. 63+15 RT. MINE RD.	171
STA. 72+74.36 (PROJECT ENDS)	92
TOTAL	1222

**SCHEDULE
HOT MIX ASPHALT BASE COURSE WIDENING 8"**

LOCATION	QUANTITY (SQ. YD.)
STA. 34+50 TO STA. 38+63.1 RT.	459
STA. 34+50 TO STA. 38+72.1 LT.	469
STA. 39+80.2 TO STA. 48+30 RT.	944
STA. 39+74.8 TO STA. 44+18.1 LT.	619
STA. 51+45.7 TO STA. 58+00 RT.	727
STA. 51+48.2 TO STA. 55+30.7 LT.	425
STA. 46+12.3 TO STA. 48+56 LT.	271
STA. 56+99 TO STA. 58+00 LT.	112
TOTAL	4026

**SCHEDULE
SUB-BASE GRANULAR MATERIAL TYPE A 4"**

LOCATION	QUANTITY (CU. YD.)
STA. 35+89 TO STA. 38+78	61
TOTAL	61

**SCHEDULE
PORTLAND CEMENT CONCRETE SIDEWALK 4"**

LOCATION	QUANTITY (SQ. FT.)
STA. 22+40 TO STA. 22+96 RT.	262
STA. 23+31 TO STA. 23+62 RT.	124
TOTAL	386

**SCHEDULE
HOT MIX ASPHALT SURFACE REMOVAL 3"**

LOCATION	QUANTITY (SQ. YD.)
STA. 23+99 TO STA. 31+78 RT.	609
STA. 23+56 TO STA. 31+78 LT.	597
TOTAL	1206

**SCHEDULE
STORM SEWERS, CLASS A, TYPE 1 8"**

LOCATION	QUANTITY (FOOT)
STA. 36+58 TO STA. 38+14	156
TOTAL	156

QUANTITY SCHEDULES
F.A.S. 732 (C.H. 17)
(FARMERSVILLE OVERPASS)
SECTION 07-00125-01-RS
MONTGOMERY COUNTY