

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	**	MACON	106	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
** 05-00525-00SW				

SUMMARY OF QUANTITIES

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CITY OF DECATUR	MILLIKIN UNIVERSITY
60600705	CONCRETE CURB, TYPE B (ABUTTING EXISTING PAVEMENT)	FOOT	56	56	
60603900	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (ABUTTING EXISTING PAVEMENT)	FOOT	11	11	
60604500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18 (ABUTTING EXISTING PAVEMENT)	FOOT	1642	1642	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1331	1331	
60605100	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (ABUTTING EXISTING PAVEMENT)	FOOT	738	738	
60606900	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.18 (ABUTTING EXISTING PAVEMENT)	FOOT	120	120	
60608700	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06 (ABUTTING EXISTING PAVEMENT)	FOOT	173	173	
60624600	CORRUGATED MEDIAN	SQ FT	610	610	
67100100	MOBILIZATION	L SUM	1	1	
70101900	TRAFFIC CONTROL AND PROTECTION (DETOUR 1)	L SUM	1	1	
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
70106201	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606, LOCATION 1	L SUM	1	1	
70106202	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606, LOCATION 2	L SUM	1	1	
70106203	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606, LOCATION 3	L SUM	1	1	
70106311	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602, LOCATION 1	L SUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	5098	5098	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	18	18	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	5098	5098	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	118	118	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	900	900	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	45	45	
XX007317	INSTALL EXISTING SIGN PANEL	EACH	8	8	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	18	18	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	5098	5098	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	118	118	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	900	900	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	45	45	
* 78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	53	53	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2736	2736	
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	270	270	
* 78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	608	608	

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CITY OF DECATUR	MILLIKIN UNIVERSITY
* 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	125	125	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	725	725	
* 81000500	CONDUIT IN TRENCH, 1 1/2" DIA., GALVANIZED STEEL	FOOT	16	16	
* 81012400	CONDUIT IN TRENCH, 1 1/4" DIA., PVC	FOOT	2340	2340	
* 81021320	CONDUIT PUSHED, 1 1/2" DIA., PVC	FOOT	90	90	
* 81400115	HANDHOLE TO BE ADJUSTED	EACH	5	5	
* 81500100	GULFBOX JUNCTION	EACH	7	7	
* 81500130	GULFBOX JUNCTION REMOVAL	EACH	1	1	
* 81702100	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 12	FOOT	66	66	
* 81702120	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 8	FOOT	4917	4917	
* 81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	10780	10780	
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	2171	2171	
* 83600400	POLE FOUNDATION, METAL	EACH	26	26	
* 83600120	LIGHT POLE FOUNDATION, SPECIAL	FOOT	144	144	
* 84200700	LIGHTING FOUNDATION REMOVAL	EACH	26	26	
* 84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	26	26	
* 85100100	PAINT EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	2	2	
* 87301515	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 18 3 PAIR	FOOT	206	206	
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1040	1040	

* SPECIALTY ITEMS

REV. NO.	DESCRIPTION	BY	DATE	APPROVED
SUMMARY OF QUANTITIES				
DESIGN BWC	WEST MAIN STREET PHASE II CITY OF DECATUR			SCALE
DATE				BWC PROJECT NO. 009-0605
DRAWN	BWC BLANK, WESSELINK, COOK & ASSOCIATES, INC.			DATE
DATE				SHEET 2 OF 3
CHECKED	ARCHITECTS ENGINEERS			
APPROVED	2623 EAST PERSHING ROAD, DECATUR, IL 62524 (217) 428-0973 FAX (217) 428-8934			
DATE				